



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Lakhnaur

Estimate for Mortable of the Road from L022 - L021 REO
ROAD TO JAGDAR (VR022) Back FDR at Block- Lakhnaur
in Madhubani District.

TOTAL COST FOR MOTORABLE Rs. ~~6.52440~~ lac.

2.45716 lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Laxmanpur

Name of Road :- Laxmanpur Road To Jagadpur

A. For Road

1. Damage Location Chainage :- 0-200, 700-900, 1200-1500
2. Damage Length :- 127.5 M
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Portland Cement
 - ii. Equipment's/Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- 103.73 m
 - iv. Restored Length:- 127.5 M

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- L022-L021 REO Road To Jagdar (VR 022)

प्राक्कलित राशि :- 6.52440 2.45716 lac

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक L022-L021 REO Road To Jagdar (VR 022) पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

**Estimate for Motorability of road damaged by flood from L022 - L021 REO ROAD TO JAGDAR
(VR022) For Year 2021**

Head :- FDR 2245

Length :- 1.56 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	275.07 103.73	2004.96	2 07 974.50 551504.35

2 07 974.50
 ₹ 5,51,504.35
 24956.94
 Add 12 % GST ₹ 66,180.52
 2079.75
 Add 1 % L.C ₹ 5,515.04
 103.73
 Add S. Fee (275.07 x 1063.00) x 10 % ₹ 10704.94
 29,239.94
 1032
 Total ₹ 245716.13
 6,52,439.85
 Say ₹ 6,52,440.00
 2,45,716.00



 Junior Engineer
 R.W.D, Works Section,
 Lakhnaur

Assistant Engineer
 R.W.D, Work sub Div.
 Lakhnaur


 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur

कै. वि. पालक अभियंता, मा. का. वि., जयनगर
 जयपुरांत चक्रांक 6.7.8 के द्वारा दिनांक 4/5/22
 के आधार पर

Technically Sanctioned for Rs. 245716.00 (Rupees two lakh
 forty five thousand Seven hundred sixteen only)
 Only


 Superintending Engineer
 RWD work Circle, Darbhanga

Name of Road :- L022 - L021 REO ROAD TO JAGDAR (VR022)

me :- PMGSY Length :- 1.560 km Block :- Lakhnaur

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)

Chainage	Nos.		Length (In Mtr.)		Bldth (In Mtr.)		Thickness (In Mtr.)				Quantity	
ch. 0 to 200 m	X 1	x	8.00	x	1.80	x	1.80	0.75	0.75	av.	=	10.80
	1	x	7.00	x	0.30	x	0.30	0.80	0.30	av.	=	6.63
ch. 700 to 900 m	X 1	x	24.00	x	2.10	x	2.10	0.65	0.65	av.	=	32.76
	1	x	30.00	x	2.30	x	3.30	0.60	0.50	av.	=	14.83
	1	x	10.00	x	3.30	x	3.30	0.75	0.4	av.	=	12.81
	1	x	18.50	x	3.60	x	3.60	0.80	0.50	av.	=	33.30
ch. 1200 to 1500 m	1	x	30.00	x	1.10	x	1.10	0.7	0.30	av.	=	42.90
Total qty.											=	275.07

103.73 m³

28/11/22

Junior Engineer
R.W.D, Works Section,
Lakhnaur

Assistant Engineer
R.W.D, Work sub Div.
Lakhnaur

28/04/2022
J.E

28/04/22
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

28/04/2022
J.E

28/04/2022
AE

28/4