



बिहार सरकार
ग्रामीण कार्य विभाग
Rural Works Department, Govt. of Bihar

159

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Nawani Muswa Pakar
Gachhi To Sirkhariya Road FDR at Block- Jhanjharpur in
Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~2.41435 lac~~

~~3.6111 lac.~~

2.41121 lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- नवानी मुखवा पक्कड़ गावडी से सिरखरिया पर

प्राक्कलित राशि :- 361111=00 ~~241111=00~~ 2.41121 292

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक नवानी मुखवा पक्कड़

गावडी से सिरखरिया पर पथ के लिए तैयार किया गया है, जो

कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- Nawani Mulwa Pakar Gachhi to Srikhanya road

A. For Road

1. Damage Location Chainage :- 300m, 550m, 600m, 800m

2. Damage Length :- 127.5m

3. Nature of Damage :-

4. Details of Restoration Works

i. Materials being used in restoration works:- Brick-bats

ii. Equipment's/Tools being used in Restoration works:- Tractor - Tolly

iii. Procedure taken up in Restoration works:- 101.79m

iv. Restored Length:- 127.5m

B. For Bridge

1. Damage Location Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Materials being used in restoration works:-

ii. Equipment's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-


C. Requirement Of New CD/ Bridges


i. Name of Road:-

ii. Location/ Chainage:-

iii. Type of CD Work/ Length required:-

"S"


28/04/22
Signature of JE/AE/EE


22/4/22
RR


Signature
(Name of Inspection)

Rate for Motorability of road damaged by flood from Nawani Muswa Pakar Gachhi To Sirkhariya Road For Year 2021

MMGSY[SC]

Length :- 3.45 km

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
	Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	152.25 101.79	2004.96	305245.14 204084.88

204084.88
 ₹ 3,05,245.14
 Add 12 % GST ₹ 36,629.42
 Add 1 % L.C ₹ 3,052.45
 Add S. Fee (152.25 x 1063.00) x 10 % ₹ 16,183.64
 Total ₹ 3,61,110.65
 Say ₹ 3,61,111.00
 241121

Junior Engineer

R.W.D, Works Section,
Jhanjharpur

Assistant Engineer

R.W.D, Work sub Div.
Jhanjharpur

Executive Engineer

R.W.D (W) Division,
Jhanjharpur

काग्रेसीक अग्रीमंता, छां का वि, जगनगर के द्वारा जॉनोपरां
 सि पतांक - 671 (अड) रिनांक - 29/04/22 के आवार पर
 Technically Sanctioned for Rs - 241121.00 (Rupees two
 lakh fourty One thousands One hundred twenty One) Only

Superintending Engineer
RWD Work Circle, Darbhanga

Abhinav
05/05/22

Name of Road :- Nawani Muswa Pakar Gachhi ToSirkhariya

MR

Length :- 3.45 km

Block :- Jhanjharpur

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (In Mtr.)		Bldth (In Mtr.)		Thickness (In Mtr.)				Quantity	
H. 300M	1	x	66.00 ✓	x	2.90 ✓	x	2.90	0.40 ✓	0.40	av.	=	76.56 ✓ cum
H. 550M	1	x	24.00 19.5	x	2.90	x	2.90	0.40	0.40	av.	=	27.84 11.50m
H. 600M	1	x	32.00	x	2.90	x	2.90	0.40	0.40	av.	=	37.12 cum
H. 800M	1	x	5.50 ✓	x	3.00	x	3.00	0.65 ✓	0.65	av.	=	10.73 cum
Total qty.											=	152.25 cum

Junior Engineer
W.D. Works Section,
Jhanjharpur

Assistant Engineer
R.W.D. Work sub Div.
Jhanjharpur

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

25/4