



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Bishauli Path to
Machhighi Mahadalit Tol FDR at **Block- Jhanjharpur** in
Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~0.86723~~ lac.

0.77948

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- बिबौर पथ से महुवी महापति रोड

प्राक्कलित राशि :- 0.86723 लाख
0.77948

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक
..... पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- Mortable of Road from Bishaul Path to
Machheshi Mahadalit Tol

A. For Road


1. Damage Location Chainage :-
2. Damage Length :- 13.00 m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- 32.956 m
 - iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:- — 5' —


98/4/22
Signature of JE/AE/EE


3036
20/4/22
EE


28/4/22
Signature
(Name of Inspection)

**Estimate for Motorability of road damaged by flood from Bishaul Path to Machhighi Mahadalit Tol
For Year 2021**

Estimate No. :- FDR 2245

Length :- 0.747 km

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
	Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	36.56 32.906	2004.96	73306.35

	₹	65975.21
	₹	73306.35
	₹	7917.02
Add 12 % GST	₹	8796.76
	₹	659.75
Add 1 % L.C	₹	733.06
	₹	3395.90
Add S. Fee (32.906 x 1039/100) x 10 %	₹	3886.59
	₹	77947.88
Total	₹	86722.77
Say	₹	77948 = 00
	₹	86723.00

Junior Engineer
R.W.D, Works Section,
Jhanjharpur

Assistant Engineer
R.W.D, Work sub Div.
Jhanjharpur

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

कार्यपालक अभियंता, या० का- वि०, जयनगर
जयपुरांत पत्रांक- 678 (अ.क.) द्वारा दिनांक- 05/05/22
के आधार पर।

Technically Sanctioned for ₹ 77948 = 00
Seventy Seven thousand Nine hundred
(Rupees) Only.
Twenty eight) only.

Superintending Engineer
RWD Work Circle, Darbhanga

Name of Road :- Bishaul Path to Machhighi Mahadalit Tol												
MMGSY			Length :- 0.747 km							Block :- Jhanjharpur		
Appendix - I												
Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)												
Chainage	No.		Length		Bldth							

MMGSY

Length :- 0.747 km

Block :- Jhanjharpur

Appendix - I

[illegible]

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)				Quantity	
ch. 150 m	1	x	13.00	x	(3.90+3.60)/2	x	0.75 + 0.6 2	0.75	av.	=	32.936 36.56	cum
							Total qty.			=	36.56 32.936	cum

28/04/22
7k

Junior Engineer
R.W.D, Works Section,
Jhanjharpur


Assistant Engineer
R.W.D, Work sub Div.
Jhanjharpur

Executive Engineer
R.W.D (W) Division,
Jhunjharpur

28/4/20