

Estimate for Restoration work of Road from L032 to Bishanpur for the year 2021-2022 in Bisfi Block

Length-0.973 KM

Sr NO.	Item of Work							
1	Labour for lying dry graded Jhama khoa or Stone filter under Brick pitching in slope or							
Ch	Nos	Length	Width	Height	Quantity	Unit	Rate	Amount
0.250 Km	1	10.00	5.00+4.75	1.50	65.812			
				1.2+1.5+1.35	75.00			
Less HP	-1	1.13	5.00		-5.66			127671.00
					69.35	Cum	1939.93	134524.446
2	Supplying and fixing of 1000 MM dia Hume Pipe as per direction of E/I							
	3	2.50			7.50		6040.7	45305.25
								179829.70

Add 12% GST

Add 1% L/Cess

Add Signorage Fee(69.35x1032x10%)

Total

=F 21579.56

=R 1798.30

= 71563.94

=R: 274771.50

00.14-201671=

[Signature]
30-11-21
J E

RWD
Bisfi

[Signature]
A E

RWD
Bisfi

[Signature]
27-11-21
E E

RWD
Benipatti

check & verified

[Signature]
20.12.2021
J.E

[Signature]
20/12/2021
A.E.

[Signature]
20/12/21
E.E

Post facto T/s recorded for Rs. 201671.00 (Rs Two Lacs one thousand six hundred seventy one only.)

Reference Letter no. 233 dated 21/2/22 of E.E. Darbhanga-2.

[Signature]
Superintending Engineer
RWD Works Circle, Darbhanga

21/2/22

24

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20-12-2021 Name of PIU :- RWD (W) Div. Darbhanga 2
Name of Block / PIU :- Madhawapur (RWD (W) Div Benipatti)
Name of Road :- L-32 to Bishunpur

For Road :-

1. Damage Location/ Chainage :- 0.250 KM

2. Damage Length :- 10.0 Mtr

3. Nature of Damage :- Breach

4. Details of Restoration Works :-

i. Material being used in Restoration Works Brick bats & Humapipe

ii. Equipment's/ Tools being used in Restoration Works Tractor & Roller

iii. Procedure taken up in Restoration Works Filling & compaction

iv. Restored Length 10.0 Mtr & ~~the~~ 3 Humepipe of 2.5m length

Remarks :- Works found satisfactory

H.E.
20.12.21
Signature of JE/AE

Canopy
20/12/21
Signature of E.E