


RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work :- Majkuri To Majkuri Madarsa Tola

Block :- KOCHADHAMAN

Total Length:- 0.850 KM

Damage Length Part-I :- 0.157 Km

Damage Length Part-II :- 0.360 Km

Total Damage Length (Part-I + Part-II) :- 0.517Km

Estimated cost Part-I :- Rs 3502718.00

Estimated cost Part-II:- Rs 4842865.00

Total Estimated cost (Part-I + Part-II) :- Rs 8336144.00

Year : 2021-22

Inspection Report for Flood Damage Work

1. Name of PIUs : Kishanganj-1
2. Name Of Block / Road : maskuri madarsa Tola
A. For Road
1. Damage Location / Chainage :
2. Damage Length : 517 m
3. Nature Of Damage : Damage and deep side cutting
4. Details Of Restoration :
i) Material Being Used In Restoration : sand, cement bag, Geo bag, Bamboo, Brick bats
ii) Equipment / Tools Being Used In Restoration Works : tractor, Bamboo piling machine
iii) Procedure Taken Up In Restoration Works : manually
iv) Restored Length : 517 m
B. For Bridge
1. Damage Location / Chainage :
2. Damage Length :
3. Nature Of Damage :
4. Details Of Restoration :
i) Material Being Used In Restoration :
ii) Equipment / Tools Being Used in Restoration Works :
iii) Procedure Taken Up In Restoration Works :
iv) Restored Length :

Satisfactory

Signature of JE / AE / EE


Signature
कार्यपालक अभियन्ता
(Name Of Inspector)
प्रमाण कार्य विभाग
कार्य प्रमण्डल, अररिया

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, किशनगंज-1 अंतर्गत कोचाधामन प्रखंड के पथ "Majkuri To Majkuri Madarsa Tola----(PART-I)" जो विभागीय Online Monitoring Syatem MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:- मु0अ0- 4 (मु0) विविध कार्य- 23-60/2020 - 1937 / पटना, दिनांक- 07.07.2021 से प्राप्त है। इस पत्र से Real time geo-tagged photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में Kankai नदी/नदी उपधार से आए बाढ़ के कारण इस पथ के Road way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Motorable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक 26/07/2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलने वाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। Motorable कार्य में आवश्यकता अनुसार Bamboo Pilling / Pitching of E.C. Bags filled with local sand / Local sand filling / Brick bats का इस्तेमाल किया गया है। Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये गए कार्य का Geo-tagged photo real time के साथ MIS पर अपलोड है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्धतन है।


प्राक्कलन की यथा शीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा- कोचाधामन




सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल- कोचाधामन




कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, किशनगंज -1

ABSTRACT OF COST


Name of Work :-	Majkuri To Majkuri Madarsa Tola	
Block :-	KOCHADHAMAN	
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work Part-I :-	Rs 3067983.00
B	Cost of Restoration work Part-II:-	Rs 4244832.00
	Total Cost of Restoration work (Part-I + Part-II) :-	Rs 7312815.00
C	Add 12 % GST	Rs 877538.00
D	Add 1 % L. Cess	Rs 73128.00
E	Add S.Fee @ 10 % of Material Cost	Rs 72663.00
	Total Cost with GST, LC & S.Fee	Rs 8336144.00


J.E

RWD
KOCHADHAMAN



A.E


R.W.D
KOCHADHAMAN


E.E

R.W.D
Kishanganj - I


Technical Sanctioned for Rs 8336144/- (Rupees Eighty three lakh thirty six thousand one hundred forty four) only.



अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज



06/04/22
E.O

ABSTRACT OF COST

Name of Work :-		Majkuri To Majkuri Madarsa Tola (PART-I)
Block :-		KOCHADHAMAN
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 3067983.00
B	Add 12 % GST	Rs 368158.00
C	Add 1 % L. Cess	Rs 30680.00
D	Add S.Fee @ 10 % of Material Cost	Rs 35897.00
Total Cost with GST, LC & S.Fee		Rs 3502718.00



10-11-21
J.E
RWD
KOCHADHAMAN



10/11/21
A.E
R.W.D
KOCHADHAMAN



E.E
R.W.D
Kishanganj - I

Detailed Estimate

Name of Work :-			Majkuri To Majkuri Madarsa Tola (PART-I)									
Sl. No.	SDB No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I	1	1370	4.50	-	-	6165.00			
									Total:-	6165.00	Mtr.	55.40
2	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.									341541.00
3	WRD	5.7.40	Brick bats	2	2	137.00	-	-	548.00	Mtr.	30.87	16917.00
			Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I									
				1	1	20.00	2.50	0.45	22.50			
12		5.7.52	Supply of new bag with NC						Total:-	22.50	Cum	2168.72
			Supply of new bag and NC with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing in Nylon crate of size (1m x 1m x 1m) with a lead of 150m including supply of nylon threads etc, placing the filled crates in dry portion within a lead of 30m, all complete as per approved design, specification and direction of E/I.									48796.00
				2	2	10.00	(1.5+1.0)/2	(1.0+0.9)/2	47.50			
				2	2	12.00	(1.5+1.0)/2	(1.0+0.9)/2	57.00			
									Total:-	104.50	Cum	
									@ 0.85 Cum/ NC bag	123	No.	1249.46
4		5.7.53	Providing and filling empty cement bags									153684.00
			Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.									
				1	1	137.00	(2.5+2.0)/2	(3.5+3.0)/2	1001.81			
				1	1	137.00	(3.5+3.0)/2	(3.0+2.5)/2	1224.44			
									Total:-	2226.25	Cum	
									@ 0.034 Cum each bag	65478	No.	38.03
												2490128.00
												TOTAL 3067983.00



 J.E
 RWD
 KOCHADHAMAN


 A.E
 R.W.D
 KOCHADHAMAN



 E.E
 R.W.D
 Kishanganj - I

ABSTRACT OF QUANTITY & COST


Sl No	Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
					26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
1	Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
2	GSB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
3	Brick Bats:-	22.50	Cum	-	-	-	-	27.000	-	
4	Local Sand Filling:-	0.00	Cum	-	-	-	-	-	0.000	
5	Providing & Filling Empty Cement Bags:-	65478.00	No.	-	-	-	-	-	2226.252	
6	Providing & Filling Empty Cement Bags in Nylon Crate:-	123.00	No.	-	-	-	-	-	104.550	
		Total Quantity:-		0.000	0.000	0.000	0.000	27.000	2330.802	
		Rate:-		Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
		Total Amount:-		0.00	0.00	0.00	0.00	28350.00	330624.00	Rs 358974.00
								S.Fee@10% of M.Cost:-		Rs 35897.00


10.11.21
JE/RWD

KOCHADHAMAN


10.11.21
AE/RWD

KOCHADHAMAN




EE/RWD
Kishanganj-1

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, किशनगंज-1 अंतर्गत कोचाधामन प्रखंड के पथ "Majkuri To Majkuri Madarsa Tola----(PART-II)" जो विभागीय Online Monitoring Syatem MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:- मु0अ0- 4 (मु0) विविध कार्य- 23-60/2020 - 1937 / पटना, दिनांक- 07.07.2021 से प्राप्त है। इस पत्र से Real time geo-tagged photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में Kankai नदी/नदी उपधार से आए बाढ़ के कारण इस पथ के Road way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Motorable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक 26/07/2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलने वाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। Motorable कार्य में आवश्यकता अनुसार Bamboo Pilling / Pitching of E.C. Bags filled with local sand / Local sand filling / Brick bats का इस्तेमाल किया गया है। Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये गए कार्य का Geo-tagged photo real time के साथ MIS पर अपलोड है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अर्द्धतन है।


प्राक्कलन की यथा शीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा- कोचाधामन




सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल- कोचाधामन





कार्यपास्तक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, किशनगंज -1

ABSTRACT OF COST

Name of Work :-		Majkuri To Majkuri Madarsa Tola (PART-II)
Block :-		KOCHADHAMAN
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 4244832.00
B	Add 12 % GST	Rs 509380.00
C	Add 1 % L. Cess	Rs 42448.00
D	Add S.Fee @ 10 % of Material Cost	Rs 46205.00
	Total Cost with GST, LC & S.Fee	Rs 4842865.00



J.E
RWD
KOCHADHAMAN



A.E
R.W.D
KOCHADHAMAN



E.E
R.W.D
Kishanganj - I

Detailed Estimate

Name of Work :-			Detailed Estimate									
Majkuri To Majkuri Madarsa Tola (PART-II)												
Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I									
				1	3600	6.00	-	-	21600.00			
									Total:-	21600.00	Mtr.	55.40 ✓ 1196640.00
2	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.									
				2	2	360.00	-	-	1440.00	Mtr.	30.87 ✓ 44453.00	
6	9.2 (i)	1100 & 800	Sand filling or Type B (First class) bedding Fillling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9									
				1	1	360.00	(2.5+2.0)/2	(1.5+1.2)/2	1093.50			
									Total:-	1093.50	Cum	514.43 562529.00
3	WRD	5.7.40	Brick bats Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I									
				1	1	10.00	(1.0+1.2)/2	(0.3+0.25)/2	3.03			
									Total:-	3.03	Cum	2168.72 ✓ 6571.00
4		5.7.53	Providing and filling empty cement bags Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.									
				1	1	180.00	(8.0+6.8+5.3+8.0+6.8+7.0)/6	(0.8+0.9)/2	1068.45			
				1	1	180.00	+6.8+7.0)/6	(0.8+0.9)/2	1068.45			
									Total:-	2136.90	Cum	
							0.034 Cum each bag		62850	No.	38.03 ✓ 2390186.00	
											TOTAL	4244832.00



 J.E
 RWD
 KOCHADHAMAN



 A.E
 R.W.D
 KOCHADHAMAN



 E.E
 R.W.D
 Kishanganj - I

ABSTRACT OF QUANTITY & COST

Sl No	Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
					26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
1	Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
2	GSB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
3	Brick Bats:-	3.03	Cum	-	-	-	-	3.636	-	
4	Local Sand Filling:-	1093.50	Cum	-	-	-	-	-	1093.500	
5	Providing & Filling Empty Cement Bags:-	62850.00	No.	-	-	-	-	-	2136.900	
6	Providing & Filling Empty Cement Bags in Nylon Crate:-	0.00	No.	-	-	-	-	-	0.000	
		Total Quantity:-		0.000	0.000	0.000	0.000	3.636	3230.400	
		Rate:-		Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
		Total Amount:-		0.00	0.00	0.00	0.00	3818.00	458232.00	Rs 462050.00
								S.Fee@10% of M.Cost:-		Rs 46205.00


 JE/RWD
 KOCHADHAMAN


 AE/RWD
 KOCHADHAMAN


 EE/RWD
 Kishanganj-1