



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

PLAN HEAD :- F.D.R. 2245

A.A. COPY

YEAR (2021-22)

State :- BIHAR

District :- Darbhanga

Block :- MANIGACHHI

PWD Road Se Tatma Tol

Actual Length of Road	=	1.000 Km
Flood affected Length of Road	=	0.098 Km
TOTAL COST OF PAVEMENT	Rs	514,681.00 363788.00
TOTAL PROJECT COST	Rs	514,681.00 363788.00

Submitted By:
Executive Engineer
RWD (W) Division, Darbhanga-2

Prepared By:
Executive Engineer
RWD (W) Division, Darbhanga-2

Inspection Report for Flood Damage Work

Date :- 27.11.21

Name of PIU :- Executive Engineer, RWD, Works Division, Madhubani, Darbhanga-2

Name of Block :- Manigachhi, R.W.D. Works Divn. DARBHANGA-2

Name of Road :- PND Road Se Tatma Tol.

(A) For Road :-

1. Damage Location/Chainage :- CH, 35.00 M, 350 M, 400 M, 450 M, 500 M.

2. Damage Length :- 71.00 M.

3. Nature of Damage :- Road Breach and Erosion of Shoulders.

4. Details of Restoration Work :-

(i) Material being used in Restoration Works :- Brick Bats

(ii) Equipment's/Tools being used in Restoration works :- Tractor, Rammer etc.

(iii) Procedure taken up in Restoration Works :- Manual laying and compaction of Brick Bats.

(iv) Restored Length :- 71.00 M

(B) For Bridge :-

1. Damage Location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Work :-

(i) Material being used in Restoration Works :-

(ii) Equipment's/Tools being used in Restoration works :-

(iii) Procedure taken up in Restoration Works :-

(iv) Restored Length :-

Signature of JE/AE/EE

27.11.21
AE

Satisfactory

Signature

(Name of Inspecting Officer)

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- PWD Road Se Tatma Tol
 DISTRICT :- Darbhanga
 BLOCK :- MANIGACHHI
 Actual Length of Road :- 1.000 Km
 Flood Affected Length of Road :- 0.098 Km

		Lead in Km	7	+	1	
Sr. No.	Description				Amount (In Rs.)	
1	Brick bats Total Qty. = 217.28 153-5751 ³ 137.587 @ 2,004.96				435,627.00 307911.00	275856-
2	Add GST @ 12% =				52,275.00 26949.00	33103-00
3	Add Labour Cess @ 1% =				4,356.00 3079.00	2759-00
4	S.F. @10% on material(Brick Bats)=				32,423.00 15849.00	14199-00
TOTAL RESTORATION COST OF THE PROJECT IN Rs.					514,681.00 362788.00	325917-

~~Post facto T/S for Rs 2,75,856-00 (Rs Two lacs Seventy Five Thousand Eight Hundred Fifty six only.)~~
 Post facto T/S for Rs 3,25,917-00 (Rs Three lacs Twenty Five Thousand Nine Hundred Seventeen only.)

Superintending Engineer
 RWD Works Circle, Darbhanga

Junior Engineer

RWD (W) Division, Darbhanga-2

Assistant Engineer

RWD (W) Division, Darbhanga-2

Executive Engineer

RWD (W) Division, Darbhanga-2

