



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

PLAN HEAD :- F.D.R. 2245

A.A. COPY

YEAR (2021-22)

State :- BIHAR

District :- Darbhanga

Block :- MANIGACHHI

PWD Sarak Suvdhi Das ke Ghar Se Dan Ji Mandal Tol Vai
Refaral Hospital

Actual Length of Road	=	1.765 Km
Flood affected Length of Road	=	0.060 Km
TOTAL COST OF PAVEMENT	Rs	755,056.00 553305.00
TOTAL PROJECT COST	Rs	755,056.00 553305.00

Submitted By:
Executive Engineer
RWD (W) Division, Darbhanga-2

Prepared By:
Executive Engineer
RWD (W) Division, Darbhanga-2

Inspection Report for Flood Damage Work

Date :- 30.11.21

Name of PIU :- Executive Engineer, RWD, Works Division, Dharbhanga-2

Name of Block :- Manigachhi

Name of Road :- PWD Satak Suvdhi Das Ka Ghar Se Dandi Mandal Tol
via Refal Hospital

(A) For Road :-

1. Damage Location/Chainage :- 0 to 200 m

2. Damage Length :- 0.060 km.

3. Nature of Damage :- Road Breach

4. Details of Restoration Work :-

(i) Material being used in Restoration Works :- Brick Bat

(ii) Equipment's/Tools being used in Restoration works :- Tractor, Roller etc.

(iii) Procedure taken up in Restoration Works :- Manually laying and compacting
of Brick Bats

(iv) Restored Length :-

(B) For Bridge :-

1. Damage Location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Work :-


(i) Material being used in Restoration Works :-

(ii) Equipment's/Tools being used in Restoration works :-

(iii) Procedure taken up in Restoration Works :-

(iv) Restored Length :-

work found satisfactory


30.11.21
Signature of JE/AE/EE


30.11.21
AE


30.11.21
Signature

(Name of Inspecting Officer)

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- PWD Sarak Suvdhi Das ke Ghar Se Dan Ji Mandal Tol
 DISTRICT :- Darbhanga
 BLOCK :- MANIGACHHI
 Actual Length of Road :- 1.765 Km
 Flood Affected Length of Road :- 0.060 Km

		Lead in Km	7	+	1
Sr. No.	Description				Amount (In Rs.)
1	Brick bats Total Qty. = 318.75 @ 2,004.96	233.58			468319.00 639,080.00 56,198.00 76,698.00 4683.00 6,391.00 24,105.00 32,895.00
2	Add GST @ 12%=				
3	Add Labour Cess @ 1%=				
4	S.F. @10% on material(Brick Bats)=				
TOTAL RESTORATION COST OF THE PROJECT IN Rs.					553305.00 755,056.00

Post facto T/S for Rs 5,53,305/- (As five lacs fifty three thousand Three Hundred Five only.)

Superintending Engineer
 RWD Works Circle, Darbhanga

Junior Engineer

RWD (W) Division, Darbhanga-2

Assistant Engineer

RWD (W) Division, Darbhanga-2

Executive Engineer

RWD (W) Division, Darbhanga-2

Estimate for Temporary Restoration of Flood affected Road

Name of Road:- PWD Sarak Suvdhi Das ke Ghar Se Dan Ji Mandal Tol Vai Refaral

BLOCK :- MANIGACHHI

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/L.

Sl No	Chainage		Unit	Nos.	Length (m)	Width (m)	Depth/ Thickness (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
1	0 to 200		Cum	1.00	60.00	$\frac{3.50 + 4.25}{2}$	$\frac{0.33 + 1.23}{2}$	$\frac{2.30 + 2.30}{2}$	2,004.96	6,39,890.00
					60.000			$\frac{2.30 + 2.30}{2}$	Total Amt.	6,39,890.00

Sumi
Junior Engineer

RWD (W) Division, Darbhanga-2

Assistant Engineer

RWD (W) Division, Darbhanga-2

Sumi
Executive Engineer

RWD (W) Division, Darbhanga-2

Verified and corrected as per Site

Qty - 233.58 m³

Sumi
JE

Sumi
AG

Sumi
EG