RURAL WORKS DEPARTMENT

GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work :-	School Tolaa to T03
Block :-	KOCHADHAMAN
Total Length:-	1.626 KM
Damage Length:-	0.220 KM
Estimated cost :-	Rs 1157869.00

Year : 2021-22

Inspection Report for Flood Damage Work

1.Name of PIUs : Kishanganj-1

2. Name Of Block / Road : School Tola to T03

A. For Road

1.Damage Location / Chainage : 220 m

2.Damage Length : Damage and deep side cutting

3.Nature Of Damage :

4.Details Of Restoration :

i) Material Being Used In Restoration : sand, cement bag, Bamboo, Brick bats

ii) Equipment / Tools Being Used In Restoration Works : Tractor

iii) Procedure Taken Up In Restoration Works : manually

iv) Restored Length : 220 m

B. For Bridge

1.Damage Location / Chainage :

2.Damage Length :

3.Nature Of Damage :

4.Details Of Restoration :

i) Material Being Used In Restoration :

ii) Equipment / Tools Being Used in Restoration Works :

iii) Procedure Taken Up In Restoration Works :

iv) Restored Length :

NA

Satisfactory

04-04-22
JE

04/04/22
AE

Signature of JE / AE / EE

04/04/22

Signature
कार्यपालक अभियन्ता
(Name Of Executive Engineer)
कार्य प्रमण्डल, अररिया

ABSTRACT OF COST

Name of Work :-	School Tolaa to T03
Block :-	KOCHADHAMAN

Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 998367.00
B	Add 12 % GST	Rs 119804.00
C	Add 1 % L. Cess	Rs 9984.00
D	Add S.Fee @ 10 % of Material Cost	Rs 29714.00
	Total Cost with GST, LC & S.Fee	**Rs 1157869.00**

28-11-021
J.E
RWD
KOCHADHAMAN

30/11/21
A.E
R.W.D
KOCHADHAMAN

30/11/21
E.E
R.W.D
Kishanganj - I

Technical sanctioned for Rs 1157869/- (Rupees Eleven lakh fifty seven thousand Eight hundred sixty nine) only.

06/04/22
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

06/04/22
E.O

Detailed Estimate

Name of Work :-			School Tolaa to T03								
Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I									
				2	1125	2.00	-	-	4500.00			
								Total:-	4500.00	Mtr.	55.40	249300.00
2	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.									
				1	1	220.00	-	-	220.00			
								Total:-	220.00	Mtr.	30.87	6791.00
3	WRD	5.7.40	**Brick bats**									
			Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I									
				1	1	150.00	0.9+1.2+1.5/2	0.60	162.00			
				1	1	70.00	0.9+1.2/2	0.60	44.10			
								Total:-	206.10	Cum	2168.72	446973.00
4		5.7.53	**Providing and filling empty cement bags**									
			Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stiching on two line by approved nylon thread with stiching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.									
				1	1	150.00	0.80	1.50	180.00			
				1	1	70.00	0.80	1.50	84.00			
								Total:-	264.00	Cum		
							@ 0.034 Cum each bag		7765	No.	38.03	295303.00
											TOTAL	998367.00

28-11-021

J.E
RWD
KOCHADHAMAN

30/11/21

A.E
R.W.D
KOCHADHAMAN

E.E
R.W.D
Kishanganj - I

ABSTRACT OF QUANTITY & COST

Sl No	Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
					26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
1	Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
2	GSB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
3	Brick Bats:-	206.10	Cum	-	-	-	-	247.320	-	
4	Local Sand Filling:-	0.00	Cum	-	-	-	-	-	0.000	
5	Providing & Filling Empty Cement Bags:-	7765.00	No.	-	-	-	-	-	264.010	
6	Providing & Filling Empty Cement Bags in Nylon Crate:-	0.00	No.	-	-	-	-	-	0.000	
	Total Quantity.:-			0.000	0.000	0.000	0.000	247.320	264.010	
	Rate:-			Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
	Total Amount:-			0.00	0.00	0.00	0.00	259686.00	37450.00	**Rs 297136.00**
									S.Fee@10% of M.Cost:-	**Rs 29714.00**

28-11-2021
JE/RWD
KOCHADHAMAN

30/11/21
AE/RWD
KOCHADHAMAN

EE/RWD
Kishanganj-1