



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

156

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Lakhnaur

Estimate for Mortable of the Road from NH-57 to Dudarbanana FDR
at Block- **Lakhnaur** in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~0.83034~~ lac.

0.03980 Lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Lakhnau

Name of Road :- NH-57 to Dubourbanana

A. For Road

1. Damage Location Chainage :- 200m, 275 m
2. Damage Length :- 28.50 m
3. Nature of Damage :- Flood
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick Bat
 - ii. Equipment's/Tools being used in Restoration works:- Tractor, Back hoe loader
 - iii. Procedure taken up in Restoration works:- 1.68 m³
 - iv. Restored Length:- 28.50 m

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

Signature of JE/AE/EE

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- NH-57 To Dudarbanana

प्राक्कलित राशि :- ~~0.83034~~ Lacs

0.3980

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक NH-57 से

दुडरबनना पथ के लिए तैयार किया गया है, जो

कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।

कनीय अभियंता

सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from NH-57 to Dudarbanana For Year 2021

ad :- MMGSY OLD

Length :- 1.225 km

Item No.	Name of Item	Unit	Quantity As per Appendix - I	Rate	Amount
	Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	35.01 1.68	2004.96	3368.33 70188.64

3368.33
 $\text{₹ } 3368.33$
 404.20
 Add 12 % GST $\text{₹ } 8,422.64$
 33.68
 Add 1 % L.C $\text{₹ } 701.89$
 1.68
 Add S. Fee $(35.01 \times 1063.00) \times 10\%$ $\text{₹ } 173.38$
 1032
 3721.30
 Total $\text{₹ } 3979.59$
 $83,034.46$
 Say $\text{₹ } 83,034.00$
 3980.00

25/11/21

Junior Engineer
R.W.D. Works Section,
Lakhnaur

25/11/21

Assistant Engineer
R.W.D. Work sub Div.
Lakhnaur

25/11/21
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

678.00
4/15/22

3980.00 (Rupees Three thousand
Nine hundred Eighty only)
Only.

25/11/21
Superintending Engineer
R.W.D. Work Circle, Darbhanga

25/11/21

Name of Road :- NH-57 to Dudarbanana

MMGSY OLD

Length :- 1.225 km

Block :- Lakhnaur

**Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)**

Chainage	Nos.		Length (In Mtr.)		Bidth (In Mtr.)		Thickness (In Mtr.)			Quantity		
CH. 200M	1	x	7.50 2.10	x	2.10	x	1.10	0.20	1.10	av.	= 6.48 21.38	cum
CH. 275M	1	x	19.00	x	2.75	x	0.25		0.25	av.	= 13.06	cum
Total qty.										=	35.01	cum

1.68 cum

PS/11/21

Junior Engineer
R.W.D. Works Section,
Lakhnaur

Oy/5/11/21

Assistant Engineer
R.W.D, Work sub Div.
Lakhnaur

RA/27/10/22
S-6

Executive Engineer
R.W.D (W) Division
Jhanjharpur

RA/27/10/22
S-6

27/04/2022
ME

27/4