



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2020-21

DETAILED PROJECT REPORT

TEMPORARY RESTORATION WORK

DISTRICT :-	DARBHANGA	BLOCK :-	Darbhanga		
ROAD NAME :	Kali mandir Kansi Se Naya Tola Kansi				
HEAD	FDR		YEAR-2021-22		
	TOTAL LENGTH OF ROAD	:	1.000	KM	
	DAMAGE LENGTH	:	0.157	KM	
	TOTAL COST OF PROJECT	:	12.491	LAKH	

Executive Engineer
RWD Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Beni Baur

Name of Block/Road:- Kalmankar se Naya Jala Kansi

A. For Road

1. Damage Location Chainage:- 600 m to 800 m
2. Damage Length :- 157 m
3. Nature of Damage :- E.C. bags & Geo Bag / Bamboo Piling
4. Details of Restoration Works :- E.C. bags, locally Recd Crush
i. Material being used in Restoration works:- E.C. bag / tractor / Bank 600
ii. Equipment's / Tools being used in Restoration works:- Locally E.C. bag with L / sand
iii. Procedure taken up in Restoration works:-
iv. Restored Length:- 157 m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
i. Material being used in Restoration works:-
ii. Equipment's / Tools being used in Restoration works:-
iii. Procedure taken up in Restoration works:-
iv. Restored Length:-

M / A

Signature of JE/AE/EE

work found satisfactory
7/3/22
AE

Signature

अधिक्षण अभियंता (Name of Inspection)
कार्य अंचल, दरभंगा

प्रतिवेदन

का नाम - काली मंदिर काली रतनरा एला केली
की लंबाई - 1.00 K.M (इतिहास पत्रांक - 0.157 K.M)
कलित राशि - 12.491 माल
डल का नाम - काली प्रमंडल दरभंगा-1
डल का नाम - दरभंगा-1
जना का नाम - F.D.R

तुत प्राक्कलन काली मंदिर काली रतनरा एला केली पथ के लिए तैयार किया गया है, जो कि बाढ़ अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। इसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का मना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विध (कार्य)-23-60/2020-1937 पटना, दिनांक-07.07.2021 के आलोक में तैयार किया जा है।

Geo Bag/ Ec Bag (सिंह)

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईंट के टुकड़ों से भरकर उसका मरम्मत किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचित दर पर तैयार किया गया है। यह कार्य कथित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। इस कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।

नीय अभियंता
ग्रामीण कार्य विभाग

सहायक अभियंता
ग्रामीण कार्य विभाग

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, दरभंगा-1

GENERAL ABTRACT OF COST

NAME OF ROAD :	Kali mandir Kansi Se Naya Tola Kansi	
DISTRICT	DARBHANGA	
BLOCK	DARBHANGA	
LENGTH OF ROAD (in Km)	1.000	
DAMAGED LENGTH (KM)	0.157	
Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	1098455.060
2	GST @12%	131814.607
3	Labour cess @1%	10984.551
4	Seigniorage fee	7837.744
5	Grand Total	1249091.961
6	Say(lacs)	12.491

[Signature]
28/02/22

JE
RWD

[Signature]
7/3/2022

AE
RWD

[Signature]
28/02/22

EE
RWD

Post Facto T/S for Rs 1249000=00 (Rs Twelve
lacs Forty Nine Thousand only)

[Signature]
अधिक्षण अभियंता
कार्य अंचल, दरभंगा
4/3/22

Detail Estimate For Motorable work of Road

Detail Estimate For Motorable Work of Road								
Name of road		Block			District	Division		Length(KM)
Kali mandir Kansi Se Naya Tola Kansi		DARHANGA			DARHANGA	DARHANGA-I		1
Description		Unit	Nos	LENGTH	width	Area	RATE	AMOUNT (in Rs.)
Providing and laying filling Geo bag 1mx0.7m with local sand 126 kg including stiching stacking placing loading unloading carrige with trolly within 150m as per specifiction wrd sor 5.7.54, lead of local sand 0.5km	ch.-0.00m -180m		1.00	157.00	2.40	376.80		
			1.00	157.00	0.60	94.20		
			1.00	157.00	0.60	94.20		
			Total (A)			565.20		
			Nos of Geo Bags= A/0.54			1,046.67		
			Total			1046.00	156.70	1,63,908.20
		Nos	length	width	height	qty		
Construction of Embankment with material obtained from borrow pits with a lift upto 1.5 m , transporting to the site spreading , grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 .		1	157	3.75	2.5	1471.88	225.76	3,32,290.50
Providing and laying filling EC bag with local sand including stiching stacking placing loading unloading carrige								
		1	157	1.2	2.25	423.90	423.90	
			nos of bags =254.34/0.034			12467.00	37.70	4,70,005.90
Supply of Bamboo	nos					290	166.5	48285


[Signature]
12/2/22

[Signature]
12/2/2022

Supply of Bitumen drums	nos			166	123.71	20535.86
Labour for cutting , making shoes, driving etc	m			2033	31.2	63429.6
Total						1098455.06


7/3/22

JE
RWD


7/3/2022

AE
RWD



EE
RWD

cutting fitting
supply
runner