



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Raghunandanpur to
Arariya paswan tol **under FDR at Block- Jhanjharpur** in
Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

~~4-66382 lac.~~

~~6-25720 lac.~~

1-73141 lac

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- Raghunandampur to Araria Paschim.

प्राक्कलित राशि :- ~~1.66382 lac~~ 1.72141 lac

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा


योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Raghunandampur to Araria Paschim पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।


यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईंट के टुकड़े/ मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- Raghunandanpur to Arariya Jeevan tal.

A. For Road

1. Damage Location Chainage :- Ch. 1120 m, 500, 20 m Gap.
2. Damage Length :- 0.124 Km
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick bats
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- 70.147 m³
 - iv. Restored Length:- 0.124 Km

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

S'

Signature of JE/AE/EE

303E,
23/4/22
ER

Signature
(Name of Inspection)


**Rate for Motorability of road damaged by flood from Raghunandanpur to Arariya paswan tol
For Year 2021**

FDR 2245

Length :- 1.375 km

Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
	Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/L.	Cum	70.147 263.80 73.092	2004.96	528918.42 140641.93 146545.54

140641.93
 ₹ 5,28,918.42
 146346.54
 Add 12 % GST ₹ 63,470.21
 1,65,77.03
 17,585.58
 Add 1 % L.C ₹ 5,289.18
 140641.93
 1465.43
 Add S. Fee (263.80 x 1063.00) x 10 % ₹ 28,042.47
 73.092 1032
 245613
 7543.09
 Total ₹ 6,25,720.28
 1,66,382.01
 Say ₹ 6,25,720.00
 1,66,382
 173141.00


 Junior Engineer
 R.W.D. Works Section,
 Jhanjharpur


 Assistant Engineer
 R.W.D. Work sub Div.
 Jhanjharpur


 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur

कार्यपालक अभियंता द्वारा कार्ड कि जमानत के द्वारा औचित्यपूर्ण
पत्रांक 671 (अन०) दि. 29/04/22 के अन्तर्गत

Technically Sanctioned at Rs 1,73,141.00 (Rupees one Lakh Seventy
three thousand one hundred forty one) only.


 Superintending Engineer
 RWD Work Circle, Darbhanga

Abhinav
 05/05/22

Name of Road :- Raghunandanpur to Arariya paswan tol

MMGSY

Length :- 1.375 km

Block :- Jhanjharpur

Appendix - I

**Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)**

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)			Quantity	
1120 m gap	1	x	8.80	x	(1.80+1.70+1.80)/3	x	1.77	(1.20+1.35+1.20)/3	0.6	13.24	cum
1120 m gap	1	x	9.50	x	(1.50+1.40+1.30)/3	x	1.40	(1.20+1.25+1.30)/3	0.6	15.53	cum
h. 500 mm	1	x	30.00	x	(1.10+1.30)/2	x	1.20	(0.70+0.80+0.70)/3	0.6	13.24	cum
h. 20 m Gap	1	x	8.70	x	(1.10+1.30)/2	x	1.20	(0.70+0.80+0.70)/3	0.6	22.47	cum
h. 20 m Gap	1	x	30.00	x	(1.10+1.30)/2	x	1.20	(0.70+0.80+0.70)/3	0.6	22.47	cum
h. 20 m Gap	1	x	9.80	x	(1.10+1.30)/2	x	1.20	(1.30+1.20+1.10)/3	0.6	16.44	cum
h. 20 m Gap	1	x	5.00	x	(1.10+1.20)/2	x	1.20	(1.20+1.05)/2	0.6	6.75	cum
h. 500 mm	2	x	10.30	x	(1.40+1.30+1.20)/2	x	1.35	(1.30+1.25+1.30)/3	0.6	25.78	cum
Total qty.										= 253.20	cum

9.34 ✓
59.56 ✓
13.62 ✓
6.264 ✓
31.60 ✓
3.528 ✓
1.725 ✓
2.03 12.05 ✓
73.092 ✓
210492

[Signature]
05/11/21

Junior Engineer
R.W.D. Works Section,
Jhanjharpur

[Signature]
05/11/21

Assistant Engineer
R.W.D. Work sub Div.
Jhanjharpur

[Signature]
05/11/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur