

प्रशासनिक प्रतिवेदन

पथ का नाम :- लोआम से हजमा टोला रोड तक मरम्मति कार्य (FDR)
 पथ की लम्बाई :- 1.180 कि०मी०
 प्राक्कलित राशि:- 1.45149 लाख मात्र।
 प्रमण्डल का नाम :- ग्रामीण कार्य विभाग, कार्य प्रमण्डल, दरभंगा-1
 अंचल का नाम:- ग्रामीण कार्य विभाग, कार्य अंचल, दरभंगा।
 योजना शीर्ष :- FDR-2245
 योजना वर्ष :- 2020-21

प्रस्तुत प्राक्कलन दरभंगा सदर प्रखंड अन्तर्गत लोआम से हजमा टोला रोड तक पथ मरम्मति कार्य के लिए तैयार किया गया है, जो कि वर्ष 2021 में आयी भीषण बाढ़ एवं अतिवृष्टि के कारण उक्त पथ का पथांश कई स्थानों पर क्षतिग्रस्त हो गया था। जिसके कारण यातायात अवरुद्ध हो गई थी। यातायात को पुनः बहाल करने के लिए पथ को अस्थायी रूप से मोटरेबुल (Motorable) किया गया। मोटरेबुल (Motorable) कार्य करने हेतु आवश्यकतानुसार प्राक्कलन में (Brick Bats) ईंट के टुकड़ों से भरकर उसका सम्पीडन किये जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन विभागीय पत्रांक-मु0अ0-4 (मु0) विविध (कार्य)-23-60/2020-1937, पटना दिनांक-07.07.2021 के अनुपालन में तैयार किया गया है।

प्रस्तुत प्राक्कलन वर्तमान अनुसूचित दर के आधार पर तैयार किया गया है। चूंकि यह कार्य विभागीय स्तर पर कराया गया है। प्रस्तुत प्राक्कलन में संवेदक लाभांश का प्रावधान नहीं किया गया है।

अतः यह प्राक्कलन की लोकहित एवं जनहित में तकनीकी अनुमोदन अपेक्षित है।


 कर्मचारी अभियंता,
 ग्रामीण कार्य विभाग,
 प्रशाखा, दरभंगा सदर


 सहायक अभियंता,
 ग्रामीण कार्य विभाग,
 कार्य अवर प्रमण्डल, दरभंगा सदर


 कार्यपालक अभियंता
 ग्रामीण कार्य विभागाध्यक्ष
 कार्य प्र० दरभंगा-1

Page No. - 19

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benipar

Name of Block/Road:- Loam to Hajma tala

A. For Road

1. Damage Location Chainage:- 1000 M to 1100 M
2. Damage Length :- 39 M
3. Nature of Damage :- Road Crust damaged
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Bricks
 - ii. Equipment's /Tools being used in Restoration works:- J.C.B / tractor / Labour
 - iii. Procedure taken up in Restoration works:- Laying of Bricks with light ramming
 - iv. Restored Length:- 39 M

B. For Bridge

1. Damage Location Chainage:-
 2. Damage Length :-
 3. Nature of Damage :-
 4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipment's /Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-
- N/A

work found Satisfactory

[Signature]

Signature of JE/AE/EE

Signature
(Name of Inspection)

[Circular Stamp]
25/03/2022
J-E

[Signature]
25/3/22
AE

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- LOAM Se HAZAM TOLA ROAD

DISTRICT :- Darbhanga

BLOCK :- Darbhanga Sadar

Actual Length of Road :- 1.180 Km

Flood Affected Length of Road :- 0.039 Km

		Lead in Km	7	+	1
Sr. No.	Description				Amount (In Rs.)
1	Brick bats Total Qty. = 61.28 55.19	@	2,004.96		122,854.00 1,10,653.75
2	Add GST @ 12%=		13,278.98		14,742.00
3	Add Labour Cess @ 1%=		1106.53		1,229.00
4	S.F. @10% on material(Brick Bats)=		5695.60		6,324.00
TOTAL RESTORATION COST OF THE PROJECT IN Rs.					145,149.00

= 1,30,734.33

Rs. 1,30,734.33

कार्यपालक अभियंता, बेनीपुर के जाँच प्रतिवेदन के आधार पर
Technically sanctioned for Rs. 1,30,734.00 (Rupees
one lakh thirty thousand seven hundred thirty four) only

Superintending Engineer
RWD Works Circle, Darbhanga

Junior Engineer

RWD (W) Division, Darbhanga-1

Assistant Engineer

RWD (W) Division, Darbhanga-1

Executive Engineer

RWD (W) Division, Darbhanga-1

Estimate for Temporary Restoration of Flood affected Road

Name of Road:- LOAM Se HAZAM TOLA ROAD

BLOCK :- Darbhanga Sadar

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/I.

Sl No	Chainage		Unit	Nos.	Length (m)	Width (m)	Depth/Thickness (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
	0	to 300 m	Cum	1.00	10.00	3.00	0.30	9.000	2,004.96	18,045.0
	300	to 400 m	Cum	1.00	13.00	$\frac{3.60 + 3.80}{2}$	$\frac{0.60 + 0.90}{2}$	36.075	2,004.96	72,329.0
	400	to 700 m	Cum	1.00	8.00	$\frac{2.30 + 2.70}{2}$	0.45	9.000	2,004.96	18,044.0
	700	to 800 m	Cum	1.00	8.00	3.00	0.30	7.200	2,004.96	14,436.0
					39.000			61.275	Total Amt.	1,22,854.00

55-19 1,10,653.75

Junior Engineer
RWD (W) Division, Darbhanga-1

Assistant Engineer
RWD (W) Division, Darbhanga-1

Executive Engineer
RWD (W) Division, Darbhanga-1

Verified & found Correct

25/3/22
AE

25/3/22
EE

60,128.75