



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

PLAN HEAD :- F.D.R. 2245

A.A. COPY

YEAR (2021-22)

State :- BIHAR

District :- Darbhanga

Block :- Darbhanga Sadar

MISHROLIYA PMGSY ROAD Se NAVTOLIYA

Actual Length of Road	=	1.072 Km
Flood affected Length of Road	=	0.056 Km
TOTAL COST OF PAVEMENT	Rs	296,431.00
TOTAL PROJECT COST	Rs	296,431.00

Submitted By:
Executive Engineer
RWD (W) Division, Darbhanga-1

Prepared By:
Executive Engineer
RWD (W) Division, Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benihur

Name of Block/Road:- Mishnoliya P.M.G.S.Y Road to Navtoliya

A. For Road

1. Damage Location Chainage:- 700 M to 800 M

2. Damage Length :- 56 M

3. Nature of Damage :- Road crust damaged

4. Details of Restoration Works

i. Material being used in Restoration works:- Bitick Bal

ii. Equipment's /Tools being used in Restoration works:- J.C.B / tractor / Labour

iii. Procedure taken up in Restoration works:-

iv. Restored Length:- Laying of Bitick bal with light Rm

56 M

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

H/A

work found satisfactory

Signature of JE/AE/EE

25/03/2022
JE

Shashi
25/3/22
AE

Signature

(Name of Inspection)

प्रशासनिक प्रतिवेदन


पथ का नाम :- मिश्रोलिया PMGSY रोड से नवटोलिया तक मरम्मत कार्य (FDR)
पथ की लम्बाई :- 1.072 कि०मी०
प्राक्कलित राशि:- 2.96431 लाख मात्र।
प्रमण्डल का नाम :- ग्रामीण कार्य विभाग, कार्य प्रमण्डल, दरभंगा-1
अंचल का नाम:- ग्रामीण कार्य विभाग, कार्य अंचल, दरभंगा।
योजना शीर्ष :- FDR-2245
योजना वर्ष :- 2020-21


प्रस्तुत प्राक्कलन दरभंगा सदर प्रखंड अन्तर्गत मिश्रोलिया PMGSY रोड से नवटोलिया तक पथ मरम्मत कार्य के लिए तैयार किया गया है, जो कि वर्ष 2021 में आयी भीषण बाढ़ एवं अतिवृष्टि के कारण उक्त पथ का पथांश कई स्थानों पर क्षतिग्रस्त हो गया था। जिसके कारण यातायात अवरुद्ध हो गई थी। यातायात को पुनः बहाल करने के लिए पथ को अस्थायी रूप से मोटरबुल (Motorable) किया गया। मोटरबुल (Motorable) कार्य करने हेतु आवश्यकतानुसार प्राक्कलन में (Brick Bats) ईंट के टुकड़ों से भरकर उसका सम्पीडन किये जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन विभागीय पत्रांक-मु0अ0-4 (मु0) विविध (कार्य)-23-60/2020-1937, पटना दिनांक-07.07.2021 के अनुपालन में तैयार किया गया है।

प्रस्तुत प्राक्कलन वर्तमान अनुसूचित दर के आधार पर तैयार किया गया है। चूँकि यह कार्य विभागीय स्तर पर कराया गया है। प्रस्तुत प्राक्कलन में संवेदक लाभांश का प्रावधान नहीं किया गया है।

अतः यह प्राक्कलन की लोकहित एवं जनहित में तकनीकी अनुमोदन अपेक्षित है।


कमीय अभियंता,
ग्रामीण कार्य विभाग,
प्रशाखा, दरभंगा सदर


सहायक अभियंता
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, दरभंगा सदर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्र० दरभंगा-1

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- MISHROLIYA PMGSY ROAD Se NAVTOLIYA
 DISTRICT :- Darbhanga
 BLOCK :- Darbhanga Sadar
 Actual Length of Road :- 1.072 Km
 Flood Affected Length of Road :- 0.056 Km

		Lead in Km	7	+	1
Sr. No.	Description				Amount (In Rs.)
1	Brick bats Total Qty. = 125.14 113.97	@	2,004.96		250,900.00 2,28,509.20
2	Add GST @ 12%=		27420.48		30,108.00
3	Add Labour Cess @ 1%=		2285.09		2,509.00
4	S.F. @10% on material(Brick Bats)=		11761.70		12,914.00
TOTAL RESTORATION COST OF THE PROJECT IN Rs.					296,431.00

= 2,69,971.22
 (Rupee 2,69,971.22)

कार्यपालक अभियंता, वैनीपुर के जाँच प्रतिवेदन के आधार पर
 Technically sanctioned for Rs. 2,69,971.22 (Rupees two
 lacs sixty nine thousand nine hundred seventy one) only

Superintending Engineer
 RWD Works Circle, Darbhanga

Junior Engineer

RWD (W) Division, Darbhanga-1

Assistant Engineer

RWD (W) Division, Darbhanga-1

Executive Engineer

RWD (W) Division, Darbhanga-1

Estimate for Temporary Restoration of Flood affected Road

Name of Road:- MISHROLIYA PMGSY ROAD Se NAVTOLIYA

BLOCK :- Darbhanga Sadar

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/I.

Sl No	Chainage		Unit	Nos.	Length (m)	Width (m)	Depth / Thickness (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
	0	to 200m	Cum	1.00	19.00	$\frac{4.00 + 4.20 + 3.80}{2}$	$\frac{0.75 + 1.25}{2}$	64.83	2,004.96	1,52,377.00
	200	to 300	Cum	1.00	30.00	$\frac{3.00 + 3.30}{2}$	$\frac{0.60 + 0.30}{2}$	42.525	2,004.96	85,260.0
	300	to 400m	Cum	1.00	7.00	$\frac{3.00 + 3.30}{2}$	0.30	6.615	2,004.96	13,263.0
					56.000			125.140	Total Amt.	2,50,900.00

113.97

2,28,508

Jun 30-11-21
Junior Engineer

RWD (W) Division, Darbhanga-1

20/11/21
Assistant Engineer

RWD (W) Division, Darbhanga-1

16/11/21

Executive Engineer

RWD (W) Division, Darbhanga-1

Verified & found correct

25/3/22
AE

25/3/22
JE

25/3/22

EE

1299