

ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK

(Temporary restoration 2021-22)



Name of the Road :- Muzaffarpur jila anatar gat P.W.D path hussepur chauk se hote hue hussepur P.M.G.S.Y path tak path.

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD	:	2.100	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	6.951 6.783	Lac
-------------------	---	---------------------------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

6.72

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : मुजफ्फरपुर जिलाअंतर्गत PWD पथ डुल्लपुर चौक से
डोले डुल्लपुर pm 658 पथ तक पथ /


पथ की लम्बाई (km) : 2.10

तात्कालिक मरम्मति
कार्य की राशि (लाख) : ~~6.75~~ 6.79

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु
Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/
1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल
हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर
विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/21

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021

सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE, RWD(W) DIV - MUZAFFARPUR EAST-1
- 2 Name of Block/Road : SAKRA / MUZAFFARPUR Jile Antargat PWD path hussepur
chowk ke hote hue hussepur pombay 400 to 500
- A For Road
 - 1 Damage Location/Chainage : 1.85 - 2.1 km chⁿ
 - 2 Damage Length : 0.105 km
 - 3 Nature of Damage : Embankment damaged / Breached.
(High embankment & flood water overtopped it)
 - 4 Details of Restoration Works : B. Pits = 261.54m Bamboo pile = 1428 nos Sand Bag
Bamboo pile = 1110.0m. Bamboo runner = 1364m. Satisfactory
 - i Material being used in Restoration Works : Brickbat, Sand Bag, Bamboo.
 - ii Equipments/Tools being used in Restoration Works : Roller, Tipper, tractor, trailer, manual tools
 - iii Procedure Taken up in Restoration Works : Breach filled with Brickbat &
flank were controlled by using
sand bag & bamboo pile.
 - iv Restored Length : 105 km

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

Executive Engineer
R.W.D. Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- Muzaaffarpur jila anatargat P.W.D path hussepur chauk se hote hue hussepur P.M.G.S
 District Muzaaffarpur
 Block Sakra
 Division Muzaaffarpur East-1
 Length of Road (in Km) 2.1

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	5.614 5.652 5.606
2	Sand bag	0.544 0.544 0.560
3	Bamboo Piles	0.711 0.711 0.599
4	Bamboo Runners	0.043 0.043 0.022
	GRAND SUB TOTAL	6.79 6.951 6.783
TOTAL COST OF PROJECT IN LACS =		6.79 6.951 6.783

[Signature]
 20.11.21
 JE
 RWD

[Signature]
 20/11/2021
 AE
 RWD

[Signature]
 24.11.21
 EE
 RWD

As Per S.E. RWD (W) Circle Muz.
 Letter No 1179 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. RWD. (W) Division Muz East Mahmar

Technically Sanctioned for Rs. 6.79 lacs
 (Rs. Six lacs Seventy nine thousand) only
 (provisionally)

[Signature]
 27.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

[Signature]
 27.12.21

Name of the Road :- Muzaffarpur jila anatar gat P.W.D path hussepur chauk se hote hue hussepur P.M.G.S.Y pat						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat			
			Brick Bat			
			Providing and laying of Brick bats, including all taxes etc. all complete job as per specification and directions of E/I			
			As per M B copy annexed	Cum	261.54	2146.58
				Total	261.54	561418.53
2		WRD 10.7.40	Sand bags			
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I			
			As per M B copy annexed	No	1423.000	3932
				Total	1423.00	54429.75
3		WRD 5.7.7	Bamboo piling			
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I			
			As per M B copy annexed	M	1110.000	53.53
				Total	1110.00	71106.60
4		WRD 5.7.9	Bamboo RUNNERS			
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification			
			As per M B copy annexed	M	136.400	1611
				Total	136.40	4341.64
Total						695112.98

2245.14
 6782744
 679103.48
 20.11.22
 20.11.22
 20.11.22