



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- Sarvodaya High MMGSY[SC]hool Vishunpur Bandhangari
To Sonar Tola Jhitkahi

DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Sakra		
TOTAL LENGTH OF ROAD	:	2.110	KM
CONSTRUCTION COST	:	2.970 2.914	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

2918

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)


पथ का नाम : ~~स्मार्ट रोड स्कूल~~ mmbsr (sc) 001 विधुनपुर बल-राय
से सीनार रोड मिटकाड़ी

तात्कालिक मरम्मत
कार्य की राशि (लाख) : ~~2.47~~ 2.914 2.918

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु
Brick bat/ Bamboo piling/ Bamboo runners/ Local Sand Bag (EC Bags)/
1000mm RCC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल
हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर
विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


24/11/21
कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021
सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

1 Name of PIUs : EE, RWD (W) DIV - MUZAFFARPUR DISTRICT

2 Name of Block/Road : SAHARA / SARVODAYA HIGH SCHOOL VISHWANPUR
BAGHINAGRI TO SONAROLA JHITRAHI

A For Road

1 Damage Location/Chainage : 2 stretch damaged in 2nd km.

2 Damage Length : 0.048 km

3 Nature of Damage : Embankment damaged, breach in c/w
Brick Bats 121.63m³ Bamboo sunniss - Nil - Work is Satisfactory

4 Details of Restoration Works : Bamboo pile 3624 Sand Bag - 280

i Material being used in Restoration Works : Brick Bat, Sand Bag, Bamboo pile

ii Equipments/Tools being used in Restoration Works, MANUAL TOOL, TRACTOR, trailer.

iii Procedure Taken up in Restoration Works : Brick Bat filled in Breach & Bamboo

iv Restored Length : 0.048 km piling on edge of road with sand bag.

B For Bridge

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works

i Material being used in Restoration Works

ii Equipments/Tools being used in Restoration Works

iii Procedure Taken up in Restoration Works

iv Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)

Executive Engineer
RWD, Works Division, Muzaffarpur
RWD, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- Sarvodaya High MMGSY[SC]hool Vishunpur Bandhangari To Sonar Tola Jhitkahi

District Muzaffarpur
Block Sakra
Division Muzaffarpur East-1
Length of Road (in Km) 2.11

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	2.611 2.629 2.607
2	Sand bag	0.110 0.113
3	Bamboo Piles	0.232 0.194
	GRAND SUB TOTAL	2.918 2.970 2.914
TOTAL COST OF PROJECT IN LACS =		2.918 2.970 2.914

Abhinav
20.11.21

JE
RWD

Amir
20/11/2021

AE
RWD

Free
24.11.21
EE
RWD

As Per C.E. RWD, Muz Circle Muz

Letter No. 114/2021 dated 10/10/2021

Estimate has been verified by inspecting

E.E. RWD, (H) Division Muz East I Mahmar

Technically sanctioned for Rs. 2.918 lacs
(Rs. Two lacs ninety one thousand eight
hundred) only (provisionally)

Yb
27.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

27.12.21

Name of the Road :- Sarvodaya High MMGSY[SC]hool Vishunpur Bandhangari To Sonar Tola Jhikahi

Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	121.63	2146.83	260855.43
				Total	121.63	2146.18	262864.32
2		WRD1 0.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	287	39.22	1129.19
				Total	287	38.25	10977.75
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	362.000	53.59	19377.86
				Total	362.00	64.05	23489.72
Total							297031.79

As per M B copy annexed
20.1.24
JE

As per M B copy annexed
20.1.24
JE

201705-58

201380.01