



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- PMGSY Kutubpur to Kumhar tola (Mahto Tola)

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD : 0.910 KM

CONSTRUCTION COST : ~~8.355~~ 8.247 Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

8.258

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : PMGSY 44 कुतुबपुर से कुम्हार रोड (मडती रोड)

पथ की लम्बाई (km) : 0.91


तात्कालिक मरम्मति

कार्य की राशि (लाख) : ~~2.35~~ 3.258

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


कनीय अभियंता
कार्य प्रशाखा सकरा


सहायक अभियंता
अवर प्रमंडल सकरा


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE, RWD (W) Div MUZAFFARPUR EAST-1
2 Name of Block/Road SAKRAI PMGSY KUTUBPUR TO KUMHAR TOLA
(MAHATO TOLA)

A For Road

- 1 Damage Location/Chainage : MULTIPLE STRECH DAMAGED 250-800m ch.
2 Damage Length : 0.23 km
3 Nature of Damage : Breach in C/W & Embankment damaged
4 Details of Restoration Works : Bridge Bats = 367075, Bamboo pile 4455m runners = nil
Sand bag 358.0 nos. Work is satisfactory.
i Material being used in Restoration Works : Brick Bat, Sand Bag, Bamboo.
ii Equipments/Tools being used in Restoration Works : Tractor trailer, Tipper, roller, manual ramming
iii Procedure Taken up in Restoration Works : Brick Bat filled in Breach/damage
iv Restored Length : 0.23 km
recompacted to resume traffic.

B For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works
i Material being used in Restoration Works
ii Equipments/Tools being used in Restoration Works
iii Procedure Taken up in Restoration Works
iv Restored Length

Signature of JE/AE/EE

11/12/2021
me

11/12/21

Signature

(Name of Inspector)

Executive Engineer

R.W.D. Works Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- PMGSY Kutubpur to Kumhar tola (Mahto Tola)
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 0.91

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	7.879 7.833 7.868
2	Sand bag	0.137 0.141
3	Bamboo Piles	0.286 0.238
4	Bamboo Runners	0.000 0.000
	GRAND SUB TOTAL	8.253 8.355 8.247
TOTAL COST OF PROJECT IN LACS =		8.253 8.355 8.247

Ashutosh
 22.12.21
 JE
 RWD

Cut
 20/11/2021
 AE
 RWD

Shree
 24.11.21
 EE
 RWD

As Per S.E. RWD (M) Circle Muz.
 Letter No. 1178 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. RWD. (M) Division - Muzaffarpur

Technically Sanctioned for Rs. 8.258 lacs
 (Rs. Eight lacs twenty five thousand
 eight hundred) only (provisionally)

Sh
 27.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

Sh
 27.12.21

Name of the Road :- PMGSY Kutubpur to Kumhar tola (Mahito Tola)						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat			
			Brick Bat			
			Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I			
			As per M B copy annexed	Cum	367.07	727345.12
				Total	367.07	727345.12
2		WRD 10.7.40	Sand bags			
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I			
			As per M B copy annexed	No	358.000	14094.66
				Total	358.00	14094.66
3		WRD 5.7.7	Bamboo piling			
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I			
			As per M B copy annexed	M	445.250	23834.23
				Total	445.25	23834.23
Total						835520.56

Shubh
20.11.21
TE

Cud
20.11.21
TE

825873.81