



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- **Muzaffarpur Mahua Sadak to Chakdah Pachdahoi
Pashuram Pachdahi Tak**

DISTRICT **Muzaffarpur**

DIVISION **Muzaffarpur East-1**

BLOCK **Sakra**

TOTAL LENGTH OF ROAD	:	1.950	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	3.753 3.577	Lac
-------------------	---	---------------------------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

3-581

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : मुजफ्फरपुर हाइड्रो सेक्टर में चकड़ा पंचायत परधरपुर
पंचायत तक

पथ की लम्बाई (km) : 1.95


तात्कालिक मरम्मति

कार्य की राशि (लाख) : ~~3.53~~ ~~3.57~~ 3.581

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RGC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20.11.21

कनीय अभियंता
कार्य प्रशाखा सकरा


20.11.2021

सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE, RWD (W) Div- Muzaffarpur East 1
- 2 Name of Block/Road SAKRA / Muzaffarpur Mahua & dalk to Passurapur
pachdahi (VR34).
- A For Road
 - 1 Damage Location/Chainage 1 km 0-40 KM, 1.1-1.4 KM ch²
Muzaff. multiple reach damaged, embankment
Breach in C/W.
 - 2 Damage Length 0.142 KM
 - 3 Nature of Damage Multiple reach damaged, Embankment, most
C/W Breached.
 - 4 Details of Restoration Works : Bl/Bats = 122.25 m³ Sand Bag = 627 m. Bamboo pile = 123.50 m
Bamboo runness 122.50 m. Work is satisfactory.
 - i Material being used in Restoration Works Sand Bag, Bamboo, Brick Bat.
 - ii Equipments/Tools being used in Restoration Works Tractor-tipper tolly manual sanning
tools & JCB
 - iii Procedure Taken up in Restoration Works : Brick Bat filled into breach site &
Blank/brickbat further restored
& protected using sand bag &
Bamboo piling
 - iv Restored Length 0.142 KM
- B For Bridge
 - 1 Damage Location/Chainage
 - 2 Damage Length
 - 3 Nature of Damage
 - 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length

Signature of JE/AE/EE
11/12/21

Cell
11/12/21
11/12/21

Signature
(Name of Inspector)

Executive Engineer
R.W.D. Works Division, Mahua

GENERAL ABSTRACT

Name of the Road :-

Muzaffarpur Mahua Sadak to Chakdah Pachdahoi Pashuram Pachdahi Tak

District

Muzaffarpur

Block

Sakra

Division

Muzaffarpur East-1

Length of Road (in Km)

1.95

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	2.624 2.642 2.620
2	Sand bag	0.240 0.247
3	Bamboo Piles	0.816 0.682
4	Bamboo Runners	0.056 0.028
	GRAND SUB TOTAL	3.581 3.763 3.577
TOTAL COST OF PROJECT IN LACS =		3.581 3.763 3.577

Ashutosh
20.11.21
JE
RWD

Arund
20/11/2021
AE
RWD

Praveen
24.11.21
EE
RWD

As per S.E. RWD, Muzaffarpur

Letter No. 11/15/2021

Estimated cost of work

E. E. RWD. (W) Division ~~1442~~ East + Mahanar

Technically Sanctioned for Rs. 3-581 lacs
(Rs. Three lacs fifty eight thousand one
hundred) only (provisionally)

29.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

27.12.21

Name of the Road :- Muzaffarpur Mahua Sadak to Chakdah Pachdahoi Pashuram Pachdahai Tak						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat			
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I			
			As per M B copy annexed	Cum	122.25	262413.41
				Total	122.25	262413.41
2		WRD 10.7.4 0	Sand bags			
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I			
			As per M B copy annexed	No	627.000	24684.99
				Total	627.00	24684.99
3		WRD 5.7.7	Bamboo piling			
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I			
			As per M B copy annexed	M	1273.500	68130.46
				Total	1273.50	68130.46
4		WRD 5.7.9	Bamboo RUNNERS			
			Providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification			
			As per M B copy annexed	M	172.500	2839.35
				Total	172.50	2839.35
Total						375258.09

As per M B copy annexed
20/11/2024
PC

358114.2-1

55326.67
 25326.67