



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :-

Middle School Bairuadih to Harijan Tola

DISTRICT

Muzaffarpur

DIVISION

Muzaffarpur East-1

BLOCK

Sakra

TOTAL LENGTH OF ROAD

:

2.260

KM

CONSTRUCTION COST

:

~~6.092~~
5.977

Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

5.977

प्रतियेदन

शीर्षक : FDR Part A (Temporary Restoration)

पथ का नाम : 1. मध्य (अवधि) 1. 10/10/21 2. 10/10/21

पथ की लंबाई (km) : 0.105 km

तात्कालिक मरम्मत

कार्य की राशि (लाख) : 4.45 - 5.50

वर्ष 2021 में आगी बाद में क्षतिग्रस्त पथों के बर्धन यातायात को पुनः शुरू करने हेतु
Brick bat/ Bamboo piling/ Bamboo turners/ Local Sand Bag(EC Bags)/
100mm RCC Pipes से तात्कालिक मरम्मत कार्य कराया गया एवं अग्रिम पुनः स्थापना
हुआ।

सम्बन्धी निर्गत विभागीय निर्देशों के आश्रय में अग्रिम प्रावधानों एवं अनुमोदित दर
विश्रीयत करते हुए प्रावधान तैयार किया गया है। (मु. अ.नि. - 4275 - 22-10-21)

MIS एप्लीकेशन में की गयी ऑनसाइट प्रीयोर की प्रति संलग्न है।

M. J. S. ज. अ. नि. 174 प/ अ. नि. 3।
निमा 17/4 प/ अ. नि. 4555 दिनांक

कनीय अभियंता
20/10/21

कनीय अभियंता
कार्य प्रशाखा सकरा

सहायक अभियंता
अवर प्रमंडल सकरा

सहायक अभियंता
अवर प्रमंडल सकरा

कार्यपालक अभियंता
ग्रामीण कार्य विभाग

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date


- 1 Name of PIUs EE RWD (W) Div. Muzaffarpur East-1
- 2 Name of Block/Road SAKRAI Middle School Basmah to kharjan tola.

A For Road

- 1 Damage Location/Chainage : Damaged between 0.9 - 1.6 km length of road
- 2 Damage Length : 0.105 km
- 3 Nature of Damage : Embankment / crust damaged, breach in chw
- 4 Details of Restoration Works : B.P. = 247.20m² Bamboo pile 693.5m runners = 82.7m, Sand Bag = 722 Nos Work is satisfactory
- i Material being used in Restoration Works : Brick Bat, Sand Bag, Bamboo
- ii Equipments/Tools being used in Restoration Works : Roller, Tractor, tipper, 200, manual ramming
- iii Procedure Taken up in Restoration Works : Brick Bats used for filling breach & sandbag alongwith bamboo piled line were used to protect the embankment from further damage.
- iv Restored Length :

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length


Signature of JE/AE/EE

Call
11/12/2017
1-12-17


Signature
(Name of Inspector)

Executive Engineer
RWD, Muzaffarpur, Bihar
Executive Engineer
RWD, Muzaffarpur, Bihar

GENERAL ABSTRACT

Name of the Road :- Middle School Bairuadih to Harijan Tola
District Muzaaffarpur
Block Sakra
Division Muzaaffarpur East-I
Length of Road (in Km) 2.26

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	5.306 5.348 5.299
2	Sand bag	0.276 0.284
3	Bamboo Piles	0.447 0.373
4	Bamboo Runners	0.026 0.014
	GRAND SUB TOTAL	5.977 6.092 5.970
TOTAL COST OF PROJECT IN LACS =		6.092 5.970
		5.977 Lacs

Ashish Kumar
40.11.21
JE
RWD

Gul
20/11/2021
AE
RWD

Praveen
24.11.21
EE
RWD

As Per S.E. RWD (W) Circle Muz
Letter No 1175 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD. (W) Division 1442-ET-I Mahnar

Sanctioned
Technically Appraised for Rs. 5.977 Lacs (Rs. Five
Lacs ninety seven thousand seven hundred) only
(provisionally)

21.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaaffarpur

21.12.21

Name of the Road :- Middle School Bairuadih to Harijan Tola

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat				
			Providing and laying of Brick bats, including all taxes etc. all complete job as per specification and directions of E/I As per MB copy annexed	Cum	247.2	2143.41	529755.25
				Total	247.23	2146.58 2143.41 2146.58	530634.58 529755.25 534308.53
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per MB copy annexed	No	722.000	39.33	28435.14
				Total	722.00	39.25	27618.50
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per MB copy annexed	M	697.500	53.53	27337.18
				Total	697.50	53.06	44681.85
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per MB copy annexed	M	82.720	16.96	1281.52
				Total	82.72	31.83	2632.98
Total							609239.86

Azhar K
20.11.2017

597258.47

597239.17