



Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-

Bilandpur (Nagendra Ram's House) to R. Bhatadasi

DISTRICT

Vaishali

DIVISION

Mahua

BLOCK

Raja Pakar

TOTAL DAMAGED LENGTH OF ROAD

•

3.330

KM

CONSTRUCTION COST

• •

12.697

	Lac
--	-----

**Submitted By :-
Executive Engineer
RWD Work Division, Mahua**

प्रतिवेदन

कार्य का नाम:- बिन्तपुर नौल राम के घर से आर मथादासी

.....पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- राजापूर


वित्तीय वर्ष - 2021-22


प्राक्कलित राशि - Rs. 12.697 लाख


प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 12.697 लाख है,

....., प्रखंड-राजापूर में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4589 दिनांक 13/11/21 द्वारा दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है। MIS में प्रविष्टि की गई है (व्याख्याप्रति संलग्न)।


15/12/21
कनीय अभियंता


15/12/21
सहायक अभियंता


15.12.21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Inspection Report for Flood Damage Work

Date:- 21/12/2021

1 Name of PIUs :- Executive Engineer KWS, I.D. Mahua

2 Name of Block/Road :- Rajabakas/Bidandpur (Nagendram House to R. Bhatadasi)

(A) For Road:


1. Damage Location/Chainage :- 0 to 3 km
2. Damage Length :- 1 km
3. Nature of Damage :- Flood
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipment's/Tools being used in Restoration works:- Tractor, Road roller
 - (iii) Procedure taken up in Restoration works:- Filling brick bats
 - (iv) Restored Length :- 1 km


(B) For Bridge:


1. Damage Location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:-
 - (ii) Equipment's/Tools being used in Restoration works:-
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :-

N/A

Work found satisfactory


Signature of JE/AE/EE


AE


Signature


(Name of Inspection)

GENERAL ABSTRACT

Name of Road Bilandpur (Nagendra Ram's House) to R. Bhatadasi
District Vaishali
Block Raja Pakar
Division Mahua
Length of Road (in Km) 3.330 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	11.616
3	Sand Filling	1.081
4	Sand bag	0.000
5	H.P.	0.000
6	Bamboo piles	0.000
	SUB TOTAL	12.697
	GRAND SUB TOTAL	12.697


JE
RWD


AE
RWD


15.12.21
EE
RWD

As Per S.E. RWD (W) Circle Muz
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division

Technically Sanctioned for Rs. 12,697 Lacs
(Rs. Twelve Lacs Sixty nine thousand Seven
hundred) only (provisionally)


30.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur


30.12.21

SI. No.	SDB SL NO.	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1			Providing and Laying of Brick Bats Providing laying spreading & compacting Brick Bats including spreading in uniform thickness hand packing (Manual Means) As Per Appendix - I	Cum Total	562.65 562.65	2064.56	1161624.68
2		11.20	Local Sand Filling in foundation trenches as per drawing and technical specification Clause 305.3.9	Cum Total	189.580 189.58	569.96	108053.02
Total Cost :-							1269677.70

15/12/21
AE

15/12/21
AE

13.12.21