



Rural Works Department, Govt of Bihar

**DETAILED PROJECT REPORT FOR
FDR**



Sanichar Hat Rajapakar to Rajapakar Prakhand Hote
Hue Basra Chakrajo Part of T06

Vaishali

Mahua

Raja Pakar

KM

Lac	
-----	--

Submitted By :-
Executive Engineer
RWD Work Division, Mahua

प्रतिवेदन

कार्य का नाम:- शमिपर हाट राजापाकड से राजापाकड परकड होने डर
वसु चकाजे पटि 700 पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड:- राजापाकड
वित्तीय वर्ष - - 2021-22
प्राक्कलित राशि - Rs. 9.483 लाख

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 9.483 लाख है,
प्रखंड- राजापाकड में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4589 दिनांक 13/11/21 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है। MIS में प्रविष्टि की गई है (दृष्टाया प्रति संलग्न)।

15/11/21
कनीय अभियंता
JF

15/11/21
सहायक अभियंता

15.12.21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Inspection Report for Flood Damage Work

Date:- 21. 12. 2021

1 Name of PIUs :- Executive Engineer R.W.D. - Mahua.

2 Name of Block/Road :- Rajabakar/Sanichar Hat Rajabakar to Rajabakar Prakhanda
Hote hue Basara Chakrajo part of TOG

(A) For Road:

1. Damage Location/Chainage :- 80M to 2800M

2. Damage Length :- 266M

3. Nature of Damage :- Flood.

4. Details of Restoration Works :-

(i) Material being used in Restoration works:- Brick bats (84.83 m³)

(ii) Equipment's/Tools being used in Restoration works:- Tractor, Road Roller

(iii) Procedure taken up in Restoration works:

(iv) Restored Length :- 266M Telling brick bats.

(B) For Bridge:

1. Damage Location/Chainage :- NA

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works :-

(i) Material being used in Restoration works:-

(ii) Equipment's/Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:-

(iv) Restored Length :- Work found Satisfactory.

Signature of JE/AE/EE
15/12/21

Signature of JE/AE/EE
15/12/21
AE

Signature
21/12

(Name of Inspection)

E.E.
Hajipur.

GENERAL ABSTRACT

Name of Road Sanichar Hat Rajapakar to Rajapakar Prakhand Hote Hue Basra Chakrajo Part of T06

District Vaishali

Block Raja Pakar

Division Mahua

Length of Road (in Km) 3.000 Km

SI. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	8.681
3	Sand Filling	0.802
4	Sand bag	0.000
5	H.P.	0.000
6	Bamboo piles	0.000
	SUB TOTAL	9.483
	GRAND SUB TOTAL	9.483

[Signature]
15/12/21
JE
RWD

[Signature]
15/12/21
AE
RWD

[Signature]
13/12/21
EE
RWD

As Per S.E. RWD (W) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
F. E. RWD. (W) Division Hajipur

Technically Sanctioned for Rs. 9.483 lacs
(Rs. Nine lacs forty eight thousand three
hundred) only (provisionally)

[Signature]
30.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1			Providing and Laying of Brick Bats Providing laying spreading & compacting Brick Bats including spreading in uniform thickness hand packing (Manual Means) As Per Appendix - I	Cum	420.47		
			Total		420.47	2064.56	868085.54
2			Kiln Rubbish Filling in foundation trenches as per drawing and technical specification Clause 305.3.9	Cum	84.830		
			Total		84.83	945.10	80172.83
Total Cost :-							948258.37

15/11/24
AC

15/11/24
AC

15/12/24
AC