



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-

Bishanpur Balbhardarpur Gospur P. A. Chaksikandar
Mahua REO Path Pawan Singh Ke Ghar to Mahadalit
Tola Hote Hue Paswan Tola Rasulpur Bakhri Kabristan
Tak

DISTRICT	Vaishali		
DIVISION	Mahua		
BLOCK	Raja Pakar		
TOTAL DAMAGED LENGTH OF ROAD	:	0.040	KM
CONSTRUCTION COST	:	✓ 7.093	Lac

Submitted By :-
Executive Engineer
RWD Work Division, Mahua

7.092

प्रतिवेदन

कार्य का नाम:-

कार्य का नाम:- R.E.O रोड पथ पथ के दर से महाफिलिंग टोला टोले उर पावकान केला
रफूला परदर केविहान लो पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड—

प्रखण्ड- १ राजापाकड

वित्तीय वर्ष - - 2020-2021

प्राक्कलित राशि - Rs. - ~~7.093~~ lakh
7.092

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि

लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4589 दिनांक 13/11/21 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है। M15 में प्रविष्टि की गई है (प्रशासक प्रति संलग्न)।

कनीय अभियंता

15/12/24
सहायक अभियंता

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Inspection Report for Flood Damage Work

Date:- 21/12/2021

1 Name of PIUs :- Executive Engineer, RWD, WD Mahua

2 Name of Block/Road :- Rajabakas/Bishanpur Balbharadpur Hospur P.A Chak Sikandra
Mahua R.E.O Road Path Pawan Singh ke Ghar to Mahadehit
tola hote hue Pawan tala Kasutia Bakmi Kabristan tak

(A) For Road:

1. Damage Location/Chainage :- 0 to 100 m
2. Damage Length :- 20.1 m
3. Nature of Damage :- Approach wash out at culvert
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:- Brick bats (337 61 m³)
 - (ii) Equipment's/Tools being used in Restoration works:- Tractor, Road Roller
 - (iii) Procedure taken up in Restoration works:- Filling brick bats
 - (iv) Restored Length :- 20.1 m

(B) For Bridge:

1. Damage Location/Chainage :- 0 to 100 M
2. Damage Length :- (20 M)
3. Nature of Damage :-
4. Details of Restoration Works :-
 - (i) Material being used in Restoration works:-
 - (ii) Equipment's/Tools being used in Restoration works:-
 - (iii) Procedure taken up in Restoration works:-
 - (iv) Restored Length :-

N/A

Work found Satisfactory

Signature of JE/AE/EE
15/12/21
AE

Signature
15/12/21

(Name of Inspection)


E.E.
Hajipur


GENERAL ABSTRACT


Name of Road Bishanpur Balbhardarpur Gospur P. A. Chaksikandar Mahua REO Path Pawan Singh Ke Ghar to Mahadalit Tola Hote Hue Paswan Tola Rasulpur Bakhri Kabristan Tak
District Vaishali
Block Raja Pakar
Division Mahua
Length of Road (in Km) 0.040 Km

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	6.970
3	Sand Filling	0.122
4	Sand bag	0.000
5	H.P.	0.000
6	Bamboo piles	0.000
	SUB TOTAL	7.093
	GRAND SUB TOTAL	7.093

7.092
7.092



JE
RWD


AE
RWD


EE
RWD

As Per S.E. RWD (W) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division Hajipur

Technically Sanctioned for Rs. 7.092 Lacs (Rs. Seven Lacs ninety thousand two hundred) only (Provisionally)


30.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

30.12.21

SI. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTITY	RATE	AMOUNT (in Rs.)
1			Providing and Laying of Brick Bats Providing laying spreading & compacting Brick Bats including spreading in uniform thickness hand packing (Manual Means) As Per Appendix - I	Cum Total	337.61 337.61	2064.56	697016.10
2		11.20	Kil Rabish Filling in foundation trenches as per drawing and technical specification Clause 305.3.9	Cum Total	12.960 12.96	945.10	12248.50
3		WRD 5.7.40	Sand bag Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/	Nos Total	0.00	39.37	0.00
Total Cost :-							709264.60

15/12/21
AE

15/12/21
AE