



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

150

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Madhepur

Estimate for Mortable of the Road from Khoer Madanpur Daldal
to Bagahi Mahadalit Tol **FDR at Block- Madhepur** in
Madhubani District.

0.94278

TOTAL COST FOR MOTORABLE Rs.

~~1.46584~~ lac.

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- *Madhepur*

Name of Road :- *Khoer Madanpur Daldal to Bagahi Mahadali't*
to 1

A. For Road

1. Damage Location Chainage :- *350m, 400m*
2. Damage Length :- *50.00 m*
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- *Brick Bats*
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:- *30m - 39.80m*

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

grade 13'

[Signature]
29/04/22

Signature of JE/AE/EE

[Signature]
24/4/22
RE

[Signature]
29/4/22

Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Khoer Madanpur Daldal to Bagahi Mahadali to

प्राक्कलित राशि :- 1.46504 Lac

प्रमण्डल का नाम:- झांझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Khoer Madanpur Daldal to Bagahi Mahadali to पथ के लिए तैयार किया गया है, जो

कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवैदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता

सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झांझारपुर

**Estimate for Motorability of road damaged by flood from Khoer Madanpur Daldal to Bagahi
Mahadalit Tol For Year 2021**

end :- FDR 2245

Length :-0.664 km

Sl No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/L.	Cum	39.80 m ³ 61.80 <i>Ch</i>	2004.96	79797.41 123906.53

₹ 79797.41
~~1,23,906.53~~
 Add 12 % GST ₹ 9575.69
~~14,868.78~~
 Add 1 % L.C ₹ 797.97
~~1,239.07~~
 Add S. Fee (61.80 x 1032) x 10 % ₹ 4107.36
~~6,569.54~~
 Total ₹ 94278.43
~~1,46,583.72~~
 Say ₹ 94278.00
~~1,46,584.00~~

Junior Engineer
R.W.D, Works Section,
Madhepur

Assistant Engineer
R.W.D, Work sub Div.
Madhepur

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

कार्यपालक अभियंता, श्री ० को वि०, जयनगर
जयपुरात पत्रांक... 678... के द्वारा दिनांक 04/05/2022
के आधार पर।

Technically sanctioned for Rs. 94,278.00
Ninety four thousand two hundred seventy eight
Rupees Only.

Superintending Engineer
R.W.D Work Circle

Abhinav
07/05/22

Name of Road :- Khoer Madanpur Daldal to Bagahi Mahadalit Tol

MMGSY	Length :- 0.664 km	Block :- Madhepur
Appendix - I		
Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)		

Chainage	Nos.		Length (in Mtr.)		Bidth (in Mtr.)		Thickness (in Mtr.)		Quantity	
ch. 0	2	x	8.00	x	2.00	x	0.40 0.60	av. =	19.20	cum.
ch. 350	2		12.00		1.50		0.60	av. =	21.60	
ch. 400	1		10.00		2.80	1.20 x	0.75 0.45	av. =	21.00	5.40 m ³
							Total qty.	=	61.80	cum


30 m³

12.80 m³

39.80 m³
6 June/22
29/04/22

Junior Engineer
R.W.D, Works Section,
Madhepur


Assistant Engineer
R.W.D, Work sub Div.
Madhepur


Executive Engineer
R.W.D (W) Division,
Jhanjharpur


29/4/22