



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## 3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- Murgi Farm Chowk to Bariyarpur East Tola Tak

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD : 3.000 KM

CONSTRUCTION COST : ~~0.995~~  
0.946 Lac

Submitted By :- Executive Engineer  
RWD Work Division Muzaffarpur East-1

0.947

## प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration )

पथ का नाम : मुरगी फार्म चौक से बरवारपुर स्टेट रोड

पथ की लम्बाई (km): 3.0

तात्कालिक मरम्मति

कार्य की राशि (लाख):

~~0.490.946~~ 0.947


वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु

Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/

1000mm RGC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।

  
20/11/24

कनीय अभियंता  
कार्य प्रशाखा सकरा

  
20/11/24

सहायक अभियंता  
अवर प्रमंडल सकरा

  
24/11/24

कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
मुजफ्फरपुर, पूर्वी-1

## Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE, RWD (W) - Muzaffarpur East I
- 2 Name of Block/Road Muzi farm Chowk to Benyarpur  
east to lake


### A For Road

- 1 Damage Location/Chainage : Multiple reach in km 2-3 of the road.
- 2 Damage Length : 0.062 km
- 3 Nature of Damage : Embankment damaged due to flood.  
Breach at 2 location in C/W.
- 4 Details of Restoration Works : Brick Bat = 29.84 m<sup>3</sup>. Bamboo runner = Nil  
Bamboo pile = 439.5 m. Sandbag = 180. Work is Satisfactory.
- i Material being used in Restoration Works : Brick Bat, Bamboo pile, Sand Bag.
- ii Equipments/Tools being used in Restoration Works : Tractor, JCB, trolley, Hopper, manual rammer tool
- iii Procedure Taken up in Restoration Works : Brick Bat filled in Breach & damaged
- iv Restored Length 0.062 km part & Sand Bag with bamboo piling used for side protection.

### B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length

  
Signature of JE/AE/EE

  
1/12/2021  
  
7.12.21

  
Signature  
(Name of Inspector)  
Executive Engineer  
R.W.D. Works Division, Mahanagar

### GENERAL ABSTRACT

Name of the Road :- Murgi Farm Chowk to Bariyarpur East Tola Tak  
District Muzaffarpur  
Block Sakra  
Division Muzaffarpur East-1  
Length of Road (in Km) 3

| Sl. No.                         | DESCRIPTION     | AMOUNT (LAKHS)    |
|---------------------------------|-----------------|-------------------|
| 1                               | Brick Bat       | 0.641 0.645 0.640 |
| 2                               | Sand bag        | 0.069 0.071       |
| 3                               | Bamboo Piles    | 0.282 0.235       |
| 4                               | Bamboo Runners  | 0.000             |
|                                 | GRAND SUB TOTAL | 0.947 0.995 0.946 |
| TOTAL COST OF PROJECT IN LACS = |                 | 0.947 0.995 0.946 |

*[Signature]*  
20.11.21  
JE  
RWD

*[Signature]*  
20/11/2021  
AE  
RWD

*[Signature]*  
24.11.21  
EE  
RWD

As Per S.E. RWS (W) Circle Muz.  
Letter no. 11/18 Dated 01/10/2021  
Estimate has been formed by inspecting  
E.E. RWD (W) Division - Muzaffarpur East-1 Mahanagar

Technically Sanctioned for Rs. 0.947 lac  
(Rs. Ninety four thousand Seven hundred only)  
(provisionally)

*[Signature]*  
27.12.21  
Superintending Engineer  
Rural Works Department  
Work Circle, Muzaffarpur

*[Signature]*  
27.12.21

# Name of the Road :- Murgi Farm Chowk to Bariyarpur East Tola Tak

| Sl. No. | SDB<br>SL<br>.NO | MORD<br>Ref. No                         | Description                                                                                                                                                                                                          | Unit  | QUANTIT<br>Y | RATE                          | AMOUNT (in<br>Rs.)              |
|---------|------------------|-----------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|--------------|-------------------------------|---------------------------------|
| 1       |                  | 13.7<br>SoR<br>Bihar<br>Govt.<br>(1985) | Brick Bat                                                                                                                                                                                                            |       |              |                               |                                 |
|         |                  |                                         | Brick Bat<br>Providing and laying of Brick bats , including all taxes etc. all<br>complete job as per specification and directions of E/I                                                                            |       |              |                               |                                 |
|         |                  |                                         | As per M B copy annexed                                                                                                                                                                                              | Cum   | 29.84        | <del>2142.53</del><br>2142.53 | <del>63959.35</del><br>64053.95 |
|         |                  |                                         |                                                                                                                                                                                                                      | Total | 29.84        | 2142.18                       | 64489.61                        |
| 2       |                  | WRD<br>10.7.40                          | Sand bags                                                                                                                                                                                                            |       |              |                               |                                 |
|         |                  |                                         | Providing including labour for filling empty cement bag with local<br>sand, stitching the bag and placing including supply of sutali etc. all<br>complete as per approved design, specification and direction of E/I |       |              |                               |                                 |
|         |                  |                                         | As per M B copy annexed                                                                                                                                                                                              | No    | 180          | <del>39.37</del><br>39.37     | <del>7097.2</del><br>7097.2     |
|         |                  |                                         |                                                                                                                                                                                                                      | Total | 180          | 38.25                         | 6897.24                         |
| 3       |                  | WRD<br>5.7.7                            | Bamboo piling                                                                                                                                                                                                        |       |              |                               |                                 |
|         |                  |                                         | Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles<br>in size with making shoes and driving etc. complete job as per<br>specification and direction E/I                                                |       |              |                               |                                 |
|         |                  |                                         | As per M B copy annexed                                                                                                                                                                                              | M     | 439.500      | <del>53.53</del><br>53.53     | <del>23526.44</del><br>23526.44 |
| Total   |                  |                                         |                                                                                                                                                                                                                      | Total | 439.50       | 64.06                         | 28154.37                        |
|         |                  |                                         |                                                                                                                                                                                                                      |       |              |                               | 99541.22                        |

Abhishek  
25  
20.11.24

Arundhan  
20.11.24  
DE

94679.59

94524.99