



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- YOGINI GANGA PMGSY MD.SATTAR KE GHAR SE
MUSHARWA POKHA HOTE HUE to METHAURA TAK

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD	:	1.730	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	1.904 1.871	Lac
-------------------	---	---------------------------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

1.873

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : योशोगीगोसा एम्बेस्य सह स्टाट के थो ह
सुम्हरेका पोका थो ह मेमोरतक


पथ की लम्बाई (km) : 1.73

तात्कालिक मरम्मति
कार्य की राशि (लाख) : ~~1.904~~ 1.871 1.873 (Lakhs)

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर माँड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


कनीय अभियंता
कार्य प्रशाखा सकरा


सहायक अभियंता
अवर प्रमंडल सकरा


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE, RWD (W) DIV OMENKAPPOUR (CASE 1)
- 2 Name of Block/Road SAKRA Mogini gunge pms se md. Sakhar ke ghar se mushhama pokhar hote hue methaura tal.
- A For Road
- 1 Damage Location/Chainage 1.500 - 1.730 Km ch
- 2 Damage Length : 0.055 Km
- 3 Nature of Damage : Embankment, rust, C/W damaged
- 4 Details of Restoration Works Blat = 79.03 m³ Blat runners = 2.0 m Sand Bag 225 m³ Bamboo pile 8 - 225 m. Work is satisfactory
- i Material being used in Restoration Works Bridge Bat, Sand Bag, Bamboo.
- ii Equipments/Tools being used in Restoration Works Tractor, JCB, Jabor manual tools.
- iii Procedure Taken up in Restoration Works Bridge Bat filled into the breach. Bamboo pile & sand bag used to protect further from river beside road.
- iv Restored Length 0.055 Km
- B For Bridge
- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length 0

Signature of JE/AE/EE

[Signature]
11/12/2021
01.12.21

Signature

(Name of Inspector)

[Signature]
12/12/21
Executive Engineer
RWD. War. ...

GENERAL ABSTRACT

Name of the Road :-

District

Block

Division

Length of Road (in Km)

YOGINI GANGA PMGSY MD.SATTAR KE GHAR SE MUSHARWA POKHA HOT

Muzaffarpur

Sakra

Muzaffarpur East-1

1.73

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	
2	Sand bag	1.636 1.708 1.694
3	Bamboo Piles	0.080 0.089
4	Bamboo Runners	0.100 0.083
		0.010 0.005
	GRAND SUB TOTAL	
TOTAL COST OF PROJECT IN LACS =		1.873 1.904 1.871
		1.873 1.904 1.871

Ashutosh
JE
20-11-21
RWD

Chit
20/11/2021
AE
RWD

Shree
24.11.21
EE
RWD

As Per S.E. RWD (W) Circle Muz.
Letter No. 1179 dt. 05/10/2021
Estimate has been verified by inspecting
E.E. RWD. (W) Division - Muz. East Mahanagar

Technically Sanctioned for Rs. 1.873 Lacs
(Rs. one Lacs eighty seven thousand three
hundred) only (provisionally)

Sh
27.12.21
Superintending Engineer
Rural Works Department

Circle, Muzaffarpur
Sh
27.12.21

Name of the Road :- YOGINI GANGA PMGSY MD.SATTAR KE GHAR SE MUSHARWA POKHA HOTE
HUE to METHAURA TAK

HUE to METHAURA TAK

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I As per MB copy annexed	Cum Total	79.03 79.03	2146.58 8183.41 8181.18	169644.22 169393.69 170798.08
2		WRD 10.7.40	Sand bags Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per MB copy annexed	No Total	225.000 225.00	39.37 38.25	8858.25 8606.25
3		WRD 5.7.7	Bamboo piling Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I As per MB copy annexed	M Total	155.750 155.75	53.53 64.06	8337.30 9977.39
4		WRD 5.7.9	Bamboo RUNNERS providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification As per MB copy annexed	M Total	31.000 31.00	1846 31.83	570.26 986.73
Total							190368.38 187099.50 187350.03

A. Bhatia
20.11.14
SE

Arvind
20/11/14
SE