



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- **MMGSY SADAK to CHINTAWANPUR AGHWARA KADAUNA NADI TAK**

DISTRICT **Muzaffarpur**

DIVISION **Muzaffarpur East-1**

BLOCK **Sakra**

TOTAL LENGTH OF ROAD	:	0.738	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	3.548 3.400	Lac
-------------------	---	---------------------------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

3.404

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : MMGSY ~~सड़क से~~ ~~म-119 नहर~~ ~~अधवार~~ ~~का~~ ~~नदी~~ ~~तक~~

पथ की लम्बाई (km): 0.738

तात्कालिक मरम्मत
कार्य की राशि (लाख): ~~3.518~~ ~~3.40~~ 3.404


वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20.11.24

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2024

सहायक अभियंता
अवर प्रमंडल सकरा


25/11/24

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE, RWD(W) - Div - MURAFFARPUR EAST
2 Name of Block/Road SAKRA / CHINTAWANPUR AGHWARA KADANE MADITAK

A For Road

- 1 Damage Location/Chainage Throughout road length & block damaged.
2 Damage Length 0.185 KM
3 Nature of Damage : Embankment damaged (River bank).
4 Details of Restoration Works : Brick Bat = 108.78 m³ Bamboo pile 11425 m runness : 146.6 m
NP3 1000mm dia pipe = nil Sand Bag = 1127 nos. Work is Satisfactory
i Material being used in Restoration Works : Brick Bat, Sand Bag, Bamboo
ii Equipments/Tools being used in Restoration Works Tractor, Tipper, Bailer, manual tools.
iii Procedure Taken up in Restoration Works Brick Bat filled in breach & Sand Bag used behind Bamboo pile to hold the embankment and water striking embk
iv Restored Length 0.185 Km

B For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works
i Material being used in Restoration Works
ii Equipments/Tools being used in Restoration Works
iii Procedure Taken up in Restoration Works
iv Restored Length

[Signature]
Signature of JE/AE/EE

[Signature]
1/12/2024

[Signature]
1.12.24

[Signature]
Signature
(Name of Inspector)

[Signature]
Executive Engineer
R.W.D. Works Division, Malina

GENERAL ABSTRACT

Name of the Road :- MMGSY SADAK to CHINTAWANPUR AGHWARA KADAUNA NADI TAK
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 0.738

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	2.334 2.250 2.334
2	Sand bag	0.431 0.431 0.431
3	Bamboo Piles	0.720 0.720 0.720
4	Bamboo Runners	0.047 0.047 0.047
	GRAND SUB TOTAL	3.404 3.548 3.404
TOTAL COST OF PROJECT IN LACS =		3.404 3.548 3.404

[Signature]
 20.11.21
 JE
 RWD

[Signature]
 20/11/2021
 AE
 RWD

[Signature]
 24.11.21
 EE
 RWD

As Per S.E. RWD (W) Circle Muz.
 Letter No 1179 Batoa 01/10/2021
 Estimate has been verified by inspecting
 E. E. RWD. (W) Division - *Maharaj*

*Technically Sanctioned for Rs. 3.404 lacs (Rs. Three
 lacs forty thousand four hundred) only (provisionally)*

[Signature]
 27.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

[Signature]
 27.12.21

Name of the Road :- MMGSY SADAK to CHINTAWANPUR AGHWARA KADAUNA NADI TAK							
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	108.73	2146.58	2333397
				Total	108.73	2143.47	2335297
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	1127	39.37	44369.99
				Total	1127	38.25	43407.75
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	1124.250	53.53	60181.0
				Total	1124.25	64.06	72049.48
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per M B copy annexed	M	146.600	1646	2413.04
				Total	146.60	31.83	4666.28
Total							354778.58

Signature
20.11.21

Signature
20.11.21

34001740

340361.77

233397.64

2146.58

23352.97

2143.41

234985.10

2161.18

4369.99

3937

43407.75

38.25

6081.0

53.53

72049.48

64.06

2413.04

1646

4666.28

91.83

354778.58