



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- PRATHMIK VIDAYLAY to BHANGHA NOON NADI

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD : 0.815 KM

CONSTRUCTION COST : 4.507 Lac
4.38

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

4.38

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : प्राथमिक विद्यालय से बंगहा बून नदी तक
पथ की लम्बाई (km) : 0.815


तात्कालिक मरम्मति

कार्य की राशि (लाख) : ~~4.544~~ 4.376 4.381

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


25.11.21

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021

सहायक अभियंता
अवर प्रमंडल सकरा


29.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date


- 1 Name of PIUs EE, RWD (W) Div - Muzaffarpur East
- 2 Name of Block/Road SAKRA prathamik vidyalay to Bhangha noon nadi
tak.


A. For Road

- 1 Damage Location/Chainage at 0 km ch to 110m & 600-700 m ch.
- 2 Damage Length 0.135 km
- 3 Nature of Damage Embankment, crust damaged due to flood
- 4 Details of Restoration Works
Brick Bat = 161332, Bamboo pile = water mark (beyond river) 897m & summer = 107.2m
Said Bag = 849 mts. Work is satisfactory
- i Material being used in Restoration Works Brick bat, Sand Bag, Bamboo piling.
- ii Equipments/Tools being used in Restoration Works Tractor, tipper, trailer, JCB, manual ramming tool.
- iii Procedure Taken up in Restoration Works Bridge Bat filled in cut/damage
- iv Restored Length 0.135 km site & flank embankment / Brick Bat protected using sand Bag with Bamboo piling.

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length


Signature of JE/AE/EE


1/12/2021


1.12.21


Signature
(Name of Inspector)


GENERAL ABSTRACT

Name of the Road :- PRATHMIK VIDAYLAY to BHANGHA NOON NADI
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 0.815

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	3.573 3.549 3.549
2	Sand bag	0.326 0.334 0.334
3	Bamboo Piles	0.575 0.480 0.480
4	Bamboo Runners	0.034 0.018 0.018
	GRAND SUB TOTAL	4.507 4.381 4.381
TOTAL COST OF PROJECT IN LACS =		4.507 4.381 4.381

Ashutosh
20/11/21
JE
RWD

Chand
20/11/2021
AE
RWD

Shree
24.11.21
EE
RWD

As Per S.E. RWD (W) Circle Muz.
 Letter No. 1179 Dated 01/10/2021
 Estimated cost verified by inspecting
 E.E. RWD. (W) Division *East + Muzaffarpur*
Technically Sanctioned for Rs. 4.381 lacs
(Rs. Four lacs thirty eight thousand
and hundred) only (provisionally)

27.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

Name of the Road :- PRATHMIK VIDAYLAY to BHANGHA NOON NADI

Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	165.33	2161.18	354834.07
				Total	165.33		354834.98
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	849	323.37	325425.13
				Total	849	323.37	325425.13
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	897.000	53.53	48016.47
				Total	897.00	53.53	48016.47
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per M B copy annexed	M	107.200	1646	1764.57
				Total	107.20	1646	1764.57
Total							450656.14

437576.03

Prathmik
20.11.2021
w/o
20.11.2021

435102.12