



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- **JAGDISHPUR BAGHNAGRI L056 to VISHUNPUR
BAGHNAGRI HARIJAN TOLA**

DISTRICT **Muzaffarpur**

DIVISION **Muzaffarpur East-1**

BLOCK **Sakra**

TOTAL LENGTH OF ROAD : 3.008 KM

CONSTRUCTION COST : ~~4.877~~ **4.695** Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

4.70

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : अजगरीशपुर बन्धनगरी- 1056 से निशुनपुर बन्धनगरी हरिजन रोसा

पथ की लम्बाई (km) : 3.008


तात्कालिक मरम्मत

कार्य की राशि (लाख) : ~~4.892~~ 4.695 4.70

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/21
कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021
सहायक अभियंता
अवर प्रमंडल सकरा


24-11-21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE RWD(W) DIV - MUZAFFARPUR EAST-1
2 Name of Block/Road : SAKA / JAGDISHPUR BASHNAGRI Losh SE
NISHUNPUR BASHNAGRI HARDANTOLA TAK

A For Road

- 1 Damage Location/Chainage : MULTIPLE LOCATION IN 2nd & 3rd km.
2 Damage Length : 0.215 km
3 Nature of Damage : Embankment damaged.
4 Details of Restoration Works : Brick Bat = 154.69 m³ Bamboo pile = 1493.75 m
Sunness = 85.70 m. Sand Bag = 1438 No. Work is Satisfactory
i Material being used in Restoration Works : Brick Bat, Sand Bag, Bamboo pile
ii Equipments/Tools being used in Restoration Works : Tipper, Tractor, Trailer, manual tool
iii Procedure Taken up in Restoration Works : Brick Bat filled into ditches / cut / damaged
iv Restored Length : 0.215 km part. flank protected by Bamboo
pile + sand bag protection.

B For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works
i Material being used in Restoration Works
ii Equipments/Tools being used in Restoration Works
iii Procedure Taken up in Restoration Works
iv Restored Length

Signature of JE/AE/EE

[Signature]
11/12/2021
JE

Signature

(Name of Inspector)

[Signature]
Executive Engineer
R.W.D. Works Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- JAGDISHPUR BAGHNAGRI L056 to VISHUNPUR BAGHNAGRI HARIJAN TOLA
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 3.008

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	
2	Sand bag	3.820 2.343 3.216
3	Bamboo Piles	0.650 0.566 0.566
4	Bamboo Runners	0.937 0.8 0.8
		0.027 0.014 0.014
	GRAND SUB TOTAL	
TOTAL COST OF PROJECT IN LACS =		4.70 4.877 4.695
		4.70 4.877 4.695

[Signature]
 JE
 RWD

[Signature]
 AE
 RWD

[Signature]
 EE
 RWD

As Per S.E. RWD (M) Circle Muz.

Letter No. 1178 Dated 01/10/2021

Estimate has been verified by inspecting

E.E. RWD. (M) Division Muzaffarpur

Technically Sanctioned for Rs. 4.70 lacs (Rs. Four
 lacs seventy thousand) only (provisionally)

[Signature]
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

[Signature]
 27.12.21

Name of the Road :- JAGDISHPUR BAGHNAGRI L056 to VISHUNPUR BAGHNAGRI HARIJAN TOLA

Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	154.69	2140.53	332054.46
				Total	154.69	2140.53	332054.46
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	1438	39.37	56614.06
				Total	1438	39.37	56614.06
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	1493.750	53.53	79960.47
				Total	1493.75	53.53	79960.47
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per M B copy annexed	M	85.700	16.46	1410.62
				Total	85.70	16.46	1410.62
Total							
							487733.89

20.11.21

20/11/21

470033.58

469549.21