

ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :-		BARIYARPUR KANDH ME BHUNESHWAR RAY KE GHAR SE to HARIJAN TOLA NOON NADI TAK		
DISTRICT		Muzaffarpur		
DIVISION		Muzaffarpur East-1		
BLOCK		Sakra		
TOTAL LENGTH OF ROAD		:	1.435	KM
CONSTRUCTION COST		:	2.110 2.053	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

2.053

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : बरवाटपुर काँध में गुजेश्वर राय के घर से हरिजन रोला
-तक सीतक

पथ की लम्बाई (km) : 1.435 KM

तात्कालिक मरम्मति
कार्य की राशि (लाख) : ~~2.051~~ 2.053

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु
Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/
1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल
हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर
विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/21

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021

सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1


Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EG, RWD(W) MUZAFFARPUR EAST I
- 2 Name of Block/Road : SAICRAI BARIYARPUR KANDIA ME BHUNESWAR
RAY KE GHAR & HARIDANTOLA TAK.
- A For Road
 - 1 Damage Location/Chainage : 0.7 - 0.9 KM ch
 - 2 Damage Length : 0.095 KM
 - 3 Nature of Damage : Embankment damaged.
 - 4 Details of Restoration Works : Brick Bat = 72.21 m³ Bamboo runners = nil
Bamboo pile = 505 m Sand Bag = 59 nos. Work is Satisfactory
 - i Material being used in Restoration Works : Brick Bat, sand Bag, Bamboo pile
 - ii Equipments/Tools being used in Restoration Works : Manual tool, Tractor, tipper etc
 - iii Procedure Taken up in Restoration Works : Brick Bat filled in damaged portion
 - iv Restored Length : 0.095 KM after piling bamboo & fencing with sand bag.

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length


Signature of JE/AE/EE


11/12/2017


21-12-17


Signature

(Name of Inspector)


Executive Engineer
R.W.D. Works Division, Munger

GENERAL ABSTRACT

Name of the Road :- BARIYARPUR KANDH ME BHUNESHWAR RAY KE GHAR SE to HARIJAN TOLA NOON NADI TAK

District Muzaffarpur
Block Sakra
Division Muzaffarpur East-1
Length of Road (in Km) 1.435

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	1.550 1.561 + 548
2	Sand bag	0.226 0.226 0.233
3	Bamboo Piles	0.324 0.324 0.270
4	Bamboo Runners	0.000
	GRAND SUB TOTAL	2.053 2.110 2.051
TOTAL COST OF PROJECT IN LACS =		2.110 2.110 2.051

2.053

Arbittler
2.11.21

JE
RWD

Arbittler
20/11/2021

AE
RWD

Arbittler
24.11.21

EE
RWD

As Per S.E. RWD (W) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD. (W) Division - Muzaffarpur

Technically Sanctioned for Rs. 2.053 lacs (Rs. Two
lacs five thousand three hundred) only (provisionally)

Arbittler
27.12.21
Superintending Engineer
Rural Works Department
Work Circle Muzaffarpur

Name of the Road :- BARIYARPUR KANDH ME BHUNESHWAR RAY KE GHAR SE to HARIJAN TOLA NO						
Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat			
			Brick Bat			
			Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I			
			As per M B copy annexed	Cum	72.21	155004.54
				Total	72.21	155004.54
2		WRD 10.7.40	Sand bags			
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I			
			As per M B copy annexed	No	591	23267.67
				Total	591	22605.75
3		WRD 5.7.7	Bamboo piling			
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I			
			As per M B copy annexed	M	505.000	27032.65
				Total	505.00	32360.30
Total						211014.86

As per
20.11.24
20

As per
20.11.24
20

205304.86