



ग्रामीण कार्य विभाग

RURAL WORKS DEPARTMENT, GOVT OF BIHAR

DETAILED PROJECT REPORT FOR FDR 2021-2022



Name of Road :-	MADHUBAN P.W.D PATH MADHYA VIDHALAY BARA GOBIND SE TELI TOLA BARA GOBING		
DISTRICT	EAST CHAMPARAN		
DIVISION	CHAKIA		
BLOCK	CHAKIA		
TOTAL LENGTH OF ROAD	1.5	KM	
COST OF RECTIFICATION	4.643	5.038	LAC

Inspection Report For Flood Damage Work


Date

1. Name Of PIUs - Executive Engineer, RWD; Chakia,
2. Name Of Block - Chakia,
3. Name Of Road - Madhuban PWD Road Madhya vidhalew Bara-gobind to
Tel' tola Baragobind,

(A) For Road

1. Damage Location /Chainage - 1400 - 1500 mtr
2. Damage Length - 60 mtr.
3. Nature of Damage - Poths due to heavy rain & water logging
4. Details of Restoration Works
 - (i) Materials being used in restoration - B. Dol
 - (ii) equipments/ Tools being used in Restoration Work - Tractor, JCB, Roller
 - (iii) Procedure taken up in restoration works
 - (iv) Restored length - ~~96 mtr~~ 96 mtr.

Work found satisfactory.


6/2/2022
Signature Of Inspecting Officer

प्रतिवेदन

कार्य का नाम :- Madhuban P.W.D Road Madhya Vidhaley Boragobind to

TeLi tola Boragobind.....पथ मे अप्रत्याशित बाढ़ / अतिवृष्टि 2021 से क्षतिग्रस्त पथ में यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड :- चकिया

वित्तीय वर्ष : 2021-2022

प्रकल्पित राशि :-

प्रस्तुत प्राक्कलन, जिसकी प्रकल्पित राशि 5.03 लाख है, प्रखण्ड चकिया में यातायात बहाली हेतु आपातकालीन मरम्मत के लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4275 दिनांक 22/10/21 द्वारा दिये गए निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त भाग में brick Bats & Local sand भरकर पथ को चालू करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसकी घटनोत्तर स्वीकृति अपेक्षित है।

Abhi
23/10/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा चकिया

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल चकिया

23/10/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल चकिया

GENERAL ABSTRACT OF COST FOR FDR

Name of road MADHUBAN P.W.D PATH MADHYA VIDHALAY BARA GC
 District EAST CHAMPARAN
 Block CHAKIA
 Division CHAKIA
 length of road (in Km) 1.5

SL NO	DESCRIPTION	AMOUNT (LAKHS)
1	Excavation in soil using hydraulic excavator	454825
2	Brick bats	489,384.00
3	Sand filling	9488 14,395.00
4	Sand bags	.
5	Bamboo piles	

Total

INR 503,779.00
464293=

503 - 464300 =

Abw
23/10/24

Junior Engineer
Rural Works Department
Work Section,
Chakia

Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

Executive Engineer
Rural Works Department
Works Division,
Chakia

23/10/24

Post facto T.A/T S is accorded for Rs. 464300
 (.....crore.....lacs.....thousand
 Three hundred.....) only

S.E. (R.W.D)
works Circle
Motihari

SL NO.	SBD SL NO.	MORD REF NO.	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT (IN RS.)
1	3.5	302(iii)	Excavation in soil using Hydraulic Excavator excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting only and as per Technical Specification Clause 302.3				
			Appendix -I	cum	0	112.47	0
2			Brick Bats laying Brick Bats in ditches as per direction and specification with all complete job				
			Appendix -II	cum	237.52	1914.89	454825.22
			Sand Filling			2060.40	489384
			Filling in foundation trenches as per drawing and technical specification clause 305.3.9				
3			Appendix -III	cum	31.3	302.50	9468.25
						459.91	14395

Name of Road :- MADHUBAN P.W.D PATH MADHYA VIDHALAY BARA C

Block :- CHAKIA

Appendix - III

sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thicknes s(M)	Av. Thicknes s (M)	quantity (Cum)
1		1	18.00		2.25		0.100	4.050
1		1	7.50		2.00		0.100	1.500
1		1	7.50		2.50		0.100	1.875
1		1	10.00		4.00		0.100	4.000
1		1	12.00		4.00		0.100	4.800
1		1	12.00		4.50		0.100	5.400
1		1	15.00		4.25		0.100	6.375
1		1	12.00		2.75		0.100	3.300

Total 31.300

Obw
23/10/21
Junior Engineer
Rural Works Department
Work Section,
Chakia

Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

[Signature]
23/10/21
Executive Engineer
Rural Works Department
Works Division,
Chakia

Name of Road :- MADHUBAN P.W.D PATH MADHYA VIDHALAY BARA GOBIND SE
TELI TOLA BARA GOBIND

Block :- CHAKIA

Appendix - II

sl no	Chainage	no	Length	Width (M)	Avg. Width (M)	Thickness (M)	Av. Thicknes s (M)	quantity (Cum)
1		1	18.00		2.25		1.500	60.750
1		1	7.50		2.00		1.000	15.000
1		1	7.50		2.50		1.500	28.125
1		1	10.00		4.00		1.250	50.000
1		1	12.00		4.00		0.950	45.600
1		1	12.00		4.50		0.225	12.150
1		1	15.00		4.25		0.225	14.344
1		1	14.00		2.75		0.300	11.550

Total **237.52**

Abw
23/10/21

Junior Engineer
Rural Works Department
Work Section,
Chakia

Assistant Engineer
Rural Works Department
Work Sub Division
Chakia

23/10/21

Executive Engineer
Rural Works Department
Works Division,
Chakia