

ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- Chhapra Chouk - Maricha Road to Laxmipur

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD	:	1.629	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	1.554 1.520	Lac
-------------------	---	---------------------------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

1.531

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : छपरा चौक मरीचा रोड से लक्ष्मीपुर

पथ की लम्बाई (km) : 1.629


तात्कालिक मरम्मत

कार्य की राशि (लाख) : ~~1.55~~ 1.53

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RGC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20.11.21

कनीय अभियंता
कार्य प्रशाखा सकरा


20.11.21

सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE, RWD(W) Div - MUZAFFARPUR EAST-1
- 2 Name of Block/Road : SAKRA/CHHAPRA CHOWK TO MARICHA ROAD TO LAXMIPUR.

A For Road

- 1 Damage Location/Chainage : 1500 - 1620 m. ch.
- 2 Damage Length : 0.042 KM
- 3 Nature of Damage : Embankment, crest damaged
- 4 Details of Restoration Works : Brick Bat = 66.04 m³ Bamboo pile = 94.25 m Sand Bag = 152
Bamboo runners = 25.10 m Work is Satisfactory
- i Material being used in Restoration Works : Brick Bat, EC Bag filled with L sand, Bamboo runner, pile etc
- ii Equipments/Tools being used in Restoration Works : Tractor, trolley, manual labour.
- iii Procedure Taken up in Restoration Works : Breach/damaged filled with Brick Bat after enclosing the line with sand bag & bamboo piling.
- iv Restored Length : 0.042 KM

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)


Forwards Engineer

Works Division, Muzaffarpur


GENERAL ABSTRACT

Name of the Road :- Chhapra Chouk - Maricha Road to Laxmipur
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 1.629

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	1.417 1.427 1.416
2	Sand bag	0.058 0.058 0.060
3	Bamboo Piles	0.060 0.060 0.050
4	Bamboo Runners	0.008 0.008 0.004
	GRAND SUB TOTAL	1.531 1.554 1.530
TOTAL COST OF PROJECT IN LACS =		1.554 1.530
		1.531


 JE
RWD


 AE
RWD


 EE
RWD

As Per S.E. RWD (W) Circle Muz
 Letter No. 1179 Dated 01/10/2021
 Estimate has been verified by inspecting
 E. E. RWD. (W) Division *Not in order*

*Technically Sanctioned for Rs. 1.531 lacs (Rs. one
 lakh fifty three thousand one hundred) only
 (provisionally)*


 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

Name of the Road :- Chhapra Chouk - Maricha Road to Laxmipur

Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	66.04	2145.47	141766.47
				Total	66.04	2161.18	141550.80 141760.14
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	152.000	39.37	5984.24
				Total	152.00	38.25	5844.00
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	94.250	53.53	5045.20
				Total	94.25	64.06	6037.66
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per M B copy annexed	M	25.100	16.46	413.15
				Total	25.10	34.83	798.93
Total							156374.92 153202.73

As per M B copy annexed
20.11.21
26

Sub total
20/11/2021