



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- L039- Bariyarpur Kandh To Paigamberpur (Patel Chowk) to Paigamber Pur High School Tak

DISTRICT	Muzaffarpur
DIVISION	Muzaffarpur East-1
BLOCK	Sakra
TOTAL LENGTH OF ROAD	: 1.353 KM
CONSTRUCTION COST	: 5.421 Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

S. 177
5.203

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : 2039-4 रियारपुर काँध से पेंगमरपुर (पहल-चोक) से पेंगमरपुर हाई स्कूल तक

पथ की लम्बाई (km): 1.353


तात्कालिक मरम्मत

कार्य की राशि (लाख): ~~5.42~~ 5.197 5.203

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 4000mm RCC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/21

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021

सहायक अभियंता
अवर प्रमंडल सकरा


21/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE, RWD (W) DIV - MUZAFFARPUR EAST-1
- 2 Name of Block/Road : SAICRA/ W39 Baniyarpur kandi to paigambarpur
(patel chowk) to paigambarpur high school talu

A For Road

- 1 Damage Location/Chainage : various location in the road length
- 2 Damage Length : 0.242 km
- 3 Nature of Damage : Embankment damaged at multiple locations.
- 4 Details of Restoration Works : B. Bat = 18127 nos. Bamboo runner = 191.60 m Sand Bag = 103
Bamboo pile = 1647.0 m. Work is satisfactory.
- i Material being used in Restoration Works : Bridge Bat, sand bag, bamboo.
- ii Equipments/Tools being used in Restoration Works Roller, Tractor, Tipper trucks, manual tools etc
- iii Procedure Taken up in Restoration Works Bridge Bat filled in damaged portion &
- iv Restored Length : 0.242 km bamboo pile driven for holding back
Bat & sand bag.

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length

Ashwini
11/12/17
Signature of JE/AE/EE

C. S. D.
11/12/2017
AE

1-12-17

A. M. R.
Signature
(Name of Inspector)

Executive Engineer
RWD Works Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- L039- Bariyarpur Kandh To Paigamberpur (Patel Chowk) to Paigamber Pur High Sc
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 1.353

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	3.830 3.818 3.885
2	Sand bag	0.387 0.387 0.399
3	Bamboo Piles	1.055 1.055 0.882
4	Bamboo Runners	0.061 0.061 0.032
	GRAND SUB TOTAL	5.203 5.421 5.197
TOTAL COST OF PROJECT IN LACS =		5.203 5.421 5.197

Adhikari
 20.11.21
 JE
 RWD

and
 20/11/2021
 AE
 RWD

and
 24.11.21
 EE
 RWD

As Per S.E. RWD (W) Circle Muz
 Letter No 1179 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. RWD. (W) Division, Muzaffarpur East-1 Mahanar

*Technically Sanctioned for Rs. 5.203 lacs
 (Rs. Five lacs twenty thousand three hundred
 only) (provisionally)*

27.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

27.12.21

Name of the Road :- L039- Bariyarpur Kandh To Paigamberpur (Patel Chowk) to Paigamber Pur High School T						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat			
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I			
			As per M B copy annexed	Cum	181.27	388535.93
				Total	181.27	388535.93
2		WRD 10.7.40	Sand bags			
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I			
			As per M B copy annexed	No	1013	3981.81
				Total	1013	3981.81
3		WRD 5.7.7	Bamboo piling			
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I			
			As per M B copy annexed	M	1647.000	88163.91
				Total	1647.00	88163.91
4		WRD 5.7.9	Bamboo RUNNERS			
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification			
			As per M B copy annexed	M	191.600	3153.74
				Total	191.60	3153.74
Total						542109.80

519735.39

520310.02

Handwritten signature and date: 20.11.21