



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :-		Mmgsy Road (Yogi Asthan) to Gaurihar Man (Pachhiari Tola) Gaurihar Man Dakshin Bhag	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur East-1	
BLOCK		Sakra	
TOTAL LENGTH OF ROAD	:	1.412	KM
CONSTRUCTION COST	:	5.556 5.364	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

5.37

प्रतिवेदन


शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : MM 658 स्कूक (सोनी स्थान) से गोंरीहार मन (पड़ियारी
होला) गोंरीहार मन दक्षिणवाला भाग
पथ की लम्बाई (km) : 1.412
तात्कालिक मरम्मति ~~5.556~~ 5.369 5.37
कार्य की राशि (लाख) :

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु
Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/
~~1000mm RGC Pipe~~ से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल
हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर
विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर माँड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/24
कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2024
सहायक अभियंता
अवर प्रमंडल सकरा


24-11-24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE, RWD(W) DIVISION - MUZAFFARPUR EAST
- 2 Name of Block/Road : SAKRA / MMGSY Road (Yogi sthan) to Gaunihar man (Pachhiyan Tola) Gaunihar man Dakshin Bag.

A For Road

- 1 Damage Location/Chainage : Several location throughout length on river bank
- 2 Damage Length : 0.175 KM
- 3 Nature of Damage : Embankment, most damaged (road is on bank of moon river)
- 4 Details of Restoration Works : Bridge Bat = 190.01 m³. Bamboo summer = 124.6 m.
Bamboo pile = 1344.25 m. Sand Bag = 1053. Work is satisfactory.
- i Material being used in Restoration Works : Bamboo, Sand Bag, Brick Bats etc.
- ii Equipments/Tools being used in Restoration Works : Tractor, tipper, trailer, manual labour
- iii Procedure Taken up in Restoration Works : Damaged embankment controlled by piling Bamboos & then Sand Bags put. Bread was then filled with Brick Bats.
- iv Restored Length

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)

Executive Engineer
R.W.D. Works Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- Mmgsy Road (Yogi Asthan) to Gaurihar Man (Pachhiari Tola) Gaurihar Man
Dakshin Bhag

District Muzaffarpur
Block Sakra
Division Muzaffarpur East-1
Length of Road (in Km) 1.412

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	4.208 4.236 4.201
2	Sand bag	0.403 0.415
3	Bamboo Piles	0.861 0.720
4	Bamboo Runners	0.056 0.029
	GRAND SUB TOTAL	5.372 5.556 5.369
TOTAL COST OF PROJECT IN LACS =		5.372 5.556 5.369

5.372

Adhithan
20/11/21
JE
RWD

Chand
20/11/2021
AE
RWD

Praveen
24/11/21
EE
RWD

As Per S.E. RWD (W) Circle Muz
Letter No 1170 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD. (W) Division - Muz. Nagar

*Technically sanctioned for Rs. 5.37 Lacs (Rs. Five
lacs thirty seven thousand) only (provisionally)*

Praveen
21/12/21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Praveen
27/12/21

Name of the Road :- Mmgsy Road (Yogi Asthan) to Gaurihar Man (Pachhiari Tola) Gaurihar Man Dakshin Bhag

Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7	Brick Bat				
		SoR	Brick Bat				
		Bihar	Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
		Govt. (1985)					
			As per M B copy annexed	Cum	196.01	2143.47	420751.00
			Total	Total	196.01	2143.47	420751.00
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	1053	29.37	31056.61
			Total	Total	1053	29.37	31056.61
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	1344.250	52.53	70557.20
			Total	Total	1344.25	52.53	70557.20
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per M B copy annexed	M	174.600	16.46	2873.92
			Total	Total	174.60	16.46	2873.92
Total							5364160.31

As per M B copy annexed
20.11.20

As per M B copy annexed
20.11.20

Say 5.37 lacs