



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :-	L071-Pmgsy Road Gaurihar man Chhapra vaishali siman to paitrapur Gaurihar (Kahar Tola)		
DISTRICT	Muzaffarpur		
DIVISION	Muzaffarpur East-1		
BLOCK	Sakra		
TOTAL LENGTH OF ROAD	:	1.689	KM
CONSTRUCTION COST	:	6.946 6.870	Lac

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

6.87

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : L071-PM654 रोड जोरीहार मन दफरा वैशाली सीमा
से पैतरपुर जोरीहार (कडार रोला)


पथ की लम्बाई (km): 1.689

तात्कालिक मरम्मति
कार्य की राशि (लाख): ~~94 लाख~~ 6.87 लाख


वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबंधी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/24

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2024

सहायक अभियंता
अवर प्रमंडल सकरा


24.11.24

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE, RWD(W) - DIV - MUZAFFARPUR EAST-1
- 2 Name of Block/Road SAKRA) LOT 1 PM 65Y Road Gaurihar man
raishali man to g paitapur Gaurihar
(lehar tola)
- A For Road
 - 1 Damage Location/Chainage : 0-400 m & 1.0-1.3 km damaged.
 - 2 Damage Length : 0.190 Km
 - 3 Nature of Damage : Side flank damaged, c/w Breach water crossing
 - 4 Details of Restoration Works : Brick Bat = 306.373 Bamboo pile 292 m running - with
Sand bags = 292 mts ^{222.5 m} Work is satisfactory
i Material being used in Restoration Works Brick Bat, Bamboo, Sand Bag.
ii Equipments/Tools being used in Restoration Works Roller, Tractor, Trailer, Ripper
etc. manual tools.
iii Procedure Taken up in Restoration Works Brick Bat filled in cut / Trenches
& compacted to open traffic
Bamboo pile & Sand Bag used
to protect from further damage
iv Restored Length 0.191 Km
- B For Bridge
 - 1 Damage Location/Chainage
 - 2 Damage Length
 - 3 Nature of Damage
 - 4 Details of Restoration Works
 - i Material being used in Restoration Works
 - ii Equipments/Tools being used in Restoration Works
 - iii Procedure Taken up in Restoration Works
 - iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

Executive Engineer
R.W.D. Works Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- L071-Pmgsy Road Gaurihar man Chhapra vaishali siman to paitrapur Gaurihar (Kahar Tola)

District Muzaffarpur
Block Sakra
Division Muzaffarpur East-1
Length of Road (in Km) 1.689

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	6.576 6.621 6.577
2	Sand bag	0.112 0.115
3	Bamboo Piles	0.243 0.178
	GRAND SUB TOTAL	6.869 6.946 6.860
TOTAL COST OF PROJECT IN LACS =		Say 6.87 lacs 6.946 6.860

Abhinav
20.11.21
JE
RWD

Chaitanya
20/11/2021
AE
RWD

Chaitanya
24.11.21
EE
RWD

As Per S.E. RWD (W) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD. (W) Division - 14/11/2021

Technically Sanctioned for Rs. 6.87 lacs (Rs. Six lacs eighty seven thousand) only (provisionally)

Sh
27.12.21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Sh
27.12.21

Name of the Road :- L071-Pingsy Road Gaurihar man Chhapra vaishali siman to paitrapur Gaurihar (Kahar To						
Sl. No.	SDB SL NO	MORD Ref. No	Description	Unit	QUANTIT Y	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat			
			Brick Bat			
			Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I			
			As per M B copy annexed	Cum	306.37	2145.59
				Total	306.37	657647
2		WRD 10.7.40	Sand bags			
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I			
			As per M B copy annexed	No	292.000	29.37
				Total	292.00	11169.00
3		WRD 5.7.7	Bamboo piling			
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I			
			As per M B copy annexed	M	332.500	5353
				Total	332.50	24299.95
Total						694589.67

Abhishek
20.11.24
75

Chaitanya
20/11/2024
RE

6,86,942.48

17758.73

1148.84

171
6567652