

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : NH 28 ~~मार्फत चौक से गुजरकर~~ महुआ RED PINK

पथ की लम्बाई (km) : 1.90

तात्कालिक मरम्मति : 4.50

कार्य की राशि (लाख) :

वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EG Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मति कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विक्षेपित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20.11.21
कनीय अभियंता
कार्य प्रशाखा सकरा


20.11.2021
सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE / RWD (w) - Div - Muzaffarpur East - 1
- 2 Name of Block/Road NH-28 Markan Chowk to Muzaffarpur Mahua REID Path
- A For Road
- 1 Damage Location/Chainage
- 2 Damage Length : 1.50 km
- 3 Nature of Damage Embankment damaged severely at
- 4 Details of Restoration Works ^{many continuous length}
Brick Bats = 195.78 m³ HP 1000 mm dia Pipe = 7.5 m
Work in safe factory
- i Material being used in Restoration Works : HP 1000 mm dia, Brick Bat, Sand Bag, Bamboo.
- ii Equipments/Tools being used in Restoration Works Tractor, bullock, JCB, manual labour etc.
- iii Procedure Taken up in Restoration Works Brick Bat filled in damaged part.
- iv Restored Length : 1.5 km HP 1000 mm dia used in breach of W. then Brick Bat filled into that trench & traffic resumed.

B For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works
- i Material being used in Restoration Works
- ii Equipments/Tools being used in Restoration Works
- iii Procedure Taken up in Restoration Works
- iv Restored Length


Signature of JE/AE/EE

1/12/2024


1/12/24


Signature
(Name of Inspector)

GENERAL ABSTRACT

Name of the Road :- NH28 Markan chowk to Muzaffarpur Mahua RCD path
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 1.9

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	4.203 4.231 4.196
2	Sand bag	0.000
3	Bamboo Piles	0.000
4	Bamboo Runners	0.000
5	Rcc NP3 pipe	0.313 0.299 0.309
	GRAND SUB TOTAL	4.531 4.531 4.509
TOTAL COST OF PROJECT IN LACS =		4.516



 2.11.21
 JE
 RWD


 20/11/2021
 AE
 RWD


 24.11.21
 EE
 RWD

As Per S.E. RWD (W) Circle Muz
 Letter No 11/19 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. RWD. (W) Division Muz East + Mahua etc

Technically Sanctioned for Rs. 4.516 lacs (Rs. Four
 lacs fifty one thousand Six hundred) only
 (provisionally)


 24.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

27.12.21

Name of the Road :- NH28 Markan chowk to Muzaffarpur Mahua RCD path

Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	195.78	2146.58	4202257.43
				Total	195.78	2146.58	423415.82
2			NP3 RCC PIPE 1000MM DIA				
			Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design 1000 MM DIA (Single Row)				
			3Nos of 2.5 m each	M	7.500	4132.28	31251.88
				Total	7.50	3992.28	29942.10
Total							453057.92

44626.8
45049503
450928.68
451549.31

Approved for
20.11.24
20/11/24
20/11/24