

ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :-

PMGSY Sadak To Gosai Tola Tak

DISTRICT

Muzaffarpur

DIVISION

Muzaffarpur East-1

BLOCK

Sakra

TOTAL LENGTH OF ROAD

:

3.248

KM

CONSTRUCTION COST

:

~~4.495~~

Lac

4.458

4.465

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : PMGSY राडूक से जीसाई टोला तक

पथ की लम्बाई (km) : 3.248


तात्कालिक मरम्मत

कार्य की राशि (लाख) : ~~4.495~~ 4.458 4. 465


वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EG Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20/11/21

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021

सहायक अभियंता
अवर प्रमंडल सकरा


29.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs : EE, RWD(W) DIVISION MUZAFFARPUR EAST I
2 Name of Block/Road : SAKRA / PMGSY SADAK TO GOSA (TOLA) TAK

A For Road

- 1 Damage Location/Chainage : 3000-3248 m ch.ⁿ
2 Damage Length : 0.09 KM
3 Nature of Damage : Embankment damaged
4 Details of Restoration Works : Brick Bat = 208 m³. Work is satisfactory
i Material being used in Restoration Works : Brick Bat
ii Equipments/Tools being used in Restoration Works : Tractor, tipper, manual labour, trailer
iii Procedure Taken up in Restoration Works : Brick Bat filled & manually rammed to get level & to resume traffic plying.
iv Restored Length : 0.09 KM

B For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works
i Material being used in Restoration Works
ii Equipments/Tools being used in Restoration Works
iii Procedure Taken up in Restoration Works
iv Restored Length

Signature of JE/AE/EE

Signature
(Name of Inspector)

Executive Engineer
RWD, Works Division, Muzaffarpur

GENERAL ABSTRACT

Name of the Road :- PMGSY Sadak To Gosai Tola Tak
 District Muzaffarpur
 Block Sakra
 Division Muzaffarpur East-1
 Length of Road (in Km) 3.248

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	4.465 4.495 4.458
2	Sand bag	0.000
3	Bamboo Piles	0.000
	GRAND SUB TOTAL	4.465 4.495 4.458
TOTAL COST OF PROJECT IN LACS =		4.465 4.495 4.458

Ashutosh
 JE
 RWD

Chit
 20/11/21
 AE
 RWD

gove
 24-11-21
 EE
 RWD

As Per S.E. RWD (W) Circle Muz
 Letter No. 1179 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. RWD. (W) Division Muzaffarpur East-1 Matmar

Technically Sanctioned for Rs. 4.465 Lacs
 (Rs. Four Lacs forty Six thousand five
 hundred) only (provisionally)

Sh
 27/12/21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

Sh
 27/12/21

Name of the Road :- PMGSY Sadak To Gosai Tola Tak

Sl. No.	SDB SL .NO	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7	Brick Bat				
		SoR	Brick Bat				
		Bihar Govt. (1985)	Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	208.00	2145.53	446455.64
				Total	208.00	2145.53	446455.64
							449525.44
							45829.28

[Signature]
20.11.21

[Signature]
20/11/2021