



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

3054-FDR WORK (Temporary restoration 2021-22)



Name of the Road :- MUHAMMADPUR KANTH GYA PANDIT KE GHAR SE to
RAMSHARAN TOLA KUDHNI SIMAN TAK

DISTRICT Muzaffarpur

DIVISION Muzaffarpur East-1

BLOCK Sakra

TOTAL LENGTH OF ROAD	:	3.774	KM
----------------------	---	-------	----

CONSTRUCTION COST	:	3.004 2.817	Lac
-------------------	---	---------------------------	-----

Submitted By :- Executive Engineer
RWD Work Division Muzaffarpur East-1

282

प्रतिवेदन

शीर्ष : FDR Part A (Temporary Restoration)

पथ का नाम : महमपुर काँठ गायपंडित के घर से रमलखा
डोल कुदनी सीमा तक


पथ की लम्बाई (km) : 5.774 km

तात्कालिक मरम्मत : 2.812 / 2.82
कार्य की राशि (लाख) : ~~2.00~~ Lakh


वर्ष 2021 में आयी बाढ़ में क्षतिग्रस्त पथांश के बाधित यातायात को पुनः चालू करने हेतु Brick bat/ Bamboo pilling/ Bamboo runners/ Local Sand Bag(EC Bags)/ 1000mm RCC Pipe से तात्कालिक मरम्मत कार्य कराया गया एवं आवागमन पुनः बहाल हुआ।

तत्संबन्धी निर्गत विभागीय निर्देशों के आलोक में अद्यतन प्रावधानों एवं अनुसूचित दर विश्लेषित करते हुए प्राक्कलन तैयार किया गया है।

MIS एफडीआर मॉड्यूल में की गयी ऑनलाइन प्रविष्टि की प्रति संलग्न है।


20.11.21

कनीय अभियंता
कार्य प्रशाखा सकरा


20/11/2021

सहायक अभियंता
अवर प्रमंडल सकरा


24.11.21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
मुजफ्फरपुर, पूर्वी-1

Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs EE, RWD(W) Div - Mugaffarpur East-I
2 Name of Block/Road JAKRA/ Mahmaddpur kanti gya pandit
ke ghar se ramsaran jala kudhnisman late

A For Road

- 1 Damage Location/Chainage : Various location in ch 0.9 to 2.1 KM
2 Damage Length 0.105 km
3 Nature of Damage embankment damage, Breach in C/W
4 Details of Restoration Works : Brick Bat = 93.4m² Bamboo pile = 1045.2m
sunness = 424.3m Sand bag = 472 Nos. Work is Satisfactory
i Material being used in Restoration Works Bamboo, Sand Bag, Brick Bat etc
ii Equipments/Tools being used in Restoration Works Roller, tractor, trailer, mangle, rammer, JCB
iii Procedure Taken up in Restoration Works : Brick Bat filled in pot/dip/ Breaches
iv Restored Length 0.105 km to restore traffic. Bamboo & Sand bag used to protect flank & Brick Bat from falling into pond nearby.

B For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works
i Material being used in Restoration Works
ii Equipments/Tools being used in Restoration Works
iii Procedure Taken up in Restoration Works
iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

R.W.D. Works Division, Main

GENERAL ABSTRACT

Name of the Road :- MUHAMMADPUR KANTH GYA PANDIT KE GHAR SE to RAMSHARAN TOLA
KUDHNI SIMAN TAK
District Muzaffarpur
Block Sakra
Division Muzaffarpur East-1
Length of Road (in Km) 3.774

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Brick Bat	2.005 2.019 2.002
2	Sand bag	0.181 0.186
3	Bamboo Piles	0.670 0.559
4	Bamboo Runners	0.135 0.070
	GRAND SUB TOTAL	2.82 3.004 2.817
TOTAL COST OF PROJECT IN LACS =		3.004 2.817

2.82

[Signature]
20.11.21
JE
RWD

[Signature]
20/11/2021
AE
RWD

[Signature]
24.11.21
EE
RWD

As Per S.E. RWD (M) Circle Muz.
Letter No. 1178 Dated 01/10/2021
Estimate has been verified by inspecting
E.E. RWD. (M) Division - Hattisar

Technically Sanctioned for Rs. 2.82 lacs (Rs. Two
lacs eighty two thousand) only (provisionally)

[Signature]
27/12/21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

Name of the Road :- MUHAMMADPUR KANTH GYA PANDIT KE GHAR SE to RAMSHARAN TOLA
KUDHNI SIMAN TAK

Sl. No.	SDB SL NO.	MORD Ref. No	Description	Unit	QUANTIT Y	RATE	AMOUNT (in Rs.)
1		13.7 SoR Bihar Govt. (1985)	Brick Bat				
			Brick Bat Providing and laying of Brick bats , including all taxes etc. all complete job as per specification and directions of E/I				
			As per M B copy annexed	Cum	93.40	2145.53 200490.37	200494.49 200490.37
				Total	93.40	2145.18	201854.21
2		WRD 10.7.40	Sand bags				
			Providing including labour for filling empty cement bag with local sand, stitching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I				
			As per M B copy annexed	No	472.00	39.37	18582.64
				Total	472.00	39.25	18054.00
3		WRD 5.7.7	Bamboo piling				
			Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I				
			As per M B copy annexed	M	1045.20	53.53	55949.56
				Total	1045.20	54.06	66955.51
4		WRD 5.7.9	Bamboo RUNNERS				
			providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification				
			As per M B copy annexed	M	424.30	16.46	6983.98
				Total	424.30	31.83	13505.47

Ashwini
25
20.11.24

End
20.11.24
28

~~28790.67~~

282006.75