



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Work Department, Bihar

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Andhrathari

Estimate for Mortable of the Road from Hanumani Me Guar
to MNP Road under FDR at Block- Andhrathari in
Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

4.79243 lac.

3.90498 lac.

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

तकनीकी प्रतिवेदन

पथ का नाम :- Hanumani Me Gaur to MNP Road

प्राक्कलित राशि :- 4.79243

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा


योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Hanumani Me Gaur to MNP Road पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Andhathari

Name of Road :- Mostable of Road from Hanumanji me Guaz to
MHP Road.

A. For Road

1. Damage Location Chainage (km) :- 0.00, 0.07, 0.110, 0.140, 0.170, 0.250, 0.325, 0.45, 0.47
2. Damage Length :- 142.00m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- broken bits
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- 164.85m
 - iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

← S" →

Signature of JE/AE/EE

[Signature]

Signature
(Name of Inspection)

[Signature]
61612

Estimate for Motorability of road damaged by flood from Hanumani Me Guar to MNP Road For Year 2021

Head :- FDR 2245

Length :- 0.711 km

Sl No.	Item No.	Name of Item	Unit	Quantity As per Appendix - I	Rate	Amount
1		Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	202.05 164.85	2004.96	405102.17 330517.656

₹ ~~4,05,102.17~~
 Add 12 % GST ₹ ~~48,612.26~~
 Add 1 % L.C ₹ ~~4,051.02~~
 Add S. Fee. (202.50 x 1063.00) x 10 % ₹ ~~21,477.92~~
 164.85 1032
 Total ₹ ~~4,79,243.36~~
 Say ₹ ~~4,79,243.00~~
 390498.00


 Junior Engineer
 R.W.D, Works Section,
 Andhrathari


 Assistant Engineer
 R.W.D, Work sub Div.
 Andhrathari


 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur

कार्यालयक आग्रहता जयनगर के जॉयफांक 753 फांक 07/06/22
 के आधार पर technically sanctioned for Rs 3,90,498.00
 (three lac ninty thousand four hundred ninty eight
 only)


 Superintending Engineer
 RWD Work Circle, Darbhanga

-Abhinav
 09/06/22

Name of Road :- Hanumani Me Guar to MNP Road

Name :- PMGSY	Length :- 0.711 km	Block :- Andhrathari
---------------	--------------------	----------------------

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)

Chainage	Nos.		Length (In Mtr.)		Bldth (In Mtr.)		Thickness (In Mtr.)			Quantity	
ch. 0.00 km	1	x	60.00	x	3.60	x	0.500	av.	=	86.40	cum
ch. 0.070 km	1	x	20.00	x	3.90	x	0.500	av.	=	39.00	cum
ch. 0.110 km	1	x	10.00	x	3.00	x	0.30	av.	=	9.00	cum
ch. 0.140 km	1	x	12.00	x	3.00	x	0.30	av.	=	10.80	cum
ch. 0.170 km	1	x	10.00	x	3.00	x	0.40	av.	=	12.00	cum
ch. 0.250 km	1	x	8.00	x	2.50	x	0.30	av.	=	6.00	cum
ch. 0.325 km	1	x	6.00	x	2.50	x	0.30	av.	=	4.50	cum
ch. 0.450 km	1	x	10.00	x	3.00	x	0.25	av.	=	7.50	cum
ch. 0.470 km	1	x	6.00	x	2.50	x	0.35	av.	=	5.25	cum
Total qty.									=	202.05	cum

164.8500

[Signature]
5/11/21

Junior Engineer
R.W.D, Works Section,
Andhrathari

[Signature]
10/5/11/21

Assistant Engineer
R.W.D, Work sub Div.
Andhrathari

[Signature]
20/5/21
18/4/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur