



बिहार सरकार

ग्रामीण कार्य विभाग

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Andhrathari

Estimate for Motorable of the Road from Bashir Miya House to
T-51 under FDR at Block- Andhrathari in Madhubani
District

TOTAL COST FOR MOTORABLE Rs.

~~5,76,275~~ Lac.

5,75,84 Lac.

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Andhrathani

Name of Road :- Ballir Miya Houk to TOL

A. For Road

1. Damage Location Chainage(km):- 0.00, 0.100, 0.180, 0.250, 0.400, 0.650, 0.800, 0.950
2. Damage Length :- 0.180 KM
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Brick Ball
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- 218.50 m
 - iv. Restored Length:-


B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-


C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-

— S —



Signature of JE/AE/EE



Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Basir Miya House to T01

प्राक्कलित राशि :- 5.76373

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा

योजना का नाम :- F.D.R-2245


प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक **Basir Miya House to T01**

पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।


यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीड़न किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।


प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from Bashir Miya House to T01 For Year 2021

Head :- FDR 2245

Length :-1.772 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	243.00 918.50	2004.96	487205.28 438083.76

₹ ~~4,87,205.28~~

Add 12 % GST ₹

58570.05

Add 1 % L.C ₹

4380.82

Add S. Fee (243.00 x 1063.00) x 10 % ₹

4872.05

218.5 1032

Total ₹

22549.2

Say ₹

517583.84

517584.00

5/11/21

Junior Engineer
R.W.D, Works Section,
Andhrathari

5/11/21

Assistant Engineer
R.W.D, Work sub Div.
Andhrathari

2020
18/4/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

चम्पुभास अधिवासी विभाग के लिए 4 मीटर 753 रुबिक्स - 07-06-2022
के आदेश पर Technically Sanctioned for Rs. 5,17,584.00 (Rupees
Five lacs seventeen thousand five hundred eighty four only)

Superintending Engineer
RWD Work Circle, Darbhanga

Abhinav
09/06/21

Name of Road :- Bashir Miya House to T01

me :-	mmgsy	Length :- 1.772 km	Block :- Andhrathari
-------	-------	--------------------	----------------------

Appendix - I

Measurement for restoration of Embankment and shoulder with Brick Bat (Measurement in mtr.)

Chainage	Nos.		Length (In Mtr.)		Bldth (In Mtr.)		Thickness (In Mtr.)		Quantity	
ch. 0.00 km	1	x	80.00	x	3.50	x	0.450.4	av.	=	119.50
ch. 0.100 km	2	x	15.00	x	3.50	x	0.30	av.	=	126.00 cum
ch. 0.180 km	1	x	10.00	x	3.00	x	0.30	av.	=	31.50 cum
ch. 0.250 km	1	x	10.00	x	3.00	x	0.30	av.	=	9.00 cum
ch. 0.400 km	1	x	8.00	x	3.50	x	0.20	av.	=	9.00 cum
ch. 0.650 km	1	x	7.00	x	3.50	x	0.20	av.	=	5.60 cum
ch. 0.800 km	1	x	30.00	x	3.50	x	0.400.3	av.	=	4.90 cum
ch. 0.950 km	1	x	20.00	x	2.50	x	0.30	av.	=	31.50 cum
Total qty.									=	243.00 cum

218.50m)

8/5/11/21

Junior Engineer
R.W.D, Works Section,
Andhrathari

15/11/21

Assistant Engineer
R.W.D, Work sub Div.
Andhrathari

2036
18/4/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur