



बिहार सरकार

ग्रामीण कार्य विभाग
Rural Work - Employment - Development

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Chanauraganj To Majhaura (Sisauni Gram Se Majhaura hote hue Chanauraganj) FDR at Block- Jhanjharpur in Madhubani District.

TOTAL COST FOR MOTORABLE Rs.

20.20116 lac.

18.2373

Submitted by:

Executive Engineer

RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- chauragani To majhaura, (Sisauri Gram se Majhaura Hole ke chauragani)

A. For Road


1. Damage Location Chainage :-
2. Damage Length :- 425.00 m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Broken bits
 - ii. Equipment's/Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- 769, 895 m
 - iv. Restored Length:-

B. For Bridge


1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-


06/06/22
ve

Signature of JE/AE/EE




Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Chanauraganj To Majhaura (Sisauni Gram Se Majhaura hote hue Chanauraganj)

प्राक्कलित राशि :- 20.20116

प्रमण्डल का नाम:- झांझारपुर

अंचल का नाम :- दरभंगा


योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक Chanauraganj To Majhaura (Sisauni Gram Se Majhaura hote hue Chanauraganj) पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।

यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईंट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।



कनीय अभियंता



सहायक अभियंता



कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झांझारपुर

Estimate for Motorability of road damaged by flood from Chanauraganj To Majhaura (Sisauni Gram Se Majhaura hote hue Chanauraganj) For Year 2021

Head :- FDR 2245


Length :- 1.617 km

SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/L.	Cum	851.69 769.895	2004.96	1543608.68 1707594.36 1543608.68

~~₹ 17,07,594.36~~
 Add 12 % GST ₹ ~~2,04,911.32~~
 Add 1 % L.C ₹ ~~17,075.94~~
 Add S. Fee (~~851.69~~ x ~~1032~~ x 10 %) ₹ ~~90,534.12~~
 Total ₹ ~~20,20,115.74~~
 Say ₹ ~~20,20,116.00~~
18,23,731.96


 Junior Engineer
 R.W.D, Works Section,
 Jhanjharpur


 Assistant Engineer
 R.W.D, Work sub Div.
 Jhanjharpur


 Executive Engineer
 R.W.D (W) Division,
 Jhanjharpur

कार्यवाहीक अभिलेख अन्तर्गत की जाँच यन्त्रिका - 753 दिनांक 07-06-2022
 में आकर पर Technically Sanctioned for Rs. 18,23,731/- (Rupees eighteen
 lacs Twenty three thousand seven hundred thirty.) only.


 Superintending Engineer
 PWD Work Circle, Darbhanga
 Abhinav
 09/06/22

Name of Road :- Chanauraganj To Majhaura (Sisauni Gram Se Majhaura hote hue Chanauraganj)

ie :- MMGSY

Length :- 1.617 km

Brick :- Jhanjharpur

Appendix - 1

Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement in mtr.)

Chainage	Nos.		Length (in Mtr.)		Bidh (in Mtr.)		Thickness (in Mtr.)			Quantity	
ch.	1	x	14.00	x	3.50	x	3.50	0.60	0.60	21. =	75.40 cum
ch.	1	x	55.00	x	4.25	x	4.25	0.65	0.65	21. =	75.40 cum
ch.	1	x	40.00	x	3.50	x	3.50	0.50	0.50	21. =	75.40 cum
ch.	1	x	45.00	x	3.60	x	3.60	0.60	0.60	21. =	97.20 cum
ch.	1	x	33.00	x	3.50	x	3.50	0.65	0.65	21. =	75.40 cum
ch.	1	x	28.00	x	3.75	x	3.75	0.50	0.50	21. =	52.50 cum
ch.	1	x	22.00	x	3.50	x	3.50	0.75	0.75	21. =	57.75 cum
ch.	1	x	23.00	x	3.60	x	3.60	0.30	0.30	21. =	24.24 cum
ch.	1	x	53.00	x	3.50	x	3.50	0.45	0.45	21. =	33.45 cum
ch.	1	x	18.00	x	3.60	x	3.60	0.40	0.40	21. =	25.92 cum
ch.	1	x	15.00	x	3.50	x	3.50	0.30	0.30	21. =	15.75 cum
ch.	1	x	10.00	x	3.90	x	3.90	0.40	0.40	21. =	15.60 cum
ch.	1	x	5.00	x	3.50	x	3.50	0.25	0.25	21. =	4.38 cum
ch.	1	x	45.00	x	3.70	x	3.70	0.55	0.55	21. =	92.58 cum
ch.	1	x	19.00	x	3.95	x	3.95	0.75	0.75	21. =	56.25 cum
Total qty.										=	759.895 cum

25/11/21

Junior Engineer
R.W.D. Works Section,
Jhanjharpur

25/11/21

Assistant Engineer
R.W.D. Work sub Div.
Jhanjharpur

26/12/21

Executive Engineer
R.W.D (W) Division,
Jhanjharpur

26/12/21