



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

AYUB HOME TO GANGAPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2245	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	2.245	KM
TOTAL COST OF F.D.R. PART - A	Rs. 28.163	Laes
ADD G.S.T @ 12%	Rs. 3.380	Laes
ADD Labour Cess @ 1%	Rs. 0.282	Laes
ADD Seigniorage Fee @ 10%	Rs. 1.503	Laes
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 33.328	Laes

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारसोई अन्तर्गत प्रखंड के पथ (.....) जो विभागीय

Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

30/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,

30/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बारसोई

Inspection Report for Flood Damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- Barsi / Agul ~~name~~ to home to Ganga pur

A. For Road

1. Damage Location/Chainage : 270 to 270m to 1300m

2. Damage Length : 269.20m

3. Nature of Damage : flank, 15 hour lev

4. Details of Restoration :

i Material being used in Restoration brick & sand

ii Equipment/Tools being used in Restoration works: Bam & 100

iii Procedure taken up in Restoration works :

iv Restored Length 269.20 :

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

13.11.21
Signature of JE/AE/EE

Am

[Signature]
Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : AYUB HOME TO GANGAPUR
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BARSOI
LENGTH OF ROAD (IN KM) 2.245

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.290
2	HUME PIPE	0.000
3	BRICK BATS	26.882
4	SAND BAGS	0.314
5	BAMBOO WORK	0.677
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		28.163
Add G.S.T. @ 12%		3.380
Add Labour Cess @ 1%		0.282
Add Seigniorage Fee @ 10%		1.503
Total Cost of Restoration Work =		33.328

Bh
30/11/21
J.E.
RWD

Bh
30-11-21
A.E.
RWD

Bh
30/11/21
E.E.
RWD

provisional Technically Sanctioned For Rs. 33.328 Lacs.

(Rupees.....Crore..Thirty three

acs...thirty two —

Thousands...eight.....Hundred) Only

अधीनस्थ अभियंता
राजीव नगर विभाग,
नगर अंचल, पूर्णिया

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्राहीण कार्य विभाग, कार्य अंचल पूर्णिया के पत्रांक 1361 दिनांक 20-11-2021 में दिये गये निर्देश के आलोक में दिनांक 12/11/2021 से 22/11/2021 तक ग्राहीण कार्य विभाग, कार्य अंचल पूर्णिया अन्तर्गत ग्राहीण कार्य विभाग, कार्य प्रमाण्डल बारसोई में बारसोई, कदवा, बलरामपुर, डंडखोरा प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलों पर मोटरवेव है।

S.NO.	Division	ROAD NAME	Road Status	LENGTH (IN KM.)	Estimated Cost for Restoration (In Lakh)	Remarks Damage Length (in Mtr)
1	Barsoi	ACHINTOPARMANIK HOME TO PMGSY		0.990	15.602	161.700
2	Barsoi	ATTABALI HOME TO PMGSY ROAD		0.546	9.159	221.500
3	Barsoi	AYUBI HOME TO GANGAPUR		2.245	31.350	269.100
4	Barsoi	BALKAMPUR SHAPIHARA TO SOHAR PEER MAJAR			37.633	478.000
5	Barsoi	BARSOI DAKAITPUJA TO MAHESHPUR		7.275	22.877	99.099
6	Barsoi	BASALGAON TO PANCHIPEER		1.885	23.058	258.400
7	Barsoi	BELGACHI MORE LUTTIPUR TO BALKAMPUR SIMA		3.742	9.531	72.500
8	Barsoi	BIHAWANIPUR GOWALTOLI VIA HOSPITAL TO SARAKHOR		0.660	11.946	274.800
9	Barsoi	HIGHOR HAT TO PALA TOLA		3.200	19.831	323.500
10	Barsoi	BIJURIYA NII-JI TO JAWADPUR PART -I		9.500	11.374	82.600
11	Barsoi	CHIKNI TOLA TO DHUMTOLA SCHOOL		1.795	19.701	298.600
12	Barsoi	DIACHANA RAILWAY LINE TO BALUPARA		9.300	23.344	376.900
13	Barsoi	DIHAKAMPUR WARD NO -6 TO TISLIYA GACHHI		1.370	20.889	437.000
14	Barsoi	DURGA MANDIR TO PMGSY BANK		2.580	13.685	220.700
15	Barsoi	GAWN BIGHOR TO MODIPOKHAR		2.110	23.613	326.000
16	Barsoi	ITCHING BAGAN TO PMGSY		0.945	12.086	184.100
17	Barsoi	L025-T04 MAHESHPUR TO KUSIYARMORA (VR25)		1.920	18.727	180.300
18	Barsoi	L032 RATAPOKHAR TO DIACHINA (VR32)		3.799	29.097	110.300
19	Barsoi	L036-T01 TO BAJEDOGACHHI (VR36)		3.009	17.882	365.500
20	Barsoi	L039-T01 TO LODHINA (VR39)		3.208	13.136	99.800
21	Barsoi	L048-T07 SITAPUR TO MAULANAPUR KADAMGACHHI		4.600	18.093	190.400
22	Barsoi	L050-T08 TO KOLHIA (VR50)		2.165	28.890	90.100
23	Barsoi	L053-T06 TO PHUGAON (VR53)		1.100	13.144	63.000
24	Barsoi	L054-T01 LAGWN TO CHORKHARA (VR54)		1.795	13.047	279.900
25	Barsoi	LAGUA HANSHARI TO SATUA NADI DIHAR		1.470	29.276	123.500
26	Barsoi	MAHARAJA ASTHAN TO PMGSY ROAD		1.590	12.221	217.900
27	Barsoi	MASJID TO KAHIRISTAN		0.500	13.128	313.800
28	Barsoi	MASJID TO PMGSY ROAD		1.975	15.826	525.500
29	Barsoi	MAHURAPUR SCHOOL MORE TO KUMHAR TOLI		1.190	19.075	363.700

