



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

YEAR (2021-22)

FDR

STATE :- BIHAR
DISTRICT :- Samastipur
BLOCK :- Patori

NAME OF ROAD :- Repair of Flood Damaged Road in PWD
Sadak to Pyarepur Hote Hue Jodi Pokhar Ta

TOTAL COST OF CONSTRUCTION :- 4.680 Lakh

TOTAL COST OF PROJECT :- 4.680 Lakh

SUBMITTED BY:

EXECUTIVE ENGINEER

RWD (W) DIVISION, PATORI

SAMASTIPUR

FDR

YEAR (2021-22)

GENERAL ABSTRACT OF COST

Block:--Patori

District:--Samastipur

Name of Road:--

Repair of Flood Damaged Road in PWD Sadak to Pyarepur Hote
Hue Jodi Pokhar Tak

SL. No.	Item of Work	Amount
A		
	TOTAL COST OF CONSTRUCTION	3.941 Lacs
	GST @12%	0.473 Lacs
	L.Cess@ 1%	0.039 Lacs
	<u>S.Fees</u>	0.227 Lacs
	Sub Total= (A)	4.680 Lacs
	TOTAL cost of project	4.680 Lacs

Rav
16-11-2021
Junior Engineer
RWD (W) Section- Patori

Pratibha
16/11/2021
Asstt. Engineer
RWD (W) Sub Division- Patori

Pratibha
16-11-21
Executive Engineer
RWD (w) Division, Patori

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

Repair of Flood Damaged Road in PWD Sadak to Pyarepur Hote

DISTRICT

Hue Jodi Pokhar Tak

BLOCK

Samastipur

Patori

Sl. No.	DESCRIPTION	AMOUNT (in Lakh.)
1.	BRICK BAT	3.941
	SUB TOTAL OF PAVEMENT COST IN LACS =	3.941
	Sub Total :-	3.941
	12% GST on Total Amount :-	0.473
	1% Lab Cess :-	0.039
	S.Fees	0.227
	Total Construction Cost (including GST and Labour Cess) :-	4.680

Ravi
16/11/2021
Junior Engineer

RWD (W) Section- Patori

K. P. Singh
16/11/2021
Assistant Engineer

RWD (W) Sub Division- Patori

[Signature]
16/11/2021
Executive Engineer
RWD (w)
Division, Patori

From many Tech in carry Sanctioned for Rs 4.68 Lakh say four Lakh Sixty Eight Thousand only including C.P and O.M.C

[Signature]
20/12/21
बसोबस बाबबस
बाबोब बाबोब बाबोब
बाबो बाबोब, बाबोबो
400
20/12/21
T.H.

Cost Estimate for Road Work

Sl. No.	SDB SL. NO	MORD Ref. No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1			SUB HEAD : Brick Bat Filling								
			Brick Bats								
			Providing Brick Bats laying, spreading & Hand Packing...								
			-----do -----all compact job								
			Damaged Road Strech	cum	1.00	16.0	3.50	0.225	12.600		
			Damaged Road Strech	cum	1.00	16.0	3.00	1.500	72.000		
			Damaged Road Strech	cum	1.00	20.0	3.00	0.150	9.000		
			Damaged Road Strech	cum	1.00	30.0	3.00	0.150	13.500		
			Damaged Road Strech	cum	1.00	20.0	3.00	0.150	9.000		
			Damaged Road Strech	cum	1.00	18.0	3.00	0.225	12.150		
			Damaged Road Strech	cum	1.00	11.0	1.50	1.250	20.625		
			Damaged Road Strech	cum	1.00	21.0	3.00	0.150	9.450		
			Damaged Road Strech	cum	1.00	10.0	3.00	0.075	2.250		
			Damaged Road Strech	cum	1.00	8.0	2.50	0.225	4.500		
			Damaged Road Strech	cum	1.00	16.0	3.00	0.150	7.200		
			Damaged Road Strech	cum	1.00	9.0	2.00	0.150	2.700		
			Damaged Road Strech	cum	1.00	18.0	2.00	0.150	5.400		
			Damaged Road Strech	cum	1.00	5.0	2.00	0.075	0.750		
			Damaged Road Strech	cum	1.00	27.0	3.00	0.150	12.150		
			Damaged Road Strech	cum	1.00	2.0	2.50	0.075	0.375		
			Damaged Road Strech	cum	1.00	12.0	3.00	0.150	5.400		
			Damaged Road Strech	cum	1.00	1.5	3.00	0.150	0.675		
			Damaged Road Strech	cum	1.00	4.5	2.50	0.075	0.844		
			Damaged Road Strech	cum	1.00	8.0	3.00	0.225	5.400		
			Damaged Road Strech	cum	1.00	8.0	3.00	0.075	1.800		
			TOTAL						107.769	1.896.72	3,94,079.14
									SUB TOTAL(1+2) =		3,94,079.14
									GST @ 12%		47289.49722
									Lebour Cess @ 1%		3940.791435
									S. Fees		22709.00
									Grand Total		4,68,018.43

Q. 11/11/2019
 Junior Engineer
 RWD,
 Works Section - Patori

Assistant Engineer
 RWD, Works Sub Division - Patori

Executive Engineer
 RWD (w) Division, Patori

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बलिया

पत्रांक 01, कैप पटोरी

दिनांक 16/12/2

प्रेषक:-

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बलिया

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, पटोरी

विषय:-

एफ.डी.आर. योजना की जाँच के संबंध में।

प्रसंग:-

आपका पत्रांक 1514 दिनांक 19.11.2021

महाशय,

उपरोक्त विषय के संबंध में कहना है कि प्रासंगिक पत्र में उल्लेखित पथों की जाँच कर ली गई। जाँचोपरांत प्राक्कलन लौटाई जाती है। व्यौरा निम्नवत् है:-

क्रम सं०	पथ का नाम	प्रखंड	लंबाई कि०मी० में	प्राक्कलित राशि लाख में	अभियुक्ति
01	गढ़सिसई चौक से भागीरथ स्थान पीएचसी	विद्यापतिनगर	1.06	2.24	
02	टुनटुन राय से एमएमजीएसवाई	विद्यापतिनगर	1.24	7.95	
03	पीडब्लुडी रोड से सरारी माधोपुर	मोहनपुर	2.10	4.861	
04	दक्षिणी डुमरी पंचायत अंतर्गत डुमरिया बाँध से चापर दुर्गा स्थान होते हुए चापर काली स्थान	मोहनपुर	0.850	6.974	
05	विशनपुर बेरी मरगंग से मटिऔर चमार टोली काली मंदिर दो गाछी तक	मोहनपुर	2.110	4.907	
06	मोहनपुर मोहिउद्दीननगर पीडब्लुडी रोड दशहरा सहेंद्र राय के घर से सरहद सीमान भाया रविदास टोला	मोहनपुर	3.85	4.400	
07	मोहनपुर प्रखंड गेट से खनजीवा तक	मोहनपुर	2.10	3.137	
08	एस.एच.टी 01 से जौनापुर रूदार	मोहनपुर	4.60	4.036	
09	पटोरी प्रखंड के आदर्श मध्य विद्यालय हसनपुर सूरत घाट पर आदर्श मध्य विद्यालय हसनपुर सूरत के नजदीक उच्च स्तरीय पुल	पटोरी	03x16.50m	9.44	
10	टी 02 से रूपौली चौसीवा	पटोरी	1.028	2.54	
11	पटोरी मदुदाबाद पीडब्लुडी रोड से ईस्माईलपुर	पटोरी	2.570	3.919	
12	पीडब्लुडी सड़क से प्यारपुर होते हुए जोड़ी पोखर तक	पटोरी	1.30	4.680	
13	चकलालशाही जंदाहा आरईओ रोड कौआ चौक से दरवा	पटोरी	2.90	8.043	
14	वजरंगवली से बांवे रीगान भाया करतूरवा विद्यालय	पटोरी	2.01	4.614	
15	वाकरपुर चौक से वाकरपुर महादलित टोला	मोहिउद्दीननगर	0.450	1.787	
16	रमगामा विकु से ब्रह्मपुरा	मोहिउद्दीननगर	1.421	3.108	
17	पहुँच पथ से मधुसूदनपुर	मोहिउद्दीननगर	5.10	6.141	
18	मोहिउद्दीननगर बाजार से कुरसाहा नहर	मोहिउद्दीननगर	1.88	2.380	

कृ०प०उ०

	पथ का नाम	प्रखंड	लंबाई कि०मी० में	प्राक्कलित राशि लाख में	अभियुक्ति
9	मनहर से बाजितपुर सीमान	मोहिउद्दीननगर	1.365	1.439	
20	थाना चौक मोहिउद्दीननगर से कन्हौली होते हुए नवादा हेमनपुर पीएमजीएसवाई सड़क तक	मोहिउद्दीननगर	1.450	0.721	
21	राहेपुर मोड़ से तेतारपुर भाया मनियर टोला महम्मदीपुर	मोहिउद्दीननगर	4.80	5.935	
22	मोहिउद्दीननगर के टाँड़ा गाँव होते हुए पंचायत भवन तक	मोहिउद्दीननगर	2.00	7.264	
23	भूइया स्थान पासवान टोला से एस.एच. रोड	मोहिउद्दीननगर	0.50	2.329	
24	मस्तलीपुर कासिमचक होते हुए खनुआ घाट	मोहिउद्दीननगर	1.372	3.293	
25	आनंदगोलवा से रजैसी	मोहिउद्दीननगर	0.737	1.369	
26	कल्याणपुर बस्ती से हरिजन टोला	मोहिउद्दीननगर	1.935	0.727	
27	करीमनगर दुर्गा मंदिर से मोगलचक यादव टोला	मोहिउद्दीननगर	1.00	1.229	
28	मोहिउद्दीननगर से विशनपुर बेरी	मोहिउद्दीननगर	7.20	0.406	
29	मस्तलीपुर से सरहद भैरो	मोहिउद्दीननगर	1.8	0.440	

अनु०- उक्त सभी पथों का प्राक्कलन (29 अदद)

विश्वासभाजन

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बलिया

Inspection Report for Flood Damage Work

Date.: 16-12-21

1. Name of PIUs – Executive Engineer, R.W.D., Works, Division, Patorn

2. Name of Block – Patorn

3. Name of Road/Bridge – Jodi-Pokhar to MDR 702 via Pyarepur

A. for Road

1. Damage Location/Chainage : 0 m to 300 m

2. Damage Length : ~~0.30 km~~ 300 m

3. Nature of Damage : Flank & Surface

4. Details of Restoration Works :

i. Material being used in Restoration works : Brick Bats, Local Sand

ii. Equipments/Tools being used in Restoration Works : Tractor, J.C.B

iii. Procedure taken up in Restoration works : Hand Packing of Brick Bats

iv. Restored Length : 300 m toppy with Local Sand

B. for Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works :

iv. Restored Length :

Ravi
16-12-21
J.E.

A. Prakash
16-12-21
A.E.

[Signature]
Executive Engineer,
R.W.D. Works Division,

[Signature]
Signature
(Name of Inspector)