



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Road Development Agency (BRRDA)

YEAR (2021-22)

FDR

STATE :- BIHAR
DISTRICT :- Samastipur
BLOCK :- Mohiuddin Nagar

NAME OF ROAD :- Repair of Flood Damaged Road in Mohiuddin
Nagar Tanda Village Hote Hue Panchayat
Bhavan Tak

TOTAL COST OF CONSTRUCTION :- 7.264 Lacs

TOTAL COST OF PROJECT :- 7.264 Lacs

SUBMITTED BY:

EXECUTIVE ENGINEER

RWD (W) DIVISION, PATORI

SAMASTIPUR

Mohini Binayak Tamang, Hote hue Panchayat Bhawan talk



Prano
26.10.21

Ans
26.10.21

Mahinabhai Tanda Hote hue panchayat Bhawan tal



Prasad
26.10.21
JE

Am
26.10.21

FDR

YEAR (2021-22)

GENERAL ABSTRACT OF COST

Block:--Mohiuddin Nagar

District:--Samastipur

Name of Road:--

Repair of Flood Damaged Road in Mohiuddin Nagar Tanda Village
Hote Hue Panchayat Bhavan Tak

SL. No.	Item of Work	Amount
A		
	TOTAL COST OF CONSTRUCTION	6.117 Lacs
	GST @12%	0.734 Lacs
	L.Cess@ 1%	0.062 Lacs
	<u>S.Fees</u>	0.352 Lacs
	Sub Total= (A)	7.264 Lacs
	TOTAL cost of project	7.264 Lacs

[Signature]
26.10.21
Junior Engineer
RWD (W) Section-
M.Nagar

[Signature]
26.10.21
Asstt. Engineer
RWD (W) Sub Division-Mohiuddin Nagar

[Signature]
26.10.21
Executive Engineer
RWD (w) Division, Patori

Provisionally sanctioned for Rs 7.264 Lacs say seven lakh
twenty six thousand and four hundred only including 12% GST

[Signature]
20.12.21
for
20.12.21

[Signature]
20.12.21
T.A

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :

Repair of Flood Damaged Road in Mohiuddin Nagar Tanda Village
Hote Hue Panchayat Bhavan Tak
Samastipur
Mohiuddin Nagar

DISTRICT
BLOCK

Sl. No.	DESCRIPTION	AMOUNT (In Lacs.)
	BRICK BAT	6.117
	SUB TOTAL OF PAVEMENT COST IN LACS =	6.117
	Sub Total ` :--	6.117
	12% GST on Total Amount :--	0.734
	1% Lab Cess :--	0.062
	S.Fees	0.352
	Total Construction Cost (including GST and Labour Cess) :--	7.264


Junior Engineer

RWD (W) Section-M.Nagar


Assistant Engineer

RWD (W) Sub Division-Mohiuddin Nagar


Executive Engineer
RWD (w)
Division, Patori

Cost Estimate for Road Work

Sl. No.	SDR Sl. No	MORD Ref. No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1			Brick Bats								
			Laying Brick Bats on prepared soil surface as per specifications and direction of E/L								
			Damaged Road Strech	cum	1.00	10.0	3.00	0.075	2.25		
			Damaged Road Strech	cum	1.00	25.0	3.50	0.150	13.13		
			Damaged Road Strech	cum	1.00	17.0	3.50	0.150	8.93		
			Damaged Road Strech	cum	1.00	10.0	1.00	0.075	0.75		
			Damaged Road Strech	cum	1.00	15.0	2.20	0.150	4.95		
			Damaged Road Strech	cum	1.00	5.0	0.50	0.075	0.19		
			Damaged Road Strech	cum	1.00	10.0	1.00	0.150	1.50		
			Damaged Road Strech	cum	1.00	5.0	1.00	0.075	0.38		
			Damaged Road Strech	cum	4.00	30.0	4.50	0.225	121.50		
			Damaged Road Strech	cum	1.00	3.0	4.00	0.150	1.80		
			Damaged Road Strech	cum	1.00	30.0	4.80	0.150	21.60		
			Damaged Road Strech	cum	1.00	13.0	2.50	0.150	4.88		
			Damaged Road Strech	cum	1.00	1.0	1.50	0.150	0.23		
			Damaged Road Strech	cum	1.00	3.0	2.00	0.150	0.90		
			Damaged Road Strech	cum	1.00	1.5	0.50	0.075	0.06		
			Damaged Road Strech	cum	1.00	9.0	2.50	0.150	3.38		
			Damaged Road Strech	cum	1.00	2.0	2.00	0.075	0.30		
			Damaged Road Strech	cum	1.00	2.5	1.50	0.150	0.56		
			Damaged Road Strech	cum	1.00	2.0	1.00	0.075	0.15		
			Damaged Road Strech	cum	1.00	25.0	3.50	0.150	13.13		
			Damaged Road Strech	cum	1.00	12.0	4.00	0.150	7.20		
			Damaged Road Strech	cum	1.00	15.0	4.00	0.225	13.50		
			Damaged Road Strech	cum	1.00	22.0	4.00	0.225	19.80		
			Damaged Road Strech	cum	1.00	4.0	2.00	0.150	1.20		
			Damaged Road Strech	cum	1.00	7.0	3.00	0.150	3.15		
			Damaged Road Strech	cum	1.00	1.0	5.00	1.000	5.00		
			Damaged Road Strech	cum	1.00	8.0	4.00	0.150	4.80		
			Damaged Road Strech	cum	1.00	18.0	2.00	0.150	3.60		
			Damaged Road Strech	cum	1.00	2.0	2.00	0.150	0.60		
			Damaged Road Strech	cum	1.00	1.0	1.00	0.150	0.15		
			Damaged Road Strech	cum	1.00	1.0	1.00	0.150	0.15		
			Damaged Road Strech	cum	1.00	28.0	2.00	0.150	8.40		
			Damaged Road Strech	cum	1.00	12.0	1.50	0.075	1.35		
			Damaged Road Strech	cum	1.00	4.0	3.00	0.075	0.90		
			Damaged Road Strech	cum	1.00	5.0	1.00	0.075	0.38		
			Damaged Road Strech	cum	2.00	0.5	0.50	0.075	0.04		
			Damaged Road Strech	cum	1.00	2.0	1.00	0.150	0.30		

Cost Estimate for Road Work

FORMAT

Sl. No.	SDB Sl. No.	MORD Ref. No.	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
			Damaged Road Strech	cum	1.00	3.0	1.00	0.075	0.23		
			Damaged Road Strech	cum	1.00	25.0	4.00	0.150	15.00		
			Damaged Road Strech	cum	1.00	30.0	4.50	0.225	30.38		
			Damaged Road Strech	cum	2.00	2.0	3.75	0.300	4.50		
			Damaged Road Strech	cum	1.00	3.0	3.00	0.150	1.35		
			Total						322.49	1,896.72	6,11,680.35
									SUB TOTAL =		6,11,680.35
									GST @12%		73,401.64
									Lebour Cess @1%		6116.80
									S.Fees		35248.00
									Grand Total		7,26,446.79

Junior Engineer
RWD, Section-M, Nagar

Prasanna
28.10.24

Assistant Engineer
RWD, Works Sub Division-M, Nagar

Prasanna
28.10.24

Executive Engineer
RWD (w) Division, Patori

Prasanna

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बलिया

पत्रांक 01, कैप पटोरी

दिनांक 16/12/2

प्रेषक:-

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बलिया

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, पटोरी

विषय:-

एफ.डी.आर. योजना की जाँच के संबंध में।

प्रसंग:-

आपका पत्रांक 1514 दिनांक 19.11.2021

महाशय,

उपरोक्त विषय के संबंध में कहना है कि प्रासंगिक पत्र में उल्लेखित पथों की जाँच कर ली गई। जाँचोपरांत प्राक्कलन लौटाई जाती है। व्यौरा निम्नवत् है:-

क्रम सं०	पथ का नाम	प्रखंड	लंबाई कि०मी० में	प्राक्कलित राशि लाख में	अभियुक्ति
01	गढ़सिसई चौक से भागीरथ स्थान पीएचसी	विद्यापतिनगर	1.06	2.24	
02	टुनटुन राय से एमएमजीएसवाई	विद्यापतिनगर	1.24	7.95	
03	पीडब्लुडी रोड से सरारी माधोपुर	मोहनपुर	2.10	4.861	
04	दक्षिणी डुमरी पंचायत अंतर्गत डुमरिया बाँध से चापर दुर्गा स्थान होते हुए चापर काली स्थान	मोहनपुर	0.850	6.974	
05	विशनपुर बेरी मरगंग से मटिऔर चमार टोली काली मंदिर दो गाछी तक	मोहनपुर	2.110	4.907	
06	मोहनपुर मोहिउद्दीननगर पीडब्लुडी रोड दशहरा सहेंद्र राय के घर से सरहद सीमान भाया रविदास टोला	मोहनपुर	3.85	4.400	
07	मोहनपुर प्रखंड गेट से खनजीवा तक	मोहनपुर	2.10	3.137	
08	एस.एच.टी 01 से जौनापुर रूदार	मोहनपुर	4.60	4.036	
09	पटोरी प्रखंड के आदर्श मध्य विद्यालय हसनपुर सूरत घाट पर आदर्श मध्य विद्यालय हसनपुर सूरत के नजदीक उच्च स्तरीय पुल	पटोरी	03x16.50m	9.44	
10	टी 02 से रूपौली चौसीवा	पटोरी	1.028	2.54	
11	पटोरी मदुदाबाद पीडब्लुडी रोड से ईस्माईलपुर	पटोरी	2.570	3.919	
12	पीडब्लुडी सड़क से प्यारपुर होते हुए जोड़ी पोखर तक	पटोरी	1.30	4.680	
13	चकलालशाही जंदाहा आरईओ रोड कौआ चौक से दरवा	पटोरी	2.90	8.043	
14	वजरंगवली से बांवे रीगान भाया करतूरवा विद्यालय	पटोरी	2.01	4.614	
15	वाकरपुर चौक से वाकरपुर महादलित टोला	मोहिउद्दीननगर	0.450	1.787	
16	रमगामा विकु से ब्रह्मपुरा	मोहिउद्दीननगर	1.421	3.108	
17	पहुँच पथ से मधुसूदनपुर	मोहिउद्दीननगर	5.10	6.141	
18	मोहिउद्दीननगर बाजार से कुरसाहा नहर	मोहिउद्दीननगर	1.88	2.380	

कृ०प०उ०

	पथ का नाम	प्रखंड	लंबाई कि०मी० में	प्राक्कलित राशि लाख में	अभियुक्ति
9	मनहर से बाजितपुर सीमान	मोहिउद्दीननगर	1.365	1.439	
20	थाना चौक मोहिउद्दीननगर से कन्हौली होते हुए नवादा हेमनपुर पीएमजीएसवाई सड़क तक	मोहिउद्दीननगर	1.450	0.721	
21	राहेपुर मोड़ से तैतारपुर भाया मनियर टोला महम्मदीपुर	मोहिउद्दीननगर	4.80	5.935	
22	मोहिउद्दीननगर के टाँड़ा गाँव होते हुए पंचायत भवन तक	मोहिउद्दीननगर	2.00	7.264	
23	भूइया स्थान पासवान टोला से एस.एच. रोड	मोहिउद्दीननगर	0.50	2.329	
24	मस्तलीपुर कासिमचक होते हुए खनुआ घाट	मोहिउद्दीननगर	1.372	3.293	
25	आनंदगोलवा से रजैसी	मोहिउद्दीननगर	0.737	1.369	
26	कल्याणपुर बस्ती से हरिजन टोला	मोहिउद्दीननगर	1.935	0.727	
27	करीमनगर दुर्गा मंदिर से मोगलचक यादव टोला	मोहिउद्दीननगर	1.00	1.229	
28	मोहिउद्दीननगर से विशनपुर बेरी	मोहिउद्दीननगर	7.20	0.406	
29	मस्तलीपुर से सरहद भैरो	मोहिउद्दीननगर	1.8	0.440	

अनु०- उक्त सभी पथों का प्राक्कलन (29 अदद)

विश्वासभाजन

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमंडल, बलिया

Inspection Report for Flood Damage Work

Date.: ...16-12-21.....

1. Name of PIUs – Executive Engineer, R.W.D., Works, Division, Patosi

2. Name of Block – mohiuddinagar

3. Name of Road/Bridge – Sammastipur Jilgaantargat mohiuddinagar
Tanda village Hote hue Panchayat Bhagwan
taluk

A. for Road

1. Damage Location/Chainage : Tanda village

2. Damage Length : 1.10 Km

3. Nature of Damage : Flank & Surface Damage

4. Details of Restoration Works :

i. Material being used in Restoration works :

Brick Bats only

ii. Equipments/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works :

iv. Restored Length :

:- 1.10 Km

B. for Bridge

Not applicable

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration works :

ii. Equipments/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works :

iv. Restored Length :

N/A

Pramod
16-12-21
J.E.

In
16/12/21
A.E.

Off
16-12-21
Executive Engineer,
R.W.D. Works Division,
.....

Woj
16/12/21
Signature
(Name of Inspector)