



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L050-T08 TO KOLHA (VR50)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2165	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	2.165	KM
TOTAL COST OF F.D.R. PART - A	Rs. 24.391	Lacs
ADD G.S.T @ 12%	Rs. 2.927	Lacs
ADD Labour Cess @ 1%	Rs. 0.244	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.328	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 28.890	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

Inspection Report for flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- Barsua/Tog to Kolha-

A. For Road

1. Damage Location/Chainage : 0 to 400m
2. Damage Length : 90.10
3. Nature of Damage : Washed out + shoulder
4. Details of Restoration :
 i Material being used in Restoration : gravel & bit
 ii Equipment/Tools being used in Restoration works : roller
 iii Procedure taken up in Restoration works :
 iv Restored Length : 90.10

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 i Material being used in Restoration :
 ii Equipment/Tools being used in Restoration works :
 iii Procedure taken up in Restoration works :
 iv Restored Length :

Signature of JE/AE/EE

BM

Signature

(Name of Inspector)

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारसोई अन्तर्गत ७१२ ५१/३ प्रखंड के थ १.६.४.५ ११.५.२१ (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण लायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, हार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक- 2/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

क्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के ढाबे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का गइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

30/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,

30/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

30/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बारसोई

अभियंता
कार्य विभाग
अंपल, पूर्णिया

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L050-T08 TO KOLHA (VR50)
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BARSOI
LENGTH OF ROAD (IN KM) 2.165

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	24.391
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		24.391
Add G.S.T. @ 12%		2.927
Add Labour Cess @ 1%		0.244
Add Seigniorage Fee @ 10%		1.328
Total Cost of Restoration Work =		28.890

Bmr
30-11-21
J.E.
RWD

A.E.
RWD

W. J. J. J.
E.E.
RWD

provisional Technically Sanctioned For Rs. 28.890 Lacs.

(Rupees.....Crore.....Twenty eight

lacs.....eighty nine -

Thousands.....Hundred) Only

अधीक्षक अभियंता
ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णिया

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्राहीण कार्य विभाग, कार्य अंचल पूर्णिया के पत्रांक 1361, दिनांक 20-11-2020 में दिये गये निर्देश के आलोक में दिनांक 12/1/21 से 22/2/21 तक ग्राहीण कार्य विभाग, कार्य अंचल पूर्णिया अन्तर्गत ग्राहीण कार्य विभाग, कार्य प्रमुखित बारसोई में बारसोई, कदवा, बलरामपुर, कुंडखोरा प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थलों पर मोटरवेल् है।

Sl.No.	Division	ROAD NAME	Road Status	LENGTH (IN KM.)	Estimated Cost for Restoration (In Lakh)	Remarks Damage Length (in Mtr)
1	Barsoi	ACHINTOPARMANIK HOME TO PMGSY		0.990	15.602	161.700
2	Barsoi	ATTALAI HOME TO PMGSY ROAD		0.546	9.159	221.500
3	Barsoi	AYUB HOME TO GANGAPUR		2.245	31.350	269.200
4	Barsoi	BALRAMPUR SHAPHARA TO SOHAR PEER MAJAR			37.633	498.000
5	Barsoi	BARSOI DAKAITPUJA TO MAHESHPUR		7.275	22.877	99.090
6	Barsoi	BASALGAON TO PANCHPEER		1.885	23.058	258.400
7	Barsoi	BELGACHH MORE LUTTIKUR TO BALRAMPUR SIMA		3.742	9.531	72.500
8	Barsoi	BHAWANIPUR GOWALTOLI VIA HOSPITAL TO SAKHORI		0.660	11.946	274.800
9	Barsoi	BIGHOR HAT TO PALA TOLA		3.200	19.831	323.500
10	Barsoi	BIJURIYA NH-31 TO JAWADPUR PART -I		9.500	11.374	82.600
11	Barsoi	CHIKNI TOLA TO DHUMTOILA SCHOOL		1.795	19.701	298.600
12	Barsoi	DHACHANA RAILWAY LINE TO BALUPARA		9.300	23.344	376.900
13	Barsoi	DHARAMPUR WARD NO -6 TO TISLIYA GACHH		1.370	20.889	437.000
14	Barsoi	DURGA MANDIR TO PMGSY BANK		2.580	13.685	220.700
15	Barsoi	GAWN BIGHOR TO MODIPOKHAR		2.110	23.613	326.000
16	Barsoi	ITCHING BAGAN TO PMGSY		0.945	12.086	184.100
17	Barsoi	L025-T04 MAHESHPUR TO KUSIYARMORA (VR25)		1.920	18.727	180.300
18	Barsoi	L032 RATAPOKHAR TO DHACHANA (VR32)		3.799	29.097	110.300
19	Barsoi	L036-T01 TO BAJEDOGACHH (VR36)		3.009	17.882	365.500
20	Barsoi	L039-T01 TO LODHINA (VR39)		3.208	13.136	99.800
21	Barsoi	L048-T07 SITAI PUR TO MAULANAPUR KADAMGACHH		4.600	18.093	190.400
22	Barsoi	L050-T08 TO KOLJIA (VR50)		2.165	28.890	90.100
23	Barsoi	L053-T06 TO PHUGAON (VR53)		1.100	13.144	63.000
24	Barsoi	L054-T01 LAGWN TO CHORKHARA (VR54)		1.795	13.047	279.900
25	Barsoi	LAGUA HANSIHARI TO SATUA NADI DHAR		1.470	29.276	123.500
26	Barsoi	MAHARAJA ASTHAN TO PMGSY ROAD		1.590	12.221	217.900
27	Barsoi	MASJID TO KAHIRISTAN		0.500	13.128	313.800
28	Barsoi	MASJID TO PMGSY ROAD		1.975	15.826	525.500
29	Barsoi	MATHURAMPUR SCHOOL MORE TO KUMHAR TOLI		1.190	19.075	363.700

30	AKHLOI - RAOJUNATHIPUR TO ADAMPUR	14.450	19.143
31	NADI TO KHOKHA BANGI MORI	1.780	27.633
32	PANCHITA BARKUR BHAWAN TO PMGSY (NIT ROVERED MAHAJALI TOLA)	2.740	11.138
33	PATOL TO MAHESHIKOTI	0.910	19.677
34	PMGSY ROAD TO LAHUA SOUTH EAST TOLA	0.320	9.072
35	PMGSY SADAK TO PEERASAN	0.690	11.407
36	IND ROAD TALWA CHOWK TO KKO HAT BANGORA	0.000	12.455
37	RAHMANPUR TO BANIYA TOLA	1.220	14.935
38	RED PATI SAULA BADIAR CHOWK TO PATOL NOTE HUA DHEGAI POKHAR	2.645	24.351
39	RIVER TO HATHIMORE	1.720	24.482
40	SANKOLA TO SAHARA BANGAL SIMA VIA MAHANANDA NADI	1.203	21.950
41	SHARIFNAGAR PMGSY ROAD TO AHMUNAGAR VIA KOL TOLI	0.650	10.580
42	SUKARPUR TO CHAINA TOLA	1.310	11.764
43	SUKPAN GAON TO AMIN KE GHAR MUSLIM TOLA TAK	2.100	29.588
44	SULTANPUR TO JAMIRA	6.450	24.210
45	TOL BANGAL DURGRIYA SUMAN TO JAVADPUR (VRI)	6.100	18.112

20.12.21
रुनधि अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशास्त्र

20.12.21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल

21/12/22
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल

22/12/22
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल