



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

PLAN HEAD :- F.D.R. 2245

A.A. COPY

YEAR (2021-22)

State :- BIHAR

District :- Darbhanga

Block :- Darbhanga Sadar

BMP-13 KABIR CHOWK VILLAGE RAMPUR KASIM BEHAT
Se ADARASH TOLA

Actual Length of Road	=	1.506 Km ✓ 4.250 Km
Flood affected Length of Road	=	0.420 Km ✓
TOTAL COST OF PAVEMENT	Rs	746,173.00
TOTAL PROJECT COST	Rs	746,173.00

Submitted By:
Executive Engineer
RWD (W) Division, Darbhanga-1

Prepared By:
Executive Engineer
RWD (W) Division, Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga *Inspected by Benipur*

Name of Block/Road:- *BMP-13 Kabin chowk village Rampur Kosi Behat Se Adarash Tola*

A. For Road

1. Damage Location Chainage:- *0-400, 500 m*

2. Damage Length :- *420 m*

3. Nature of Damage :- *road crust damaged*

4. Details of Restoration Works

i. Material being used in Restoration works:- *Brick bats*

ii. Equipment's /Tools being used in Restoration works:- *J.C.B / Tractor / Labour*

iii. Procedure taken up in Restoration works:- *Laying of brick bats with light Raining*

iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work Found Satisfactory

Signature of JE/AE/EE

25/03/2022
JE
Shanku
25/3/22
AE

Benipur

Signature

(Name of Inspection)

प्रशासनिक प्रतिवेदन

पथ का नाम :- BMP-13 कबीर चौक विलेज रामपुर कासिम बेहट से आदर्श टोला तक
मरम्मत कार्य (FDR)

पथ की लम्बाई :- 4.250 कि०मी०

प्राक्कलित राशि:- 7.46173 लाख मात्र।

प्रमण्डल का नाम :- ग्रामीण कार्य विभाग, कार्य प्रमण्डल, दरभंगा-1

अंचल का नाम:- ग्रामीण कार्य विभाग, कार्य अंचल, दरभंगा।

योजना शीर्ष :- FDR-2245


योजना वर्ष :- 2020-21

प्रस्तुत प्राक्कलन दरभंगा सदर प्रखंड अन्तर्गत NH BMP-13 कबीर चौक विलेज रामपुर कासिम बेहट से आदर्श टोला तक पथ मरम्मत कार्य के लिए तैयार किया गया है, जो कि वर्ष 2021 में आयी भीषण बाढ़ एवं अतिवृष्टि के कारण उक्त पथ का पथांश कई स्थानों पर क्षतिग्रस्त हो गया था। जिसके कारण यातायात अवरुद्ध हो गई थी। यातायात को पुनः बहाल करने के लिए पथ को अस्थायी रूप से मोटरेबुल (Motorable) किया गया। मोटरेबुल (Motorable) कार्य करने हेतु आवश्यकतानुसार प्राक्कलन में (Brick Bats) ईंट के टुकड़ों से भरकर उसका सम्पीडन किये जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन विभागीय पत्रांक-मु0अ0-4 (मु0) विविध (कार्य)-23-60/2020-1937, पटना दिनांक-07.07.2021 के अनुपालन में तैयार किया गया है।

प्रस्तुत प्राक्कलन वर्तमान अनुसूचित दर के आधार पर तैयार किया गया है। चूंकि यह कार्य विभागीय स्तर पर कराया गया है। प्रस्तुत प्राक्कलन में संवेदक लाभांश का प्रावधान नहीं किया गया है।

अतः यह प्राक्कलन की लोकहित एवं जनहित में तकनीकी अनुमोदन अपेक्षित है।


कमीय अभियंता,
ग्रामीण कार्य विभाग,
प्रशाखा, दरभंगा सदर


सहायक अभियंता
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, दरभंगा सदर


कार्यपालक अभियंता
ग्रामीण कार्य विभाकार्य
कार्य प्र० दरभंगा-1

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- BMP-13 KABIR CHOWK VILLAGE RAMPUR KASIM
BEHAT Se ADARASH TOLA
DISTRICT :- Darbhanga
BLOCK :- Darbhanga Sadar
Actual Length of Road :- 4.250 Km
Flood Affected Length of Road :- 0.420 Km

		Lead in Km	7	+	1
Sr. No.	Description				Amount (In Rs.)
1	Brick bats Total Qty. = 315.00 312.5	@ 2,004.96			631,562.00 6,26,550
2	Add GST @ 12%=	75186			75,787.00
3	Add Labour Cess @ 1%=	6265.50			6,316.00
4	S.F. @10% on material(Brick Bats)=	32250			32,508.00
TOTAL RESTORATION COST OF THE PROJECT IN Rs.					746,173.00

7,40,251.5
say 7,40,251.00

कार्यपालक अभियंता वैनीपुर के जाँच प्रतिवेदन के आधार पर
Technically Sanctioned For Rs. 7,40,251.00 (Rupees seven
lacs forty thousand two hundred fifty one) only

Superintending Engineer
RWD Works Circle, Darbhanga

20.11.21
Junior Engineer
RWD (W) Division, Darbhanga-1

Assistant Engineer
RWD (W) Division, Darbhanga-1

Executive Engineer
RWD (W) Division, Darbhanga-1

Estimate for Temporary Restoration of Flood affected Road

Name of Road:- BMP-13 KABIR CHOWK VILLAGE RAMPUR KASIM
BEHAT Se ADARASH TOLA

BLOCK :- Darbhanga Sadar

District:- Darbhanga

SUB HEAD : BRICK BATS

Laying & Distribution of Brick bats on affected Road portion as per specification to meet the required slope and proper light Ramming from a specified lead as per direction of E/I.

SI No	Chainage		Unit	Nos.	Length (m)	Width (m)	Depth / Thickness (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
	0	400	Cum	1.00	400.00	3.00	$\frac{0.20 + 0.30}{2}$	300.00	2,004.96	6,01,488.00
	400 to 500 m		Cum	1.00	20.00	2.50 m 3.00	0.25	15.00	2,004.96	30,074.0
					420.000			315.000	Total Amt.	6,31,562.00

25062

6,26,550.00

[Signature]
Junior Engineer
RWD (W) Division, Darbhanga-1

[Signature]
Assistant Engineer
RWD (W) Division, Darbhanga-1

[Signature]
Executive Engineer
RWD (W) Division, Darbhanga-1

Verified & found correct

[Signature]
25/3/22
AE

[Signature]

EE