



बिहार सरकार
ग्रामीण कार्य विभाग
Rural Works Department, Govt. of Bihar

155

HEAD-FDR

STATE :- BIHAR

DETAILED PROJECT REPORT

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Jhanjharpur

Estimate for Mortable of the Road from Ganga Ji ka House to
Solling Road **FDR at Block- Jhanjharpur** in Madhubani
District.

TOTAL COST FOR MOTORABLE Rs. ~~3.50615 lac.~~

2.68907 lac

Submitted by:
Executive Engineer
RWD(W) Division, Jhanjharpur

Inspection Report of Flood Damage Work

Name of PIUs :- RWD Works Division, Jhanjharpur

Name of Block :- Jhanjharpur

Name of Road :- Ganga ji ke house to Bolling Road

A. For Road


1. Damage Location Chainage :- 800m 1000m, 1150m
2. Damage Length :- 113m
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:- Bricks etc
 - ii. Equipment's/Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- 113.52 m
 - iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage :-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Materials being used in restoration works:-
 - ii. Equipment's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

C. Requirement Of New CD/ Bridges

- i. Name of Road:-
- ii. Location/ Chainage:-
- iii. Type of CD Work/ Length required:-


Signature of AE/EE


Signature
(Name of Inspection)

तकनीकी प्रतिवेदन

पथ का नाम :- Ganga Ji Ka house to rolling road

प्राक्कलित राशि :- 3.50 615 ecc.

प्रमण्डल का नाम:- झंझारपुर

अंचल का नाम :- दरभंगा


योजना का नाम :- F.D.R-2245

प्रस्तुत प्राक्कलन विभागीय स्तर से कराये गये कार्य के आलोक ~~Ganga Ji Ka~~
~~house to rolling road~~ पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/ Wave Cut के कारण क्षतिग्रस्त हो गया था जिसके कारण आवागमन बाधित हो गया था । फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था ।


यह प्राक्कलन सचिव महोदय, ग्रामीण कार्य विभाग, पटना बिहार के पत्रांक- मु0अ0- 4 (मु0) विविध (कार्य)- 23 - 60/2020- 1937 पटना, दिनांक- 07.07.2021 के आदेश के आलोक में तैयार किया गया है ।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़े/मिट्टी/स्थानीय बालु से भरकर उसका संपीडन किये जाने का प्रावधान करते हुए कार्य संपादित किया जा चुका है ।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनसूचित दर (संवेदक लाभांश छोड़कर) पर तैयार किया गया है । यह कार्य लोकहित एवं जनहित में अत्यावश्यक है । अतः इस प्राक्कलन की स्वीकृति अपेक्षित है ।


कनीय अभियंता


सहायक अभियंता


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, झंझारपुर

Estimate for Motorability of road damaged by flood from Ganga Ji ka House to Solling Road For Year 2021

Length :- 1.136 km

Head :- MMGSY[SC]


SI No.	Item No.	Name of Item	Unit	Quantity As per Appendix - 1	Rate	Amount
1		Providing and filling brick bats in ditches/ damaged embankment including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	147.82 113.52	2004.96	227603.059 296373.19 227603.059 ₹ 2,96,373.19 27312.36 Add 12 % GST ₹ 35,564.78 2276.04 Add 1 % L.C ₹ 2,963.73 11715.26 Add S. Fee (147.82 x 1063.00) x 10 % ₹ 15,713.27 268906.72 Total ₹ 3,50,614.97 268907.00 Say ₹ 3,50,615.00


Junior Engineer
R.W.D, Works Section,
Jhanjharpur


Assistant Engineer
R.W.D, Work sub Div.
Jhanjharpur


Executive Engineer
R.W.D (W) Division,
Jhanjharpur

आर्थिक अभिलेख अगस्त के ऑफ पत्रिका 753 दिनांक- 07-06-2022
ले आधारे पर Technically sanctioned for Rs. 2,68,907.00 (Rupees Two
lacs sixty eight thousand nine hundred seven) only


Superintending Engineer
RWD Work Circle, Darbhanga
Abhinav
09/06/22

Name of Road :- Ganga Ji ka House to Solling Road

ne :- PMGSY

Length :- 1.136 km

Block :- Jhanjharpur

ndix - I

**Measurement for restoration of Embankment and shoulder with Brick Bat
(Measurement In mtr.)**

Chainage	Nos.		Length (In Mtr.)		Bldth (In Mtr.)		Thickness (In Mtr.)			Quantity	
CH. 800M	1	x	33.00	x	3.10	x	3.10	0.40	0.40	av. =	40.92 cum
CH. 1000M	1	x	45.00	x	3.20	x	3.20	0.30	0.30	av. =	43.20 cum
CH. 1150M	1	x	35.00	x	2.80	x	2.80	0.65	0.65	av. =	59.42 cum
Total qty.										=	147.82 cum

113.52 m³
Sum

[Signature]
21/08/21
Junior Engineer
R.W.D, Works Section,
Jhanjharpur

[Signature]
5.11.21
Assistant Engineer
R.W.D, Work sub Div.
Jhanjharpur

[Signature]
20/08/21
Executive Engineer
R.W.D (W) Division,
Jhanjharpur

[Signature]
04/06/22
T.E.

[Signature]
16/12