



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

BIHAR RURAL ROADS PROJECT

Bihar Rural Development Agency (BRRDA)

PLAN HEAD :- F.D.R. 2245

A.A. COPY

YEAR (2021-22)

State :- BIHAR

District :- Darbhanga

Block :- Darbhanga Sadar

Bhalpatti Khraj Tola Se Bhera High School

Actual Length of Road	=	2.500 Km
Flood affected Length of Road	=	0.622 Km
TOTAL COST OF PAVEMENT	Rs	1,046,300.00
TOTAL PROJECT COST	Rs	1,046,300.00

Submitted By:

Executive Engineer

RWD (W) Division, Darbhanga-1

Prepared By:

Executive Engineer

RWD (W) Division, Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga *Inspected by Benipur*

Name of Block/Road:- *Bhalpatti khraj Tala se Bheera High School*

A. For Road

1. Damage Location Chainage:- *0, 65, 300, 900, 1400, 1500*

2. Damage Length :- *622 m*

3. Nature of Damage :- *road crust damaged.*

4. Details of Restoration Works

i. Material being used in Restoration works:- *Brick bats*

ii. Equipment's /Tools being used in Restoration works:- *J.C.B / Tractor / Labour*

iii. Procedure taken up in Restoration works:- *laying of brick bats with light tamping*

iv. Restored Length:- *622 m*

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work found Satisfactory.

Signature of JE/AE/EE

[Signature]

Signature

(Name of Inspection)

[Stamp]
25/03/2022
JE

[Signature]
25/3/22
AE

प्रशासनिक प्रतिवेदन

पथ का नाम :- भलापट्टी कराज टोला से भेडा हाई स्कूल तक मरम्माति कार्य (FDR)

पथ की लम्बाई :- 2.000 कि०मी०

प्राक्कलित राशि:- 10.46300 लाख मात्र।

प्रमण्डल का नाम :- ग्रामीण कार्य विभाग, कार्य प्रमण्डल, दरभंगा-1

अंचल का नाम:- ग्रामीण कार्य विभाग, कार्य अंचल, दरभंगा।

योजना शीर्ष :- FDR-2245


योजना वर्ष :- 2020-21


प्रस्तुत प्राक्कलन दरभंगा सदर प्रखंड अन्तर्गत भलापट्टी कराज टोला से भेडा हाई स्कूल तक पथ मरम्माति कार्य के लिए तैयार किया गया है, जो कि वर्ष 2021 में आयी भीषण बाढ़ एवं अतिवृष्टि के कारण उक्त पथ का पथांश कई स्थानों पर क्षतिग्रस्त हो गया था। जिसके कारण यातायात अवरुद्ध हो गई थी। यातायात को पुनः बहाल करने के लिए पथ को अस्थायी रूप से मोटरेबुल (Motorable) किया गया। मोटरेबुल (Motorable) कार्य करने हेतु आवश्यकतानुसार प्राक्कलन में (Brick Bats) ईंट के टुकड़ों से भरकर उसका सम्पीडन किये जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन विभागीय पत्रांक-मु0अ0-4 (मु0) विविध (कार्य)-23-60/2020-1937, पटना दिनांक-07.07.2021 के अनुपालन में तैयार किया गया है।

प्रस्तुत प्राक्कलन वर्तमान अनुसूचित दर के आधार पर तैयार किया गया है। चूँकि यह कार्य विभागीय स्तर पर कराया गया है। प्रस्तुत प्राक्कलन में संवेदक लाभांश का प्रावधान नहीं किया गया है।

अतः यह प्राक्कलन की लोकहित एवं जनहित में तकनीकी अनुमोदन अपेक्षित है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
प्रशाखा, दरभंगा सदर


सहायक अभियंता
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल, दरभंगा सदर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्र० दरभंगा-1

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- Bhalpatti Khraj Tola Se Bhera High School
 DISTRICT :- Darbhanga
 BLOCK :- Darbhanga Sadar
 Actual Length of Road :- 2.500 Km
 Flood Affected Length of Road :- ~~0.051 Km~~ ~~0.51 Km~~ 0.622 Km

Lead in Km	7	+	1
------------	---	---	---

Sr. No.	Description	Amount (In Rs.)
1	Brick bats Total Qty. = 441.70 @ 2,004.96 437.4	885,590.00 8,76,968.45
2	Add GST @ 12%= 1,05,236.21	106,271.00
3	Add Labour Cess @ 1%= 8769.68	8,856.00
4	S.F. @10% on material(Brick Bats)= 45139.68	45,583.00
TOTAL RESTORATION COST OF THE PROJECT IN Rs.		1,046,300.00

⇒ 10,36,114.02

Rs. = 10,36,114.00

कार्यपालक अभियंता वनीपुर के जांच प्रतिवेदन के आधार पर
 Technically sanctioned for Rs. 10,36,114.00 (Rupees
 Ten lacs thirty six thousand one hundred fourteen) only

Superintending Engineer
 RWD Works Circle, Darbhanga

Assistant Engineer

Executive Engineer

RWD (W) Division, Darbhanga-1

RWD (W) Division, Darbhanga-1

RWD (W) Division, Darbhanga-1

SI No	Chainage		Unit	Nos.	Length (m)	Width (m)	Depth / Thickness (m)	Quantity	Rate (In Rs.)	Amount (In Rs.)
	From	To								
	1400	to 1500	Cum	1.00	12.00	3.75	0.25	14.06	2,004.96	28,190.0
					51.350 622			441.700	Total Amt.	8,85,590.00
437.4 = 8,76,968.45										

[Signature]
Junior Engineer
RWD (W) Division, Darbhanga-1

[Signature]
Assistant Engineer
RWD (W) Division, Darbhanga-1

[Signature]
Executive Engineer
RWD (W) Division, Darbhanga-1

Verified & found correct

[Signature]
25/3/22
JE

[Signature]
25/3/22
AE

[Signature]
EF