

SCHEDULE OF WORKS

Name of Road : Chainpur To Chakwa

Length of Road : 3.840 KM

L / TR No. :

Package No. : BR-23R-177

District : Muzaffarpur

Block : Motipur

Sl.No.	Description of Work	No. or Qty.	Unit	Estimated Rate	
				Figure	Words
33	Seal Coat Providing and laying seal coat sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type A, Type B and Type C as per Technical Specification Clause 510 of Specification of Rural Roads. Case - II :	122.300000	Sqm	34.430900	Thirty Four Rupees and Forty Three Paises
34	Protection Work: Earthwork in excavation of foundation of structures as per drawing and technical specifications including setting out, construction of shoring and bracing, removal of stumps and other deleterious material, dressing of sides and bottom and backfilling with	71.310000	Cum	186.819700	One Hundred Eighty Six Rupees and Eighty One Paises
35	Providing and laying pitching on slopes laid over prepared filter media as per drawing and technical specifications Clause 1302 (I) Stone / Boulder	24.790000	Cum	2799.800800	Two Thousand Seven Hundred Ninety Nine Rupees and Eighty Paises
36	Providing concrete for plain/ reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202,1203. V) RCC Grade M 25	4.120000	Cum	7041.790700	Seven Thousand Forty One Rupees and Seventy Nine Paises
37	Supplying, fitting, and placing HYSD bar reinforcement in foundation complete as per drawing and technical specifications Clauses 1000, and 1202	0.310000	MT	44904.216200	Forty Four Thousand Nine Hundred Four Rupees and Twenty One Paises
38	Plain / reinforced cement concrete in open foundation complete as per drawing and technical specifications clause 802, 803, 1202, 1203 (I) PCC Grade M10	2.980000	Cum	5970.534200	Five Thousand Nine Hundred Seventy Rupees and Fifty Three Paises
39	Brick masonry work in cement mortar in substructure complete excepting pointing and plastering, as per drawing and technical specification Clauses 602, 603, 604, 1202 & 1204 (II) In 1:4 Cement Mortar	19.950000	Cum	5752.919600	Five Thousand Seven Hundred Fifty Two Rupees and Ninety One Paises
40	Maintainance for 1st year			49727.955884	Forty Nine Thousand Seven Hundred Twenty Seven Rupees and Ninety Five Paises
	Maintainance for 2nd year			85813.767094	Eighty Five Thousand Eight Hundred Thirteen Rupees and Seventy Six Paises
	Maintainance for 3rd year			239225.601718	Two Hundred Thirty Nine Thousand Two Hundred Twenty Five Rupees and Sixty Paises
	Maintainance for 4th year			389065.917147	Three Hundred Eighty Nine Thousand Sixty Five Rupees and Ninety One Paises
	Maintainance for 5th year			564482.890082	Five Hundred Sixty Four Thousand Four Hundred Eighty Two Rupees and Eighty Nine Paises