



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR FDR



Name of the Road :-		Chochahi PWD Road to Chochahi Road	
DISTRICT		Muzaffarpur	
DIVISION		Muzaffarpur West	
BLOCK		Paroo	
TOTAL LENGTH OF ROAD	:	2.340	KM
CONSTRUCTION COST	:	7.648 8.02	Lac

Submitted By :-
Executive Engineer
RWD Work Division Muzaffarpur West

7.691

DPR-2

61

प्रतिवेदन

कार्य का नाम:- chochahi P.W.P Road to chochahi

.....पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड- पारा
वित्तीय वर्ष - 2021-22
प्राक्कलित राशि - Rs. 7.691 (लाख)

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 7.691 (लाख) है, chochahi P.W.D
Road to chochahi, प्रखण्ड- पारा में यातायात बहाली हेतु आपातकालिन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 4589 दिनांक 13.11.2021 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
घटनोत्तर स्वीकृति अपेक्षित है। पथ की प्रकृति 1715 में दर्ज है। प्रति मीटर रु 1000

15.11.21
कनीय अभियंता

15/11/2021
सहायक अभियंता

15/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल:-

Inspection Report for Flood Damage Work

Date: 02.12.2021

1 Name of PIUs :- E.E. R.W.D, Mauza/Alpur West.

2 Name of Block/Road :- Paroo/chechahi P.W.D Road to chechahi

(A) For Road:

1. Damage Location/Chainage :- 250M.

2. Damage Length :- 54M.

3. Nature of Damage :- Road Cully by Heavy & Heavy rain

4. Details of Restoration Works :-

(i) Material being used in Restoration works:- Briars Bole - 366.52M³, Sand - 22.95M³

(ii) Equipment's/Tools being used in Restoration works:- Road roller

(iii) Procedure taken up in Restoration works:

(iv) Restored Length :- 54M.

(B) For Bridge:

1. Damage Location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works :-

(i) Material being used in Restoration works:-

(ii) Equipment's/Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration works:-

(iv) Restored Length :-

The work found Satisfactory

N.A.


work found satisfactory



02.12.21

Signature

(Name of Inspection)


Signature of JE/AE/EE

GENERAL ABSTRACT

Name of Road Chochahi PWD Road to Chochahi Road

District Muzaffarpur

Block Paroo

Division Muzaffarpur West

Length of Road (in Km) 2.340 Km

SI. No.	DESCRIPTION	AMOUNT (LAKHS)
1	Earthwork	0.000
2	Brick Bats	7.561 7.567 7.893
3	Sand Filling	0.130 0.127
4	Sand bag	0.000
5	H.P.	0.000
	SUB TOTAL	7.698 8.020
	GRAND SUB TOTAL	7.698 8.020

7.691 Lakhs

33-11-21
JE
RWD

33/11/2021
AE
RWD

33/11/21
EE
RWD

As Per S.E. RWD (W) Circle Muz.
Letter No 1179 Dated 01/10/2021
Estimate has been verified by inspecting
E. E. RWD. (W) Division

*Technically sanctioned for Rs. 7.691 lakhs
(Rs. Seven lakh Sixty nine thousand one
hundred) only (provisionally)*

28/12/21
Superintending Engineer
Rural Works Department
Work Circle, Muzaffarpur

27/12/21