



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MANIHARI AMDABAD PWD ROAD TO GOWAGACHHI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1150	
DISTRICT	KATHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.150	KM
TOTAL COST OF F.D.R. PART - A	Rs. 3.513	Lacs
ADD G.S.T. @ 12%	Rs. 0.422	Lacs
ADD Labour Cess @ 1%	Rs. 0.035	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.081	Lacs
TOTAL COST OF RESTORATION WORK IN Rs.	Rs. 4.051	Lacs
SUBMITTED BY The Executive Engineer, Works Division, Manihari		


प्रतिवेदन


पथ का नाम	:- Manihari Amdabad PWD Road To Gowagachhi
पथ की लम्बाई	:- 1.150 KM
प्राक्कलित राशि	:- 4.051 Lac
वित्तीय वर्ष	:- 2021-22 / FDR-2021
प्रखंड	:- Amdabad


प्रस्तुत प्राक्कलन मो0 4.051 लाख (चार लाख पाँच हजार एक सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के **Manihari Amdabad PWD Road To Gowagachhi** पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में बने हुए बड़े-बड़े गढ़ों में मिट्टी भरने का प्रावधान किया गया है तथा कटाव स्थान के दोनो तरफ Sand Bag डालकर पथ को कटाव से बचाया गया है। पथ में पूर्व से निर्मित GSB बहे हुए स्थान पर GSB का भी प्रावधान किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / Manihari Amdabad PWD
Road To Growagacchi

A for Road

1. Damage location : 0.47
2. Damage Length : 0.09 Km.
3. Nature of Damage : Road cross Cut
4. Details of Restoration :
 - i. Material being used in Restoration Sand bag, E/w, G.S.B.
 - ii. Equipment/Tools being used in Restoration Works : Tractor, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.09 Km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE Engineer

Executive

Rural Works Department
Rural Works Division, Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MANIHARI AMDABAD PWD ROAD TO GOWAGACHHI
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AMDABAD
LENGTH OF ROAD (IN KM) 1.150

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	1.949
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	0.292
5	G.S.B.	1.272
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		3.513
Add G.S.T. @ 12%		0.422
Add Labour Cess @ 1%		0.035
Add Seigniorage Fee @ 10%		0.081
Total Cost of Restoration Work =		4.051

J.E.
RWD
26/11/17

A.E.
RWD
26/11/17

E.E.
RWD
26/11/17

Technically Sanction for Rs. 4.051 Lac (Rs. Four Thousand One Hundred and Fifty One Only)

Superintendent Engineer
Rural Works Department
Works Circle, Purnea