



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 TO BELGACHHI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 800	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.800	KM
TOTAL COST OF F.D.R. PART - A	Rs. 10.069 5.637	Laes
ADD G.S.T @ 12%	Rs. 1.208 0.676	Laes
ADD Labour Cess @ 1%	Rs. 0.101 0.054	Laes
ADD Seigniorage Fee @ 10%	Rs. 0.393 0.229	Laes
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 11.771 6.596	Laes

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम :- T01 To Belgachhi
पथ की लम्बाई :- 0.800 KM
प्राक्कलित राशि :- ~~11.771~~ ^{6.596} Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad


प्रस्तुत प्राक्कलन मो0 ~~11.771~~ ^{6.596} लाख (ग्यारह लाख सत्तर हजार एक सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के T01 To Belgachhi पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में महानन्दा नदी के किनारे बम्बू पाईलिंग, रनर के पश्चात Sand Bag डाला गया है। पथ एवं Sand bag के बीच मिट्टी का भी प्रावधान कर महानन्दा नदी के कटाव से बचाया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियों द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari
2. Name of Block/Road Amdabad / T-01 To Belgachhi

A for Road

1. Damage location : 0.75
2. Damage Length : 0.06 km
3. Nature of Damage : Road wash out due mahanda River Bank.
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo, Earthwork & Sand bags
 - ii. Equipment/Tools being used in Restoration Works : Traector, JCB
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.06 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/Engineer

26/11/21
Executive Engineer
Rural Works Department
Manihari Division, Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD . T01 TO BELGACHHI


DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.800

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	5.683 2.665
2	HUME PIPE	0.000
3	BRICK BAT	0.000
4	SAND BAGS	2.377 2.512
5	G S B	0.000
5	BAMBOO WORK	0.594
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		10.063 5.637
Add G.S.T. @ 12%		1.208 0.676
Add Labour Cess @ 1%		0.101 0.054
Add Seigniorage Fee @ 10%		0.101 0.229
Total Cost of Restoration Work =		11.471 6.596


J.E.
RWD



A.E.
RWD


BEL
RWD

Technically Sanction for Rs. 6.596 Lac (Rs.)

Crete Six Lac fifty nine

Thousand Six Hundred


Superintendent Engineer
Rural Works Department
Works Circle, Purnea